

DEPARTMENT OF TRANSPORTATION

P.O. BOX 23660

OAKLAND, CA 94623-0660



*Flex your power!
Be energy efficient.*

March 27, 2007

Mr. Joe Lo Coco, P.E.
Principal Civil Engineer
555 County Center, 5th Floor
Redwood City, CA 94063-1665

Re: County of San Mateo, Bridge Preventive Maintenance Program (BPMP) Plan

Dear Mr. Lo Coco:

Your February 27, 2007 letter submitted the County's 2007 Bridge Preventive Maintenance Program plan and requested our reconsideration of federal fund reimbursement for the development cost.

We have reviewed the County's BPMP plan and find all work proposed to be eligible for reimbursement under the BPMP. The plan is approved and the County may begin implementation of the plan according to Caltrans "Bridge Preventive Maintenance Program Guidelines using Local Funded Advance Construction (AC), after the AC has been programmed in the FSTIP. Please refer to Chapter 2 of the Local Assistance Program Guidelines for information on AC.

Regarding reimbursement for the BPMP plan developmental cost, it is not federally reimbursable because the work was done prior to "Authorization to Proceed" (E-76) and for the reasons cited in our December 21, 2006 letter.

Should you have any questions, please contact me at (510) 622-5929.

Sincerely,

A handwritten signature in black ink that reads "Roland Nimis".

Roland Nimis, P.E.
Local Assistance Area Engineer

Federal Fiscal Year 2006/2007 Bridge Preventive Maintenance Program

Priority (Low Number is Top Priority)	County Location	Implementing Agency	Bridge Number (from Inspection Report)	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Total Particip. Cost	Unit Cost (\$/ft ²)	Federal Share	Running Fed Summary	Local Share	Running Local Summary
1		SMC	Develop 2007/2008 BPMP							Develop 2007/2008 BPMP		\$50,000.00		\$ 44,265.00	\$44,265.00	\$ 5,735.00	\$5,735.00
2		SMC	35C-16	4	Alpine Rd.	San Francisquito Ck.	0.3 Mi N of SH 250	89.4		Apply methacrylate overlay deck treatment. Remove and replace the joint seals. Remove and replace scour countermeasures	4600	\$ 101,500.00	\$ 14.11	\$ 89,857.95	\$134,122.95	\$ 11,642.05	\$17,377.05
3		SMC	35C-117	33	Stage Rd.	Pescadero Ck.	South of North St	91.6		Repair damaged pier.	4400	\$ 51,000.00	\$ 7.40	\$ 45,150.30	\$179,273.25	\$ 5,849.70	\$23,226.75
4		SMC	35C-116	21	Madera Lane	El Corte Madera	0.1 Mi N of SH 84	41.9*	SD	Remove AC overlay and investigate PCC condition. Apply methacrylate deck treatment as required. Replace deficient barrier system. Replace or repair exterior girders where deteriorating. Repair underside of PCC deck where spalling has occurred. Evaluate pier for structural integrity.	1400	\$ 329,000.00	\$ 87.43	\$ 291,283.70	\$470,536.95	\$ 37,736.30	\$60,963.05

*While the sufficiency rating of the bridge is under 50, it is included in the BPMP because of low ADT