TRINITY COUNTY DEPARTMENT OF TRANSPORTATION
Bridge Preventive Maintenance Program PM00019

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft^2)	Total Particip. Cost	Unit Cost ($/$ft^2$)	Federal Share	Running Fed Summary	Local Share	Running Local Share
1					***DEVELOP NEXT YEAR'S (2012/2013) BPMP***							***2,500***		***2,213***	***2,213***	***287***	***287***
2	HAWKINS BAR	TCDOT	05C119		DENNY ROAD	TRINITY RIVER	0.2 MI E JCT SR 299	79.1		METHACRYLATE	16,932	152,388	9.00	134,909	137,122	17,479	17,766
3	JCT CITY	TCDOT	05C070		DUTCH CREEK RD	TRINITY RIVER	0.3 MI S OF SR 299	86.8		METHACRYLATE	11,228	101,052	9.00	89,461	226,584	11,591	29,356
4	RUTH	TCDOT	05C223		RUTH-ZENIA ROAD	VAN DUZEN RIVER	0.1 MI SE VAN DUZEN ROAD	95.0		METHACRYLATE	3,640	98,280	27.00	87,007	313,591	11,273	40,629
5	KETTENPOM	TCDOT	05C224		HOAGLIN ROAD	KETTENPOM CREEK	2.9 MI E JCT W/ CR503	93.9		METHACRYLATE	1,130	30,510	27.00	27,011	340,601	3,499	44,129
6	HAYFORK	TCDOT	05C133		BIG CREEK ROAD	BIG CREEK	4.5 MI NORTH OF SR 3	91.3		RSP, SCOUR MITIGATION	2,564	75,000	29	66,398	406,999	8,603	52,731
8	HYAMPOM	TCDOT	05C037		ST. JOHN LOOP ROAD	BUTTER CREEK	7.0 MI S HYAMPOM RD	71.8		RSP, SCOUR MITIGATION	1,220	55,000	45	48,692	455,690	6,309	59,040
9	WILDWOOD	TCDOT	05C100		WILDWOOD ROAD	CARR CREEK	0.1 MI E OF SR 3	85.8		RSP, SCOUR MITIGATION	1,547	65,000	42	57,545	513,235	7,456	66,495
10	TRINITY CENTER	TCDOT	05C185		EAST SIDE ROAD	TRINITY RIVER	0.1 MI E OF STATE RTE 3	86.7		TYPE A JOINT SEAL	10,162	53,340	5.25	47,222	560,457	6,118	72,613
12	HAYFORK	TCDOT	05C105		SUMMIT CREEK ROAD	CARR CREEK	0.1 MI S OF SR 3	91.1		TYPE A JOINT SEAL	1992	15,900	7.98	14,076	574,533	1,824	74,437
13	WEAVERVILLE	TCDOT	05C153		MILL STREET	MIDDLE WEAVER CREEK	0.5 MI S OF SR 299	89.4		TYPE A JOINT SEAL	1953	15,900	8.14	14,076	588,609	1,824	76,261
14	COFFEE CREEK	TCDOT	05C205		COFFEE CREEK ROAD	E. F. COFFEE CREEK	7.35 MI W OF SR 3	93.3		TYPE B JOINT SEAL	3239	15,900	4.91	14,076	602,686	1,824	78,084
15	RUTH	TCDOT	05C223		RUTH-ZENIA ROAD	VAN DUZEN RIVER	0.1 MI SE VAN DUZEN ROAD	95.3		TYPE B JOINT SEAL	3683	15,900	4.32	14,076	616,762	1,824	79,908

Project Prioritization

Local Agencies must develop objective procedures to prioritize their preventive maintenance projects. These procedures must be included in the project files for review in future audits. High priority projects should include the repair of scour countermeasure, embankment erosion control and the repair, restoration, and strengthening of structural elements.

Priority should be given to bridges that are not eligible for rehabilitation or replacement under the Federal Highway Bridge Program. The intent of the program is to keep these bridges in structurally good condition to maximize their service life and to conserve limited funds available for bridges that do require major rehabilitation or replacement. (Bridges eligible for rehabilitation or replacement are rated SD or FO and have a sufficiency rating of 80 or less.)

Deadlines:

Local agency transmits the BPMP with cover letter certifying compliance with these program guidelines. The electronic copy (any spreadsheet format) should be included on a CD with the paper transmittal letter. The DLAE's must receive the BPMPs by September 30th for funds to be obligated in the next FFY year, and January 30th of each year for adjustments. No time extensions will be granted.

Accountability:

Local Agencies are responsible for understanding and complying with the program requirements defined in the "Bridge Preventive Maintenance Program Guidelines For Local Agencies."

PREPARED BY RANDY CESSNA 9-25-2012

TRINITY COUNTY DEPARTMENT OF TRANSPORTATION
Bridge Preventive Maintenance Program PM00019

	County Location	Bridge number from Inspection Report	Facility Carried	Feature Intersected	Location	Work Description	CON	PE/ENV	CONT.	CE	Total Particip. Cost	FED FISCAL YEAR FOR PE	FED FISCAL YEAR FOR CON
1			***DEVELOP NEXT YEAR'S (2012/2013) BPMP***								***2,500***		
2	HAWKINS BAR	05C0119	DENNY ROAD	TRINITY RIVER	0.2 MI E JCT SR 299	METHACRYLATE	101,592	25,398	10,159	15,239	152,388	2011 / 2012	2012 / 2013
3	JCT CITY	05C0070	DUTCH CREEK RD	TRINITY RIVER	0.3 MI S OF SR 299	METHACRYLATE	67,368	16,842	6,737	10,105	101,052	2011 / 2012	2012 / 2013
4	RUTH	05C0223	RUTH-ZENIA ROAD	VAN DUZEN RIVER	0.1 MI SE VAN DUZEN ROAD	METHACRYLATE	65,520	16,380	6,552	9,828	98,280	2011 / 2012	2012 / 2013
5	KETTENPOM	05C0224	HOAGLIN ROAD	KETTENPOM CREEK	2.9 MI E JCT W/ CR503	METHACRYLATE	20,340	5,085	2,034	3,051	30,510	2011 / 2012	2012 / 2013
												63,705	318,525
6	HAYFORK	05C0133	BIG CREEK ROAD	BIG CREEK	4.5 MI NORTH OF SR 3	RSP, SCOUR MITIGATION	50,000	12,500	5,000	7,500	75,000	2012 / 2013	2013 / 2014
8	HYAMPOM	05C037	ST. JOHN LOOP ROAD	BUTTER CREEK	7.0 MI S HYAMPOM RD	RSP, SCOUR MITIGATION	36,667	9,167	3667	5500	55000	2012 / 2013	2013 / 2014
9	WILDWOOD	05C100	WILDWOOD ROAD	CARR CREEK	0.1 MI E OF SR 3	RSP, SCOUR MITIGATION	43333	10,833	4333	6500	65000	2012 / 2013	2013 / 2014
												32,500	162,500
10	TRINITY CENTER	05C0185	EAST SIDE ROAD	TRINITY RIVER	0.1 MI E OF STATE RTE 3	TYPE A JOINT SEAL	35,560	8,890	3,556	5,334	53,340	2013 / 2014	2014 / 2015
12	HAYFORK	05C0105	SUMMIT CREEK ROAD	CARR CREEK	0.1 MI S OF SR 3	TYPE A JOINT SEAL	10,600	2,650	1,060	1,590	15,900	2013 / 2014	2014 / 2015
13	WEAVERVILLE	05C0153	MILL STREET	MIDDLE WEAVER CREEK	0.5 MI S OF SR 299	TYPE A JOINT SEAL	10,600	2,650	1,060	1,590	15,900	2013 / 2014	2014 / 2015
14	COFFEE CREEK	05C0205	COFFEE CREEK ROAD	E. F. COFFEE CREEK	7.35 MI W OF SR 3	TYPE B JOINT SEAL	10,600	2,650	1,060	1,590	15,900	2013 / 2014	2014 / 2015
15	RUTH	05C0223	RUTH-ZENIA ROAD	VAN DUZEN RIVER	0.1 MI SE VAN DUZEN ROAD	TYPE B JOINT SEAL	10,600	2,650	1,060	1,590	15,900	2013 / 2014	2014 / 2015
												19,490	97,450

PREPARED BY RANDY CESSNA 9-25-2012