

**Bridge Preventive Maintenance Program
South San Francisco - BPMP-5177(026)**

PM00049

| Bridge # from Insp. Report | Local Agency Bridge ID | Facility Carried | Feature Intersected | Deck Area SF | Sufficiency Rating | Location | Work Description | Deck Area SF | Total Participation Cost | Unit Cost (\$/SF) | Federal share | Running | | |
|----------------------------------|------------------------------|-------------------|-----------------------|-----------------|-----------------------|--------------------------------|------------------------------|-----------------|-----------------------------|----------------------|------------------|-------------|-----------------|---------------|
| | | | | | | | | | | | | Fed Summ | Local Share | Local Summ |
| 35C-0032 | | Dunman Street OC | Hickey Blvd | 1,500 | 95 | 0.9 mi S/W Junipero Serra Blvd | Repair Jt Seal | 3369.4 | \$4,600 | \$1.37 | \$4,072 | | \$528 | |
| 35C-0046 | | N. Access Road. | San Bruno Channel | 4,280 | 80.3 | 0.1 mi E/O S. Airport Blvd | Treat deck with methacrylate | 7372.8 | \$18,650 | \$2.53 | \$16,511 | | \$2,139 | |
| 35C-0047 | | N. Access Road. | San Bruno Channel (E) | 4,280 | 84.6 | 0.2 mi E/O S. Airport Blvd | Treat deck with methacrylate | 5504 | \$14,120 | \$2.57 | \$12,500 | | \$1,620 | |
| 35C-0048 | | San Mateo Avenue | Colmma Creek | 2,666 | 90.8 | 0.2 mi E/O Linden Avenue | Treat deck with methacrylate | 3680 | \$9,916 | \$2.69 | \$8,779 | | \$1,137 | |
| 35C-0079 | | Chestnut Avenue | Colma Canal | 6,705 | 97.2 | 0.1 mi S of Commercial | Treat deck with methacrylate | 3025.8 | \$9,450 | \$3.12 | \$8,366 | | \$1,084 | |
| 35C-0101 | | Utah Ave | Colma Creek | 4,867 | 93.1 | 0.25 mi E/O S. Airport Blvd | Treat deck with methacrylate | 9913.6 | \$23,900 | \$2.41 | \$21,159 | | \$2,741 | |
| 35C-0173 | | Oyster Point Blvd | UPRR | 38,476 | 94.5 | 0.2 mi W of Gateway | Treat deck / Patch Barrier | 31950.2 | \$185,408 | \$5.80 | \$164,142 | | \$21,266 | |
| | | | | | | | | 64815.8 | \$266,044 | \$4.10 | \$235,529 | 0 | \$30,515 | 0 |
| Construction | | | | | | | | CONST | \$266,044 | | \$235,529 | | \$30,515 | |
| Preliminary Engineering (25%) | | | | | | | | PE | \$66,511 | | \$58,882 | | \$7,629 | |
| R/W | | | | | | | | R/W | N/A | | | | | |
| Construction Engineering (15%) | | | | | | | | CE | \$39,907 | | \$35,329 | | \$4,577 | |
| TOTAL | | | | | | | | | \$372,462 | | \$329,740 | | \$42,721 | |
| | | | | | | | | | | | (State) | | (Local) | |