

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

April 24, 2002

01-DN-197-9.6
01-264104

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in DEL NORTE COUNTY ON ROUTE 197 1.6 KM SOUTH OF THE JUNCTION WITH ROUTE 101.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on May 8, 2002.

This addendum is being issued to revise the Notice to Contractors and Special Provisions.

In the Special Provisions, Section 8-1.05, "STATE-FURNISHED MATERIALS," is added as attached.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the following paragraph is added at the end of the section:

"Attention is directed to the Informational Handout provided for this project, concerning work to construct fish habitat, willow poles and brush layering. Construction of the fish habitat, willow poles and brush layering which will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications."

In the Special Provisions, Section 10-1.031, "TEMPORARY WORK PLATFORM," is added as attached.

In the Special Provisions, Section 10-1.15, "EXISTING HIGHWAY FACILITIES," the subsection, "RESET MARKER," is replaced with "REMOVE MARKER," as follows:

"REMOVE MARKER

Existing markers, at those locations shown on the plans to be removed, shall be removed and disposed of."

In the Special Provisions, Section 10-1.15, "EXISTING HIGHWAY FACILITIES," subsection, "COLD PLANE ASPHALT CONCRETE PAVEMENT," the ninth paragraph is revised as follows:

"The material planed from the roadway surface, including material deposited in existing gutters or on the adjacent traveled way, shall remain the property of the State and shall be hauled to kp 10.5 on State Route 197, and stockpiled off the shoulder adjacent to the south bound lane as directed by the Engineer. Removal operations of cold planed material shall be concurrent with planing operations and follow within 15 m of the planer, unless otherwise directed by the Engineer."

01-DN-197-9.6
01-264104

In the Special Provisions, Section 10-1.15, "EXISTING HIGHWAY FACILITIES," subsection, "COLD PLANE ASPHALT CONCRETE PAVEMENT," the eleventh paragraph is revised as follows:

"The contract price paid per square meter for cold plane asphalt concrete pavement shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cold planing asphalt concrete surfacing and for hauling and stockpiling the planed material, including furnishing the asphalt concrete for and constructing, maintaining, removing, and disposing of temporary asphalt concrete tapers, as specified in the Standard Specifications and these special provisions and as directed by the Engineer."

In the Special Provisions, Section 10-1.24, "PERMEABLE MATERIAL," in the first paragraph, the first sentence is revised as follows:

"Permeable material shall conform to the provisions in Section 68-1, "Underdrains," of the Standard Specifications, and these special provisions."

In the Special Provisions, Section 10-1.24, "PERMEABLE MATERIAL," the fourth through the last paragraphs are deleted.

In the Special Provisions, Section 10-1.25, "GEOMEMBRANE (WATER BARRIER)," in the first paragraph, the third sentence is deleted.

In the Special Provisions, Section 10-1.25, "GEOMEMBRANE (WATER BARRIER)," subsection "MATERIALS," the fourth sentence of the first paragraph is revised as follows:

"The geomembrane shall be flexible enough to bend and to conform to subgrade irregularities by its own weight, in ambient job-site air temperatures, without any overburden placed on it, and without additional heating and bending."

In the Special Provisions, Section 10-1.25, "GEOMEMBRANE (WATER BARRIER)," subsection "INSTALLATION," the second paragraph under "Damage" which reads as follows is deleted.

"Geomembrane shall be removed and disposed of at the completion of construction."

In the Special Provisions, Section 10-1.25, "GEOMEMBRANE (WATER BARRIER)," the subsections "MEASUREMENT" and "PAYMENT," are deleted.

In the Special Provisions, Section 10-1.26, "FISH HABITAT" and Section 10-1.27, "BRUSH LAYERING AND WILLOW POLES," are deleted.

In the Special Provisions, Section 10-1.281, "MARKERS AND DELINEATORS," is added as attached.

Addendum No. 1
Page 3
April 24, 2002

01-DN-197-9.6
01-264104

In the Special Provisions, Section 10-1.30, "PAVEMENT MARKERS," the following paragraph is added at the end of the section:

"At the option of the Contractor, permanent striping tape as specified in "Prequalified and Tested Signing and Delineation Materials" of these special provisions, may be placed instead of the thermoplastic traffic stripes and pavement markings specified herein, except that 3M, "Stamark" Series A320 Bisymmetric Grade, manufactured by the 3M Company, shall not be used. Pavement tape, if used, shall be installed in conformance with the manufacturer's specifications. If pavement tape is placed instead of thermoplastic traffic stripes and pavement markings, the pavement tape will be measured and paid for by the meter as thermoplastic traffic stripe and by the square meter as thermoplastic pavement marking."

To Proposal and Contract book holders:

Attached is a copy of the Material Information handout regarding fish habitat, willow poles and brush layering.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

8-1.05 STATE-FURNISHED MATERIALS

Attention is directed to Section 6-1.02, "State-Furnished Materials," of the Standard Specifications and these special provisions.

The following materials will be furnished to the Contractor:

A. Permeable material

State-furnished permeable material will be available to the Contractor at kp 10.5 on State Route 197.

10-1.031 TEMPORARY WORK PLATFORM

Temporary work platform shall conform to the details shown on the plans and these special provisions.

Temporary work platform shall be constructed to facilitate construction, and shall be removed and disposed of when no longer needed, at the locations shown on the plans.

Materials for temporary work platform shall consist of State-furnished permeable material, Class 3 permeable material and geomembrane.

Class 3 permeable material shall conform to the provisions in "Permeable Material" of these special provisions.

Geomembrane shall conform to the provisions in "Geomembrane (Water Barrier)" of these special provisions.

Dewatering shall be done in conjunction with placement of permeable material and geomembrane so as not to trap any fish. A fine mesh screen shall be placed at the inlet of any pumping devices used.

Removed temporary work platform materials shall become the property of the Contractor and shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The contract lump sum price paid for temporary work platform shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in temporary work platform, including hauling and placing State-furnished permeable material, furnishing and placing Class 3 permeable material, furnishing and placing geomembrane, removing the work platform, dewatering and for providing inlet screens, and removing and disposing of all materials when no longer needed, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.281 MARKERS AND DELINEATORS

Markers shall conform to the provisions in Section 82, "Markers and Delineators," of the Standard Specifications and these special provisions.

Retroreflective sheeting for metal target plates shall be the retroreflective sheeting designated for channelizers, markers, and delineators conforming to the requirements in ASTM Designation: D 4956-95 and in conformance with the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Culvert marker shall conform to the details shown on the plans.

The contract unit price paid for marker (culvert) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing marker (culvert), complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.