

INDEX OF PLANS

SHEET No.	DESCRIPTION
1	TITLE AND LOCATION MAP
2-3	TYPICAL CROSS SECTIONS
4-10	CONSTRUCTION DETAILS
11-12	CONSTRUCTION AREA SIGNS
13-17	DETOUR PLANS
18-19	PAVEMENT DELINEATION DETAILS
20	PAVEMENT DELINEATION QUANTITIES
21	SUMMARY OF QUANTITIES
22-23	MODIFY SIGNAL
24-26	MODIFY TRAFFIC MONITORING STATION (COUNT)
27	ELECTRICAL QUANTITIES
28-48	REVISED STANDARD PLANS


THE STANDARD PLANS LIST APPLICABLE TO THIS CONTRACT IS INCLUDED IN THE NOTICE TO BIDDERS AND SPECIAL PROVISIONS BOOK.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
PROJECT PLANS FOR CONSTRUCTION ON
STATE HIGHWAY
IN SHASTA COUNTY IN AND NEAR REDDING
ON ROUTE 5 FROM HILLTOP DRIVE
OVERCROSSING TO CHURN CREEK BRIDGE
AND ON ROUTE 273 FROM 0.1 MILE SOUTH
OF CATERPILLAR ROAD TO ROUTE 5

TO BE SUPPLEMENTED BY STANDARD PLANS DATED MAY 2010

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	1	48

LOCATION MAP



PROJECT MANAGER
LANCE BROWN
 DESIGN ENGINEER
LANCE BROWN

PROJECT ENGINEER DATE 01-08-15
 REGISTERED CIVIL ENGINEER
January 8, 2015
 PLANS APPROVAL DATE



THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

CONTRACT No.	02-0H0004
PROJECT ID	0214000152

THE CONTRACTOR SHALL POSSESS THE CLASS (OR CLASSES) OF LICENSE AS SPECIFIED IN THE "NOTICE TO BIDDERS."

NO SCALE

01-05-14 DATE PLOTTED => 09-JAN-2015 TIME PLOTTED => 14:26

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	2	48

01-08-15
 REGISTERED CIVIL ENGINEER DATE
 01-08-15
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTES:

- DIMENSIONS OF THE PAVEMENT STRUCTURES (STRUCTURAL SECTIONS) ARE SUBJECT TO TOLERANCES SPECIFIED IN THE STANDARD SPECIFICATIONS.
- EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.
- FOR ACCURATE RIGHT OF WAY DATA, CONTACT RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.
- SUPERELEVATIONS AS SHOWN OR AS DIRECTED BY THE ENGINEER.
- SEE CONSTRUCTION DETAILS FOR RAMP PAVING LIMITS AND RAMPS TO BE PAVED.
- EXACT LOCATIONS AND TYPES OF HMA DIKES AND GUARDRAIL ARE SHOWN ON THE SUMMARY OF QUANTITIES SHEET.

ABBREVIATIONS:

- RHMA-0 RUBBERIZED HOT MIX ASPHALT-OPEN GRADED (OPEN GRADED FRICTION COURSE)
 RAC-0 RUBBERIZED ASPHALT CONCRETE (TYPE 0)

LEGEND:

COLD PLANE ASPHALT CONCRETE PAVEMENT (0.08' ± 0.02')

PAVEMENT CLIMATE REGION
 INLAND VALLEY

REVISIONS: 1
 REVISIONS: 2
 REVISIONS: 3
 REVISIONS: 4
 REVISIONS: 5
 REVISIONS: 6
 REVISIONS: 7
 REVISIONS: 8
 REVISIONS: 9
 REVISIONS: 10
 REVISIONS: 11
 REVISIONS: 12
 REVISIONS: 13
 REVISIONS: 14
 REVISIONS: 15
 REVISIONS: 16
 REVISIONS: 17
 REVISIONS: 18
 REVISIONS: 19
 REVISIONS: 20
 REVISIONS: 21
 REVISIONS: 22
 REVISIONS: 23
 REVISIONS: 24
 REVISIONS: 25
 REVISIONS: 26
 REVISIONS: 27
 REVISIONS: 28
 REVISIONS: 29
 REVISIONS: 30
 REVISIONS: 31
 REVISIONS: 32
 REVISIONS: 33
 REVISIONS: 34
 REVISIONS: 35
 REVISIONS: 36
 REVISIONS: 37
 REVISIONS: 38
 REVISIONS: 39
 REVISIONS: 40
 REVISIONS: 41
 REVISIONS: 42
 REVISIONS: 43
 REVISIONS: 44
 REVISIONS: 45
 REVISIONS: 46
 REVISIONS: 47
 REVISIONS: 48
 REVISIONS: 49
 REVISIONS: 50
 REVISIONS: 51
 REVISIONS: 52
 REVISIONS: 53
 REVISIONS: 54
 REVISIONS: 55
 REVISIONS: 56
 REVISIONS: 57
 REVISIONS: 58
 REVISIONS: 59
 REVISIONS: 60
 REVISIONS: 61
 REVISIONS: 62
 REVISIONS: 63
 REVISIONS: 64
 REVISIONS: 65
 REVISIONS: 66
 REVISIONS: 67
 REVISIONS: 68
 REVISIONS: 69
 REVISIONS: 70
 REVISIONS: 71
 REVISIONS: 72
 REVISIONS: 73
 REVISIONS: 74
 REVISIONS: 75
 REVISIONS: 76
 REVISIONS: 77
 REVISIONS: 78
 REVISIONS: 79
 REVISIONS: 80
 REVISIONS: 81
 REVISIONS: 82
 REVISIONS: 83
 REVISIONS: 84
 REVISIONS: 85
 REVISIONS: 86
 REVISIONS: 87
 REVISIONS: 88
 REVISIONS: 89
 REVISIONS: 90
 REVISIONS: 91
 REVISIONS: 92
 REVISIONS: 93
 REVISIONS: 94
 REVISIONS: 95
 REVISIONS: 96
 REVISIONS: 97
 REVISIONS: 98
 REVISIONS: 99
 REVISIONS: 100

REVISOR



DESIGNER

CHECKER

FUNCTIONAL SUPERVISOR

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans MAINTENANCE

BORDER LAST REVISED 7/2/2010



TYPICAL CROSS SECTIONS
 NO SCALE **X-1**

USERNAME => s115152
 DGN FILE => 20h000ca001.dgn

RELATIVE BORDER SCALE 1" = 10' IN INCHES

UNIT 0156

PROJECT NUMBER & PHASE 02-1400-0152-1 EA 02-0H0001




LAST REVISION DATE PLOTTED => 09-JAN-2015
 01-08-15 TIME PLOTTED => 14:27

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	3	48

01-08-15	
REGISTERED CIVIL ENGINEER	DATE
01-08-15	
PLANS APPROVAL DATE	


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

- NOTES:**
- EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.
 - DO NOT SKIN PATCH DIKE UNDER TERMINAL SYSTEM.




TYPE F

PM 19.77 TO 20.03
ROUTE 273



TYPE D AND E




TYPE A

TYPICAL SKIN PATCH EXISTING ASPHALT CONCRETE DIKE


TYPICAL CROSS SECTIONS

NO SCALE


X-2



GUARDRAIL LOCATION WITH DIKE
(TYPICAL BOTH DIRECTIONS)



GUARDRAIL LOCATION WITHOUT DIKE
(TYPICAL BOTH DIRECTIONS)



ENTRANCE/EXIT RAMP

RELATIVE BORDER SCALE 1" = 10' INCHES



UNIT 0156

PROJECT NUMBER & PHASE 02-1400-0152-1

EA 02-0H0001

P:\proj\3\02\0h0001\plans\pse\20h000ca002.dgn

BORDER LAST REVISED 7/2/2010

USERNAME => s115152
DGN FILE => 20h000ca002.dgn

LAST REVISION DATE PLOTTED => 09-JAN-2015
01-08-15 TIME PLOTTED => 14:27

REVISOR	DATE
MICHAEL CONNER	KARLIE SMITH
CALCULATED/DESIGNED BY	CHECKED BY
FUNCTIONAL SUPERVISOR	LANCE BROWN
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION	MAINTENANCE

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	4	48

01-08-15	
REGISTERED CIVIL ENGINEER	DATE
01-08-15	
PLANS APPROVAL DATE	

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



NOTES:



1. THE 0.10' DEPTH COLD PLANE AC PAVEMENT SHALL BE A MINIMUM OF 66' IN LENGTH MEASURED ALONG THE ETW.
2. SEE TYPICAL CROSS SECTIONS FOR EXISTING STRUCTURAL SECTION.
3. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.
4. SHOULDER IS 0.08'± LOWER THAN TRAVELED WAY DUE TO RAC-O. COLD PLANE DEPTH TAKEN IN TRAVELED WAY. THE EXIST RAC-O TRANSITIONS OUT TO EP-EP WITHIN THE 50' TAPER SHOWN.

LEGEND:

- COLD PLANE AC PAVEMENT (0.08' TO 0.10')
- COLD PLANE AC PAVEMENT (0.08' ± 0.02') (TYPICAL)
- COLD PLANE AC PAVEMENT (0.00' TO 0.10')

ABBREVIATIONS:

- RHMA-O RUBBERIZED HOT MIX ASPHALT-OPEN GRADED (OPEN GRADED FRICTION COURSE)
- RAC-O RUBBERIZED ASPHALT CONCRETE (TYPE O)



OVERCROSSING PAVEMENT OVERLAY TAPER
N Hwy 273 TO ROUTE 5 Conn OC PM R18.48

CONSTRUCTION DETAILS
NO SCALE

C-1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION - MAINTENANCE
 FUNCTIONAL SUPERVISOR: LANCE BROWN
 CALCULATED/DESIGNED BY: [blank]
 CHECKED BY: [blank]
 MICHAEL CONNER
 KARLIE SMITH
 REVISIONS: [blank]
 REVISED BY: [blank]
 DATE: [blank]
 REVISOR: [blank]
 DATE: [blank]

LAST REVISION: [blank]
 DATE PLOTTED => 09-JAN-2015
 01-08-15
 TIME PLOTTED => 14:27

RAMPS

OVERCROSSING/ UNDERCROSSING	DIRECTION OF TRAVEL		ENTRANCE RAMP	EXIT RAMP	POST MILE	DIMENSIONS													
						WIDTH IN FEET								LENGTH IN FEET					
	NB	SB				W-1	W-2	W-3	W-4	W-5	W-6	W-7	W-8	L-1	L-2	L-3	L-4	L-5	L-6
5/299 Jct	X	X	X		R17.05	58	24	40		31	34	65	24	1890	1145		130	290	82
	X			X	R17.11	40	25	25		25	37	45	20	480	360		475	185	90
		X			R17.53	36	26	34		22	25	24	24	445	1220		165	60	36
	X		X		R17.57	40	25	24		26	26	34	24	810	850		315	430	170
TWIN VIEW Blvd	X	X	X		R17.92	27	22	24	160					800	640	93			
	X			X	R17.93	36	28	40	135					420	675	74			
		X			R18.22	31	22	26	150					375	720	64			
	X		X		R18.22	40	24	25	105					700	568	88			
5/273 Jct	X	X	X		R18.73	*	*	*	*	*	*	*	*	*	*	*	*	*	*
	X		X		R18.78	*	*	*	*	*	*	*	*	*	*	*	*	*	*

* SEE Jct 5/273 RAMPS DETAIL BELOW

NOTE:

1. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	5	48

01-08-15
DATE


01-08-15
PLANS APPROVAL DATE

REGISTERED CIVIL ENGINEER
MICHAEL A. CONNER
No. C73123
Exp. 12-31-16
CIVIL
STATE OF CALIFORNIA


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.




REPLACE AC SURFACING
LAKE Blvd NORTHBOUND EXIT RAMP
TWIN VIEW Blvd NORTHBOUND EXIT RAMP




REPLACE AC SURFACING
(TYPICAL BOTH DIRECTIONS)



PAVEMENT CONFORM DETAIL
NORTH REDDING SEPARATION
APPROACH SHOWN
DEPARTURE SIMILAR



Jct 5/273 RAMPS



TWIN VIEW Blvd RAMP DETAIL

CONSTRUCTION DETAILS

NO SCALE

C-2

P:\proj\3\02\0h000\plans\pse\20h000ga002.dgn

REVISION	DATE PLOTTED => 09-JAN-2015
01-08-15	TIME PLOTTED => 14:27

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	7	48




01-08-15	
REGISTERED CIVIL ENGINEER	DATE
01-08-15	
PLANS APPROVAL DATE	

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.




NOTES:


- FOR DIKE DETAILS, SEE REVISED STANDARD PLANS RSP A87B.
- ONLY TYPE C DIKE MAY BE USED UNDER OR IN FRONT OF TERMINAL SYSTEMS, OR WHEN DIKE IS PLACED MORE THAN 2" IN FRONT OF FACE OF MBGR, OR MORE THAN 7" IN FRONT OF FACE OF MGS.
- EXISTING MOUNTABLE TYPE E DIKE MAY REMAIN UNDER GUARDRAIL, BUT NO NEW MOUNTABLE DIKE SHOULD BE PLACED UNDER GUARDRAIL.
- GUARDRAIL DELINEATION TO BE USED WHERE SHOWN ON THE PROJECT PLANS.
- FOR STEEL LINE POSTS, USE 1/4" - 20 SELF-TAPPING SCREWS IN 0.22" DIAMETER HOLES OR 1/4" BOLTS IN 3/32" DIAMETER HOLES.
- SEE MEASURE HEIGHT AT GRADE BREAK DETAIL C-5.
- FOR DETAILS OF STANDARD HARDWARE USED TO CONSTRUCT GUARDRAIL, SEE REVISED STANDARD PLAN RSP A77M1. RSP A77M1 APPLIES TO MBGR.
- FOR DETAILS OF POSTS (WOOD OR STEEL) AND BLOCKS (WOOD OR COMPOSITE/PLASTIC) USED TO CONSTRUCT GUARDRAIL, SEE REVISED STANDARD PLAN RSP A77N1 OR RSP A77N2. RSP A77N1 OR RSP A77N2 APPLIES TO MBGR.
- IF AUTHORIZED, A SINGLE LINE POST MAY BE MOVED UP TO 12" ALONG THE GUARDRAIL TO AVOID OBSTACLES. IF POST IS MOVED, BOLT THROUGH THE POST AND BLOCK ONLY.
- SEE TYPICAL LEAVOUT AREA SHEET C-6 WHEN INSTALLING POST THROUGH PAVEMENT. POST NEED SPACE TO ROTATE DURING IMPACTS.
- PLACE TYPE F DIKE UNDER GUARDRAIL AND PLACE TYPE C DIKE IF MORE THAN 2" IN FRONT OF FACE OF GUARDRAIL.
- FOR BOLTED CONNECTION OF RAIL ELEMENT TO BLOCK AND POST, SEE "RAIL ELEMENT SPLICE DETAIL" AND "SECTION THRU RAIL ELEMENT", REVISED STANDARD PLAN RSP A77L1.
- TO CONNECT RAILING TO TERMINAL SYSTEM END TREATMENT, TRANSITION THE TOP OF RAILING HEIGHT AT A RATIO OF 120:1 TO TERMINAL SYSTEM END TREATMENT HEIGHT PLUS ONE 12'-6" STANDARD RAILING SECTION AT THE TRANSITIONED HEIGHT FOR A HORIZONTAL CONNECTION TO THE END TREATMENT.
- ADDITIONAL HOLE IN UPPERMOST PORTION OF LINE POST IS FOR POTENTIAL FUTURE ADJUSTMENTS OF RAILING HEIGHT. SEE REVISED STANDARD PLAN RSP A77N1, RSP A77N2.
- DIMENSIONS FOR POST AND BLOCKS ARE NOMINAL.
- EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.



**SECTION A-A
TYPICAL LINE
POST INSTALLATION**
SEE NOTE 9



GUARDRAIL DIKE POSITIONING



**GUARDRAIL DELINEATION
CONSTRUCTION DETAILS**
SEE NOTE 4
NO SCALE

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION - MAINTENANCE
 FUNCTIONAL SUPERVISOR: LANCE BROWN
 CALCULATED/DESIGNED BY: MICHAEL CONNER
 CHECKED BY: KARLIE SMITH
 REVISED BY: DATE REVISIONS:

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	8	48


01-08-15	
REGISTERED CIVIL ENGINEER	DATE
01-08-15	
PLANS APPROVAL DATE	

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.




NOTES:


1. Max 10:1 SLOPE IN FRONT OF GUARDRAIL.
2. FOR POST AND BLOCK DETAILS SEE REVISED STANDARD PLANS RSP A77N1 AND RSP A77N2. RSP A77N1 AND RSP A77N2 APPLIES TO MBGR.
3. FOR 8' POST USE W6 X 15 STEEL OR 10" X 10" WOOD POST.
4. BLOCKS MUST HAVE MEANS TO RESIST ROTATION OTHER THAN THROUGH BOLT.
5. PLACE RUB RAIL (GUARDRAIL ELEMENT) AND ATTACH TO POST WITH NO BLOCK WHEN HEIGHT OF GUARDRAIL IS OVER 32" ABOVE FINISH GRADE UNDER FACE OF RAIL.
6. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.




TYPICAL ROADWAY INSTALLATION
SEE NOTE 2




NARROW ROADWAY INSTALLATION
SEE NOTE 2



TYPICAL GUARDRAIL OBJECT MARKERS




GUARDRAIL WITH FLARED ALIGNMENT



NOTE A:
FOR A SERIES OF FIXED OBJECTS (BRIDGE COLUMNS, OVERHEAD SIGN SUPPORTS, ETC.) ADDITIONAL 8'-0" POST WITH BLOCKS AT 3'-1 1/2" CENTER TO CENTER SPACING ARE TO BE USED BETWEEN FIXED OBJECTS.


STRENGTHENED RAILING SECTIONS FOR FIXED OBJECT



$$Y = \frac{WX^2}{L^2}$$

Y = OFFSET FROM BASE LINE
W = MAXIMUM OFFSET
X = DISTANCE ALONG BASE LINE
L = LENGTH OF FLARE

PARABOLIC FLARE OFFSETS



WHEN THERE IS A BREAK POINT IN FRONT OF GUARDRAIL MEASURE HEIGHT OF GUARDRAIL BASED ON DISTANCE FROM GRADE BREAK TO ADJUST FOR TRAJECTORY.

MEASURE HEIGHT DETAIL AT GRADE BREAK

CONSTRUCTION DETAILS

NO SCALE

POST EMBEDMENT



STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION - MAINTENANCE
 Michael Conner
 Karlie Smith
 Lance Brown
 01-08-15 14:27

NOTES:

1. EXACT LOCATION OF ALL SIGNS TO BE DETERMINED BY THE ENGINEER.
2. ALL SIGNS SHALL BE BLACK ON ORANGE EXCEPT C40 (CA), WHICH IS BLACK ON WHITE.
3. CALIFORNIA CODES ARE DESIGNATED BY (CA), OTHERWISE FEDERAL CODES ARE SHOWN.
4. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.

LEGEND:





ENTRANCE/EXIT RAMP



Rte	PM	LOCATION
5	R17.05	5/299 Jct SB ENTRANCE
	R17.11	5/299 Jct NB EXIT
	R17.53	5/299 Jct SB EXIT
	R17.57	5/299 Jct NB ENTRANCE
	R17.92	TWIN VIEW Blvd SB ENTRANCE
	R17.93	TWIN VIEW Blvd NB EXIT
	R18.22	TWIN VIEW Blvd SB EXIT
	R18.22	TWIN VIEW Blvd NB ENTRANCE
273	R18.73	5/273 Jct SB EXIT
	R18.78	5/273 Jct NB ENTRANCE
273	19.77	CATERPILLAR Rd

CONSTRUCTION AREA SIGNS (STATIONARY MOUNTED)

TYPE	PANEL SIZE INCHES	SIGN MESSAGE	No. OF POSTS AND SIZE	No. OF SIGNS
A	C40(CA) 108" x 42"	TRAFFIC FINES DOUBLED IN CONSTRUCTION ZONES	2- 4" x 6"	2
B	C40(CA) 72" x 36"	TRAFFIC FINES DOUBLED IN CONSTRUCTION ZONES	2- 4" x 6"	1
C	W20-1 C23B(CA) 48" x 48" 54" x 24"	ROAD WORK AHEAD "PAVEMENT MAINTENANCE"	2- 4" x 6" OR BARRIER MOUNT	9
D	W20-1 C23B(CA) 48" x 48" 36" x 18"	ROAD WORK AHEAD "PAVEMENT MAINTENANCE"	2- 4" x 6"	3
E	C14(CA) 48" x 24"	END ROAD WORK	1- 4" x 4" OR BARRIER MOUNT	9
F	C14(CA) 36" x 18"	END ROAD WORK	1- 4" x 4"	3



C23B(CA) SIGN PANEL DETAIL



CONSTRUCTION AREA SIGNS

CONSTRUCTION AREA SIGNS

NO SCALE

CS-1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 Michael Conner
 Karlie Smith
 Lance Brown
 MAINTENANCE

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	12	48

01-08-15
 REGISTERED CIVIL ENGINEER DATE
 01-08-15
 PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER
 MICHAEL A. CONNER
 No. C73123
 Exp. 12-31-16
 CIVIL
 STATE OF CALIFORNIA


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTES:

1. EXACT SIGN & PCMS LOCATIONS TO BE DETERMINED BY ENGINEER.
2. SEE STANDARD PLANS FOR TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE.
3. COVER EXISTING SPEED LIMIT SIGNS WITHIN THE REDUCED SPEED ZONE.
4. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.

LEGEND:

- ▮ PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- TRAFFIC CONE



TYPICAL SIGN LAYOUT FOR TEMPORARY REDUCED SPEED ZONE

CONSTRUCTION AREA SIGNS

NO SCALE




CS-2

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans MAINTENANCE
 FUNCTIONAL SUPERVISOR LANCE BROWN
 CALCULATED/DESIGNED BY MICHAEL CONNER
 CHECKED BY KARLIE SMITH
 REVISED BY DATE REVISIONS
 USERNAME => s115152
 DGN FILE => 20h0001a002.dgn
 BORDER LAST REVISED 7/2/2010
 RELATIVE BORDER SCALE IS IN INCHES
 UNIT 0156
 PROJECT NUMBER & PHASE 02-1400-0152-1
 EA 02-0H0001

LAST REVISION | DATE PLOTTED => 09-JAN-2015
 01-08-15 TIME PLOTTED => 14:27

NOTES:

- PRE-NOTIFICATION PCMS: PLACE NEAR RAMP AND ACTIVATE APPROXIMATELY 12 HOURS PRIOR TO RAMP CLOSURE.
- RAMP CLOSED PCMS: MOVE PRE-NOTIFICATION PCMS APPROXIMATELY 1000 FEET BEFORE RAMP AND ACTIVATE DURING RAMP CLOSURE.
- PLACE 7 DAYS PRIOR TO RAMP CLOSURE.
- IF AVAILABLE, EXISTING ROUTE SHIELDS AND DIRECTIONS MAY BE USED IN PLACE OF SIGNS SHOWN.
- RAMP CLOSED PCMS: PLACE BEFORE OPEN ENTRANCE RAMP AND ACTIVATE DURING RAMP CLOSURE.
- EXACT LOCATION OF ALL SIGNS TO BE DETERMINED BY THE ENGINEER.
- EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.




EXIT NAME	EXIT NUMBER	
	SB	NB
Jct 299/LAKE Blvd	680	680
TWIN VIEW Blvd	681A	681
Jct 273/MARKET St	681B	

CONSTRUCTION AREA SIGNS (PORTABLE)


CODE	PANEL SIZE	PANEL MESSAGE
G27-2 (5) (CA)	24" x 24"	I-5
M3-1	24" x 12"	NORTH
M3-3	24" x 12"	SOUTH
M4-8A	24" x 18"	END DETOUR
M4-10L	48" x 18"	DETOUR (L+ ARROW)
M4-10R	48" x 18"	DETOUR (R+ ARROW)
SC3 (CA)	48" x 18"	DETOUR (UP ARROW)
SC6-3 (CA)	48" x 48"	RAMP CLOSED
SP1	24" x 30"	EXIT XXX

LEGEND:


- PORTABLE CHANGABLE MESSAGE SIGN
- CONSTRUCTION AREA SIGN (PORTABLE)
- DIRECTION OF TRAFFIC



TYPICAL EXIT-RAMP DETOUR SIGNING



TYPICAL ENTRANCE-RAMP DETOUR SIGNING



1.5" Radius, 0.6" Border, 0.4" Indent, Black on Orange;
 [EXIT] E Mod; [XXX] E Mod;

EXIT NUMBER SIGN (SP1) DETAIL
 (SEE NOTE 6)

DETOUR PLAN

NO SCALE

DE-1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION - MAINTENANCE
 Michael Conner, Karlie Smith, Lance Brown
 01-08-15

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	14	48

01-08-15
REGISTERED CIVIL ENGINEER DATE


01-08-15
PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
MICHAEL A. CONNER
No. C73123
Exp. 12-31-16
CIVIL
STATE OF CALIFORNIA

NOTE:


1. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.



CONSTRUCTION AREA SIGNS (PORTABLE SIGNS)

SIGN No.	CODE	PANEL SIZE (INCH)	REMARKS	No. (EA)
(A) *	SC6-3 (CA)	48" x 48"	"RAMP CLOSED" "DATE-TIME"	2
(B)	M4-10L G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (L+ ARROW) ROUTE SHIELD (5) NORTH	
(C)	M4-10R G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (5) NORTH	
(D)	SC3 (CA) G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (5) NORTH	
(E)	M4-10L G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (L+ ARROW) ROUTE SHIELD (5) SOUTH	3
(F)	M4-10R G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (5) SOUTH	2
(G)	SC3 (CA) G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (5) SOUTH	1
(H)	M4-10L SP1	48" x 18" 24" x 30"	DETOUR (L+ ARROW) EXIT XXX	2
(I)	M4-10R SP1	48" x 18" 24" x 30"	DETOUR (R+ ARROW) EXIT XXX	2
(J)	SC3 (CA) SP1	48" x 18" 24" x 30"	DETOUR (UP ARROW) EXIT XXX	2
(K)	M4-10R G28-2 (273) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (273) NORTH	
(L)	SC3 (CA) G28-2 (273) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (273) NORTH	
(M)	M4-8A	24" x 18"	END DETOUR	2
TOTAL				16

SR 299/LAKE Blvd SOUTHBOUND EXIT RAMP DETOUR



ROUTE 299/LAKE Blvd SOUTHBOUND ENTRANCE RAMP DETOUR

DETOUR PLAN

NO SCALE

DE-2

* PLACE 7 DAYS PRIOR TO RAMP CLOSURE

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION - MAINTENANCE

Caltrans

FUNCTIONAL SUPERVISOR: LANCE BROWN


DESIGNED BY: MICHAEL CONNER

CHECKED BY: KARLIE SMITH

REVISIONS: REVISION BY: DATE REVISION BY: DATE

NOTES:

- FOR LABELS ⑤ AND ⑦ SEE SHEET DE-1.
- EXACT PLACEMENT TO BE DETERMINED BY THE ENGINEER. PCMS TO READ AS BELOW OR AS DIRECTED BY THE ENGINEER:




- EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.

CONSTRUCTION AREA SIGNS (PORTABLE SIGNS)

SIGN No.	CODE	PANEL SIZE (INCH)	REMARKS	No. (EA)
Ⓐ *	SC6-3 (CA)	48" x 48"	"RAMP CLOSED" "DATE-TIME"	2
Ⓑ	M4-10L G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (L+ ARROW) ROUTE SHIELD (5) NORTH	2
Ⓒ	M4-10R G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (5) NORTH	2
Ⓓ	SC3 (CA) G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (5) NORTH	5
Ⓔ	M4-10L G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (L+ ARROW) ROUTE SHIELD (5) SOUTH	
Ⓕ	M4-10R G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (5) SOUTH	
Ⓖ	SC3 (CA) G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (5) SOUTH	
Ⓗ	M4-10L SP1	48" x 18" 24" x 30"	DETOUR (L+ ARROW) EXIT XXX	
Ⓘ	M4-10R SP1	48" x 18" 24" x 30"	DETOUR (R+ ARROW) EXIT XXX	
Ⓙ	SC3 (CA) SP1	48" x 18" 24" x 30"	DETOUR (UP ARROW) EXIT XXX	
Ⓚ	M4-10R G28-2 (273) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (273) NORTH	
Ⓛ	SC3 (CA) G28-2 (273) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (273) NORTH	
Ⓜ	M4-8A	24" x 18"	END DETOUR	1
TOTAL				12

* PLACE 7 DAYS PRIOR TO RAMP CLOSURE



ROUTE 299/LAKE Blvd NORTHBOUND ENTRANCE RAMP DETOUR

DETOUR PLAN

NO SCALE


DE-3

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 MAINTENANCE
 LANCE BROWN
 FUNCTIONAL SUPERVISOR
 CHECKED BY
 MICHAEL CONNER
 KARLIE SMITH
 REVISOR BY
 DATE REVISOR


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	16	48
			01-08-15	DATE	
			01-08-15	PLANS APPROVAL DATE	
REGISTERED CIVIL ENGINEER No. C73123 Exp. 12-31-16 CIVIL STATE OF CALIFORNIA					
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.					

NOTE:

1. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.



ROUTE 273 NORTHBOUND ENTRANCE RAMP DETOUR



ROUTE 273 SOUTHBOUND EXIT RAMP DETOUR

CONSTRUCTION AREA SIGNS (PORTABLE SIGNS)

SIGN No.	CODE	PANEL SIZE (INCH)	REMARKS	No. (EA)
(A) *	SC6-3 (CA)	48" x 48"	"RAMP CLOSED" "DATE-TIME"	2
(B)	M4-10L G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (L+ ARROW) ROUTE SHIELD (5) NORTH	2
(C)	M4-10R G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (5) NORTH	1
(D)	SC3 (CA) G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (5) NORTH	1
(E)	M4-10L G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (L+ ARROW) ROUTE SHIELD (5) SOUTH	
(F)	M4-10R G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (5) SOUTH	
(G)	SC3 (CA) G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (5) SOUTH	
(H)	M4-10L SP1	48" x 18" 24" x 30"	DETOUR (L+ ARROW) EXIT XXX	
(I)	M4-10R SP1	48" x 18" 24" x 30"	DETOUR (R+ ARROW) EXIT XXX	
(J)	SC3 (CA) SP1	48" x 18" 24" x 30"	DETOUR (UP ARROW) EXIT XXX	
(K)	M4-10R G28-2 (273) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (273) NORTH	3
(L)	SC3 (CA) G28-2 (273) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (273) NORTH	1
(M)	M4-8A	24" x 18"	END DETOUR	2
TOTAL				12

* PLACE 7 DAYS PRIOR TO RAMP CLOSURE

DETOUR PLAN

NO SCALE

DE-4

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 MAINTENANCE
 FUNCTIONAL SUPERVISOR: LANCE BROWN
 CALCULATED/DESIGNED BY: MICHAEL CONNER
 CHECKED BY: KARLIE SMITH
 REVISED BY: DATE REVISOR:

LAST REVISION | DATE PLOTTED => 09-JAN-2015
 01-08-15 TIME PLOTTED => 14:27

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	17	48


01-08-15
REGISTERED CIVIL ENGINEER DATE

01-08-15
PLANS APPROVAL DATE


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
MICHAEL A. CONNER
 No. C73123
 Exp. 12-31-16
 CIVIL
 STATE OF CALIFORNIA

NOTE:
1. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.



TWIN VIEW Blvd SOUTHBOUND ENTRANCE RAMP DETOUR



TWIN VIEW Blvd NORTHBOUND EXIT RAMP DETOUR

**CONSTRUCTION AREA SIGNS
(PORTABLE SIGNS)**

SIGN No.	CODE	PANEL SIZE (INCH)	REMARKS	No. (EA)
(A) *	SC6-3 (CA)	48" x 48"	"RAMP CLOSED" "DATE-TIME"	2
(B)	M4-10L G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (L+ ARROW) ROUTE SHIELD (5) NORTH	
(C)	M4-10R G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (5) NORTH	
(D)	SC3 (CA) G27-2 (5) (CA) M3-1	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (5) NORTH	
(E)	M4-10L G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (L+ ARROW) ROUTE SHIELD (5) SOUTH	2
(F)	M4-10R G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (5) SOUTH	3
(G)	SC3 (CA) G27-2 (5) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (5) SOUTH	1
(H)	M4-10L SP1	48" x 18" 24" x 30"	DETOUR (L+ ARROW) EXIT XXX	1
(I)	M4-10R SP1	48" x 18" 24" x 30"	DETOUR (R+ ARROW) EXIT XXX	3
(J)	SC3 (CA) SP1	48" x 18" 24" x 30"	DETOUR (UP ARROW) EXIT XXX	1
(K)	M4-10R G28-2 (273) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (R+ ARROW) ROUTE SHIELD (273) NORTH	
(L)	SC3 (CA) G28-2 (273) (CA) M3-3	48" x 18" 24" x 24" 24" x 12"	DETOUR (UP ARROW) ROUTE SHIELD (273) NORTH	
(M)	M4-8A	24" x 18"	END DETOUR	2
TOTAL				15

* PLACE 7 DAYS PRIOR TO RAMP CLOSURE

DETOUR PLAN

NO SCALE

DE-5

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION - MAINTENANCE
 LANCE BROWN
 MICHAEL CONNER
 KARLIE SMITH
 REVISIONS: 01-08-15

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	19	48



01-08-15
 REGISTERED CIVIL ENGINEER DATE
 01-08-15
 PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER
 MICHAEL A. CONNER
 No. C73123
 Exp. 12-31-16
 CIVIL
 STATE OF CALIFORNIA


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTES:


1. NO RUMBLE STRIP TO BE INSTALLED ON CONCRETE BRIDGES OR APPROACH SLABS.
2. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.



TRAFFIC STRIPE MATCH DETAIL



STANDARD GROUND IN RUMBLE STRIP



PAVEMENT DELINEATION DETAILS

GROUND IN RUMBLE STRIP AT 5/273 Jct

NO SCALE

PDD-2

REVISIONS: 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000.

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	20	48

01-08-15
REGISTERED CIVIL ENGINEER DATE

01-08-15
PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER
MICHAEL A. CONNER
No. C73123
Exp. 12-31-16
CIVIL
STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTE:

1. EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.

ABBREVIATIONS:

Dir DIRECTION

THERMOPLASTIC PAVEMENT MARKING

Rte	Dir	DESCRIPTION	PM	EA	SQFT	REMARKS
5	NB	MAINLINE	R16.50	1	3.0	DETAIL A
		5/299 Jct EXIT	R17.11	1	33.0	TYPE V ARROW
				4	168.0	TYPE III (L) ARROW
				1	42.0	TYPE III (R) ARROW
				1	87.0	CROSSWALK
				1	3.0	DETAIL A
		5/299 Jct ENTRANCE	R17.50	1	3.0	DETAIL A
			R17.57	1	25.0	TYPE I 18'-0" ARROW
		TWIN VIEW Blvd EXIT	R17.93	2	66.0	TYPE V ARROW
				2	90.0	TYPE II (L) ARROW
				2	84.0	TYPE III (R) ARROW
			2	44.0	STOP	
			1	65.0	LIMIT LINE	
			1	29.0	DELINEATED ISLAND	
	TWIN VIEW Blvd ENTRANCE	R18.22	1	33.0	TYPE V ARROW	
	MAINLINE	R18.50	1	3.0	DETAIL A	
	SB	MAINLINE	R16.50	1	3.0	DETAIL A
		5/299 Jct ENTRANCE	R17.05	3	126.0	TYPE VI ARROW
				1	94.0	CROSSWALK
				1	25.0	TYPE I 18'-0" ARROW
		MAINLINE	R17.50	1	3.0	DETAIL A
		5/299 Jct EXIT	R17.53	1	33.0	TYPE V ARROW
				2	84.0	TYPE III (R) ARROW
			3	135.0	TYPE II (L) ARROW	
			1	15.0	LIMIT LINE	
		TWIN VIEW Blvd ENTRANCE	R17.92	1	25.0	TYPE I 18'-0" ARROW
		TWIN VIEW Blvd EXIT	R18.22	2	66.0	TYPE V ARROW
				1	22.0	STOP
		1	83.0	LIMIT LINE		
MAINLINE		R18.50	1	3.0	DETAIL A	
	R18.67	1	42.0	TYPE VI ARROW		
	R18.70	1	42.0	TYPE VI ARROW		
	R18.74	1	42.0	TYPE VI ARROW		
273	NB	MAINLINE	R19.78	1	25.0	TYPE I 18'-0" ARROW
			R19.79	1	42.0	TYPE VI ARROW
			R19.80	1	42.0	TYPE VI ARROW
			R19.81	1	42.0	TYPE VI ARROW
			R19.81	1	42.0	TYPE VI ARROW
	SB	MAINLINE	R19.78	1	42.0	TYPE III (R) ARROW
			1	42.0	TYPE III (L) ARROW	
			2	66.0	TYPE V ARROW	
	1	42.0	TYPE III (R) ARROW			
	1	42.0	TYPE III (L) ARROW			
	1	42.0	TYPE III (L) ARROW			
	2	66.0	TYPE V ARROW			
TOTAL					2111.0	

REMOVE THERMOPLASTIC PAVEMENT MARKING

Rte	Dir	DESCRIPTION	PM	EA	SQFT	REMARKS
273	NB	MAINLINE	19.78	1	25.0	TYPE I 18'-0" ARROW
	SB	MAINLINE	19.78	1	42.0	TYPE III (R) ARROW
1				42.0	TYPE III (L) ARROW	
				2	66.0	TYPE V ARROW
TOTAL					175.0	

PAVEMENT MARKER (RETROREFLECTIVE)

Rte	DESCRIPTION	TYPE G	TYPE H
		EA	EA
273	MAINLINE	71	60
TOTAL		131	

PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)

Rte	DESCRIPTION	TYPE C	TYPE G	TYPE H
		EA	EA	EA
5	MAINLINE		641	585
	RAMPS	24	385	501
SUBTOTAL		24	1026	1086
TOTAL		2136		

THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)

Rte	DESCRIPTION	DETAIL 9	DETAIL 12	DETAIL 14A	DETAIL 25	DETAIL 25A	DETAIL 27B	DETAIL 36	DETAIL 36A	DETAIL 36B	DETAIL 38	DETAIL 38A	DETAIL 38B
		LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF
5	MAINLINE		30,308		27,984		27,984					120	
	RAMPS	1843	1957	864		11,960	17,565	2466	327	650	678	275	266
273	MAINLINE		2113		2746		2746						212
SUBTOTAL		1843	34,378	864	30,730	11,960	48,295	2466	327	650	678	395	478
TOTAL		133,064											

PAVEMENT DELINEATION QUANTITIES

PDQ-1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 MAINTENANCE
 LANCE BROWN
 FUNCTIONAL SUPERVISOR
 CHECKED BY
 DESIGNED BY
 KARLIE SMITH
 MICHAEL CONNER
 REVISOR BY
 DATE REVISOR

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	21	48

01-08-15
REGISTERED CIVIL ENGINEER DATE

01-08-15
PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTES:

- (N) - NOT A SEPARATE PAY ITEM, FOR INFORMATION ONLY
- NO RUMBLE STRIP TO BE INSTALLED ON CONCRETE BRIDGES OR APPROACH SLABS.
- EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.

ABBREVIATIONS:

- RHMA-O RUBBERIZED HOT MIX ASPHALT-OPEN GRADED (OPEN GRADED FRICTION COURSE)
 RAC-O RUBBERIZED ASPHALT CONCRTE (TYPE O)
 Dir DIRECTION

REPLACE ASPHALT CONCRETE SURFACING

Rte	Dir	POST MILE LIMITS	(N) No. OF DIGOUTS	(N) Avg LENGTH	(N) WIDTH	(N) DEPTH	REPLACE AC SURFACING
5	NB	PM - PM		LF	LF	LF	CY
		R16.50-R17.00	16	100	4	0.33	79
		R17.11	2	155	12	0.33	46
		R17.93	1	75	12	0.33	11
		R17.00-R18.00	16	100	4	0.33	79
		R18.00-R19.00	16	100	4	0.33	79
		R16.20-R17.00	16	100	4	0.33	79
		R17.00-R18.00	16	100	4	0.33	79
		R18.00-R19.00	16	100	4	0.33	79
		273	NB	19.70-20.03	4	100	4
SB	19.70-20.03	4	100	4	0.33	20	
TOTAL							571

SKIN PATCH EXISTING ASPHALT CONCRETE DIKE

Rte	Dir	POST MILE LIMITS	MAINLINE	RAMP	Lt	Rt	PLACE HMA DIKE				HMA (TYPE A) TON
							(TYPE A) LF	(TYPE D) LF	(TYPE E) LF	(TYPE F) LF	
5	NB	R17.03-R17.11	X	X		X	817				180
		R17.57-R17.87	X	X		X	1300				
		R18.78		X		X				505	
		R16.22-R17.05	X	X		X	2650		1750	155	
		R17.09-R17.30	X			X			1100		
		R17.35-R17.53	X			X			695	320	
		R17.53		X	X		X	1325			
		R17.53	X	X		X			670		
		R18.30-R18.37	X			X		370			
		R18.49-R18.59	X			X		544			
273	NB	R18.76-R18.89	X			X	800		126		
		R18.73		X		X		295			
		TOTAL					7806	295	4341	980	180

RUMBLE STRIP

Rte	Dir	POST MILE LIMITS	Sta	REMARKS
5	NB	R16.50-R19.00	264	MAINLINE
		R18.78	31	RAMP
		R16.20-R19.00	296	MAINLINE
273	NB	R18.73	17	RAMP
		19.78-20.03	14	MAINLINE
SB	19.78-20.03	14	MAINLINE	
TOTAL			636	

ROADWAY QUANTITIES

Rte	Dir	POST MILE LIMITS	DESCRIPTION	(N) LENGTH	(N) WIDTH	RHMA-O	SHOULDER BACKING	TACK COAT	
				LF	LF				TON
5	NB	R16.50-R19.00	MAINLINE	13,200	40-75	3856	469	26	
		R17.11	5/299 Jct EXIT RAMP			322	21	2	
		R17.57	5/299 Jct ENTRANCE RAMP			441	98	3	
		R17.93	TWIN VIEW Blvd EXIT RAMP			222	24	2	
		R18.22	TWIN VIEW Blvd ENTRANCE RAMP			225	68	2	
		R18.78	5/273 Jct ENTRANCE RAMP			520	45	4	
		SB	R16.20-R19.00	MAINLINE	14,784	40-76	4432	540	30
			R17.05	5/299 Jct ENTRANCE RAMP			685	111	5
			R17.53	5/299 Jct EXIT RAMP			329	59	2
			R17.92	TWIN VIEW Blvd ENTRANCE RAMP			226	49	2
R18.22	TWIN VIEW Blvd EXIT RAMP				184	65	1		
273	NB	19.78-20.03	MAINLINE	1320	34-40	311	89	2	
		SB	19.78-20.03	MAINLINE	1320	38-60	354	89	2
TOTAL						12,492	1825	86	

COLD PLANE ASPHALT CONCRETE PAVEMENT

Rte	Dir	POST MILE	DESCRIPTION	AREA	REMARKS	
				SQYD		
5	NB	R16.50-R19.00	MAINLINE	40,347	GRIND Exist RAC-O OVERLAY	
		R17.11	5/299 Jct EXIT RAMP	3790	GRIND Exist RAC-O OVERLAY	
		R17.57	5/299 Jct ENTRANCE RAMP	4503	GRIND Exist RAC-O OVERLAY	
		R17.93	TWIN VIEW Blvd EXIT RAMP	2657	GRIND Exist RAC-O OVERLAY	
		R18.22	TWIN VIEW Blvd ENTRANCE RAMP	2125	GRIND Exist RAC-O OVERLAY	
		R18.78	5/273 Jct ENTRANCE RAMP	4861	GRIND Exist RAC-O OVERLAY	
		SB	R16.20-R19.00	MAINLINE	42,588	GRIND Exist RAC-O OVERLAY
			R17.05	5/299 Jct ENTRANCE RAMP	5414	GRIND Exist RAC-O OVERLAY
			R17.53	5/299 Jct EXIT RAMP	3775	GRIND Exist RAC-O OVERLAY
			R17.92	TWIN VIEW Blvd ENTRANCE RAMP	2064	GRIND Exist RAC-O OVERLAY
			R18.22	TWIN VIEW Blvd EXIT RAMP	2020	GRIND Exist RAC-O OVERLAY
			R18.73	5/273 Jct EXIT RAMP	4793	GRIND Exist RAC-O OVERLAY
			R18.67-R18.80	MAINLINE	4	CONFORM AT 4 MEDIAN DI
273	NB	19.78-20.03	MAINLINE	3639	GRIND Exist RAC-O OVERLAY	
		SB	19.78-20.03	4231	GRIND Exist RAC-O OVERLAY	
TOTAL				126,811		

GUARDRAIL ITEMS

Rte	Dir	POST MILE LIMITS	MAINLINE	RAMP	SIDE	ADJUST GUARDRAIL	RECONSTRUCT GUARDRAIL	RECONSTRUCT GUARDRAIL (7' POST)	SALVAGE GUARDRAIL (STEEL POST)	RECONSTRUCT TERMINAL SYSTEM	RECONSTRUCT END ANCHOR (TYPE SFT)	(N) Exist BURIED POST END ANCHOR	RESET OBJECT MARKER	TREATED WOOD WASTE	COMMENT	
						LF	LF	LF	LF	EA	EA	EA	EA	EA		EA
5	NB	R18.09-R18.14	X		Rt				250							
		R18.28-R18.31	X		Rt	150				FLEAT	1					
		R18.38-R18.43	X		Rt	175		100				2	1		ADJUST SAND BEDDING	
		R18.46-R18.48		X	Rt		162.5					1	2	2389		
		R18.70-R18.80		X	Rt	500					FLEAT	1				
		R18.94-R19.00	X		Rt	215					SRT-8					
		SB	R16.22-R16.54	X		Rt	1750						1	1		
			R17.05		X	Rt		225				SRT-8	1	2	3274	
			R17.11-R17.30	X		Rt	900		100				1	1		
		R17.34-R17.40	X		Rt			300					1	2	4336	
		R18.09-R18.14	X		Rt	200					SRT-8					
		R18.36-R18.40	X		Rt	150							2			
		R18.47-R18.50	X		Rt	75							1			ADJUST SAND BEDDING
		R18.75-R18.79	X		Rt	100							1			ADJUST SAND BEDDING
		TOTAL						4215	687.5	200	250	5	7	8	9999	

SUMMARY OF QUANTITIES

Q-1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION - MAINTENANCE
 MICHAEL CONNER
 KARLIE SMITH
 LANCE BROWN
 FUNCTIONAL SUPERVISOR
 CALCULATED BY
 CHECKED BY
 REVISIONS: 01-08-15 DATE PLOTTED => 09-JAN-2015 TIME PLOTTED => 14:27

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	22	48



01-08-15
 REGISTERED CIVIL ENGINEER DATE
 01-08-15
 PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER
 THERESA ANDERSON
 No. C77957
 Exp. 6-30-15
 CIVIL
 STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTES:

- FOR ACCURATE RIGHT OF WAY DATA, CONTACT RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.
- EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.



TYPE D/TYPE A LOOP ARRAY
NO SCALE

MODIFY SIGNAL
SCALE: 1" = 20'

APPROVED FOR ELECTRICAL WORK ONLY

REVISOR	DATE	REVISION
TERI ANDERSON		
BEN PAULL		
ROB STINGER		
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION Electrical DESIGN		

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	24	48



<i>[Signature]</i>	01-08-15
REGISTERED CIVIL ENGINEER	DATE
01-08-15	
PLANS APPROVAL DATE	

REGISTERED PROFESSIONAL ENGINEER THERESA ANDERSON No. C77957 Exp. 6-30-15 CIVIL STATE OF CALIFORNIA



THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTES (THIS SHEET):


- FOR ACCURATE RIGHT OF WAY AND ACCESS DATA, CONTACT RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.
- EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.
- LOOP LOCATIONS ARE APPROXIMATE. FINAL LOCATION WILL BE DETERMINED BY THE ENGINEER.
- Exist LOOP DETECTORS.
- CENTER LOOP IN LANE.
- COIL 10' OF CABLES IN THE PULL BOX.



ID No. R11
PM R17.93



ID No. R12
PM R18.21



ID No. R13
PM R18.02

MODIFY TRAFFIC MONITORING STATION (COUNT)
NO SCALE

E-3

APPROVED FOR ELECTRICAL WORK ONLY



STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans ELECTRICAL DESIGN
 FUNCTIONAL SUPERVISOR: ROB STINGER
 DESIGNED BY: TERI ANDERSON
 CHECKED BY: BEN PAULL
 REVISIONS: [None]
 USERNAME => s115152
 DGN FILE => 20h000ua003.dgn
 BORDER LAST REVISED 7/2/2010



LAST REVISION | DATE PLOTTED => 09-JAN-2015
 01-08-15 | TIME PLOTTED => 14:27

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	26	48
			01-08-15	DATE	
REGISTERED CIVIL ENGINEER			THERESA ANDERSON		
01-08-15			No. C77957		
PLANS APPROVAL DATE			Exp. 6-30-15		
			CIVIL		
<small>THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.</small>					




NOTES (THIS SHEET):

- FOR ACCURATE RIGHT OF WAY AND ACCESS DATA, CONTACT RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.
- EXISTING UTILITY FACILITIES HAVE NOT BEEN INCLUDED ON THESE PLANS.
- LOOP LOCATIONS ARE APPROXIMATE. FINAL LOCATION WILL BE DETERMINED BY THE ENGINEER.
- ABExist LOOP DETECTORS.
- CENTER LOOP IN LANE.
- COIL 10' OF CABLES IN THE PULL BOX.

REVISOR	DATE	REVISION
TERI ANDERSON		
BEN PAULL		
CALCULATED/DESIGNED BY	CHECKED BY	FUNCTIONAL SUPERVISOR
		ROB STINGER
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION		
Electrical DESIGN		



ID No. R7
PM R17.11



ID No. R8
PM R17.534

MODIFY TRAFFIC MONITORING STATION (COUNT)
NO SCALE

APPROVED FOR ELECTRICAL WORK ONLY

E-5

P:\proj\3\02\0h000\plans\pse\20h000\006.dgn
 STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans ELECTRICAL DESIGN
 FUNCTIONAL SUPERVISOR
 ROB STINGER
 CALCULATED/DESIGNED BY
 CHECKED BY
 TERI ANDERSON
 BEN PAULL
 REVISED BY
 DATE REVISED

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	27	48

01-08-15
 REGISTERED CIVIL ENGINEER DATE
 01-08-15
 PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER
 THERESA ANDERSON
 No. C77957
 Exp. 6-30-15
 CIVIL
 STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

MODIFY SIGNAL

SHEET No.	DLC	TYPE D LOOP	TYPE A LOOP
	FT	EA	EA
E-1	2,950	1	7
E-2	1,110	3	13

ITEMS SHOWN IN THIS TABLE ARE NOT A SEPARATE PAY ITEM, FOR INFORMATION ONLY

MODIFY TRAFFIC MONITORING STATION (COUNT)

SHEET No.	TYPE A LOOP	10' x 6' LOOP DETECTOR
	EA	EA
E-3	3	
E-4	2	1
E-5	6	

ITEMS SHOWN IN THIS TABLE ARE NOT A SEPARATE PAY ITEM, FOR INFORMATION ONLY

MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION

TYPE	PM	DESCRIPTION
HAR	Sha-5-PM R16.13	I-5 AT HILLTOP OVERCROSSING
CCTV	Sha-5-PM R17.3	NEAR I-5/299 INTERCHANGE
CCTV	Sha-5-PM R18.6	NEAR I-5/273 INTERCHANGE
FIBER OPTIC	Sha-5-PM R16.2/R18.6	LOCATED IN THE MEDIAN

ELECTRICAL QUANTITIES

E-6

LAST REVISION | DATE PLOTTED => 09-JAN-2015
 01-08-15 | TIME PLOTTED => 14:27

	M	
Maint	MAINTENANCE	
Max	MAXIMUM	
MB	METAL BEAM	
MBB	METAL BEAM BARRIER	
MBGR	METAL BEAM GUARD RAILING	
Med	MEDIAN	
MGS	MIDWEST GUARDRAIL SYSTEM	
MH	MANHOLE	
Min	MINIMUM	
Misc	MISCELLANEOUS	
Misc I & S	MISCELLANEOUS IRON AND STEEL	
Mkr	MARKER	
Mod	MODIFIED, MODIFY	
Mon	MONUMENT	
MP	METAL PLATE	
MPGR	METAL PLATE GUARD RAILING	
MR	MOVEMENT RATING	
MSE	MECHANICALLY STABILIZED EMBANKMENT	
Mt	MOUNTAIN, MOUNT	
MtI	MATERIAL	
MVP	MAINTENANCE VEHICLE PULLOUT	
	N	
N	NORTH	
NB	NORTHBOUND	
No.	NUMBER (MUST HAVE PERIOD)	
Nos.	NUMBERS (MUST HAVE PERIOD)	
NPS	NOMINAL PIPE SIZE	
NS	NEAR SIDE	
NSP	NEW STANDARD PLAN	
NTS	NOT TO SCALE	
	O	
Obir	OBLITERATE	
OC	OVERCROSSING	
OD	OUTSIDE DIAMETER	
OF	OUTSIDE FACE	
OG	ORIGINAL GROUND	
OGAC	OPEN GRADED ASPHALT CONCRETE	
OGFC	OPEN GRADED FRICTION COURSE	
OH	OVERHEAD	
OHWM	ORDINARY HIGH WATER MARK	
O-O	OUT TO OUT	
Opp	OPPOSITE	
OSD	OVERSIDE DRAIN	
	P	
p	PAGE	
PAP	PERFORATED ALUMINUM PIPE	
PB	PULL BOX	
PC	POINT OF CURVATURE, PRECAST	
PCC	POINT OF COMPOUND CURVE, PORTLAND CEMENT CONCRETE	
PCMS	PORTABLE CHANGEABLE MESSAGE SIGN	
PCP	PERFORATED CONCRETE PIPE, PRESTRESSED CONCRETE PIPE	
PCVC	POINT OF COMPOUND VERTICAL CURVE	
PEC	PERMIT TO ENTER AND CONSTRUCT	
Ped	PEDESTRIAN	
Ped OC	PEDESTRIAN OVERCROSSING	
Ped UC	PEDESTRIAN UNDERCROSSING	
Perm MtI	PERMEABLE MATERIAL	

	P continued	
PG	PROFILE GRADE	
PI	POINT OF INTERSECTION	
PJP	PARTIAL JOINT PENETRATION	
Pkwy	PARKWAY	
PL, PL	PLATE	
P/L	PROPERTY LINE	
PM	POST MILE, TIME FROM NOON TO MIDNIGHT	
PN	PAVING NOTCH	
POC	POINT OF HORIZONTAL CURVE	
POT	POINT OF TANGENT	
POVC	POINT OF VERTICAL CURVE	
PP	PIPE PILE, PLASTIC PIPE, POWER POLE	
PPL	PREFORMED PERMEABLE LINER	
PPP	PERFORATED PLASTIC PIPE	
PRC	POINT OF REVERSE CURVE	
PRF	PAVEMENT REINFORCING FABRIC	
PRVC	POINT OF REVERSE VERTICAL CURVE	
PS&E	PLANS, SPECIFICATIONS AND ESTIMATES	
PS, P/S	PRESTRESSED	
PSP	PERFORATED STEEL PIPE	
PT	POINT OF TANGENCY	
PVC	POLYVINYL CHLORIDE	
Pvmt	PAVEMENT	
	Q	
Qty	QUANTITY	
	R	
R	RADIUS	
R & D	REMOVE AND DISPOSE	
R & S	REMOVE AND SALVAGE	
R/C	RATE OF CHANGE	
RCA	REINFORCED CONCRETE ARCH	
RCB	REINFORCED CONCRETE BOX	
RCP	REINFORCED CONCRETE PIPE	
RCPA	REINFORCED CONCRETE PIPE ARCH	
Rd	ROAD	
Reinf	REINFORCED, REINFORCEMENT, REINFORCING	
Rel	RELOCATE	
Repl	REPLACEMENT	
Ret	RETAINING	
Rev	REVISED, REVISION	
Rdwy	ROADWAY	
RHMA	RUBBERIZED HOT MIX ASPHALT	
Riv	RIVER	
RM	ROAD-MIXED	
RP	RADIUS POINT, REFERENCE POINT	
RR	RAILROAD	
RSP	ROCK SLOPE PROTECTION, REVISED STANDARD PLAN	
Rt	RIGHT	
Rte	ROUTE	
RW	REDWOOD, RETAINING WALL	
R/W	RIGHT OF WAY	
Rwy	RAILWAY	

	S	
S	SOUTH, SUPPLEMENT	
SAE	STRUCTURE APPROACH EMBANKMENT	
Salv	SALVAGE	
SAPP	STRUCTURAL ALUMINUM PLATE PIPE	
SB	SOUTHBOUND	
SC	SAND CUSHION	
SCSP	SLOTTED CORRUGATED STEEL PIPE	
SD	STORM DRAIN	
Sec	SECOND, SECTION	
Sep	SEPARATION	
SG	SUBGRADE	
Shld	SHOULDER	
Sht	SHEET	
Sim	SIMILAR	
SL	STATION LINE	
SM	SELECTED MATERIAL	
Spec	SPECIAL, SPECIFICATIONS	
SPP	SLOTTED PLASTIC PIPE	
SS	SLOPE STAKE	
SSBM	STRAP AND SADDLE BRACKET METHOD	
SSD	STRUCTURAL SECTION DRAIN	
SSPA	STRUCTURAL STEEL PLATE ARCH	
SSPP	STRUCTURAL STEEL PLATE PIPE	
SSPPA	STRUCTURAL STEEL PLATE PIPE ARCH	
SSRP	STEEL SPIRAL RIB PIPE	
St	STREET	
Sta	STATION	
STBB	SINGLE THRIE BEAM BARRIER	
Std	STANDARD	
Str	STRUCTURE	
Surf	SURFACING	
SW	SIDEWALK, SOUND WALL	
Swr	SEWER	
Sym	SYMMETRICAL	
S4S	SURFACE 4 SIDES	
	T	
T	SEMI-TANGENT	
Tan	TANGENT	
TBB	THRIE BEAM BARRIER	
Tbr	TIMBER	
TC	TOP OF CURB	
TCB	TRAFFIC CONTROL BOX	
TCE	TEMPORARY CONSTRUCTION EASEMENT	
Tel	TELEPHONE	
Temp	TEMPORARY	
TG	TOP OF GRADE	
To+	TOTAL	
TP	TELEPHONE POLE	
TPB	TREATED PERMEABLE BASE	
TPM	TREATED PERMEABLE MATERIAL	
Trans	TRANSITION	

	T continued	
TS	TRANSVERSE, TRAFFIC SIGNAL, TUBULAR STEEL	
Typ	TYPICAL	U
UC	UNDERCROSSING	
UD	UNDERDRAIN	
UG	UNDERGROUND	
UON	UNLESS OTHERWISE NOTED	
UP	UNDERPASS	V
V	VALVE, DESIGN SPEED	
Var	VARIABLE, VARIES	
VC	VERTICAL CURVE	
VCP	VITRIFIED CLAY PIPE	
Vert	VERTICAL	
Via	VIADUCT	
Vol	VOLUME	W
W	WEST, WIDTH	
WB	WESTBOUND	
WH	WEEP HOLE	
WM	WIRE MESH	
WS	WATER SURFACE	
WSP	WELDED STEEL PIPE	
W+	WEIGHT	
WV	WATER VALVE	
WW	WINGWALL	
WWL	WINGWALL LAYOUT LINE	X
X Sec	CROSS SECTION	
Xing	CROSSING	Y
Yr	YEAR	
Yrs	YEARS	

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	28	48

Grace M. Tsushima
REGISTERED CIVIL ENGINEER

REGISTERED PROFESSIONAL ENGINEER
 Grace M. Tsushima
 No. C49814
 Exp. 9-30-14
 CIVIL
 STATE OF CALIFORNIA

July 19, 2013
PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 01-08-15

UNIT OF MEASUREMENT SYMBOLS:

Some of the symbols used in the project plan quantity tables and in the Bid Item List are:

TABLE A

SYMBOL USED	DEFINITIONS
ACRE	ACRE
CF	CUBIC FOOT
CY	CUBIC YARD
EA	EACH
GAL	GALLON
LB	POUND
LF	LINEAR FOOT
SQFT	SQUARE FOOT
SQYD	SQUARE YARD
STA	100 FEET
TAB	TABLET
TON	2,000 POUNDS

Some of the symbols used in the plans other than in the project plan quantity tables are:

TABLE B

SYMBOL USED	DEFINITIONS
ksi	KIPS PER SQUARE INCH
ksf	KIPS PER SQUARE FOOT
psi	POUNDS PER SQUARE INCH
psf	POUNDS PER SQUARE FOOT
lb/ft ³ , pcf	POUNDS PER CUBIC FOOT
tsf	TONS PER SQUARE FOOT
mph, MPH *	MILES PER HOUR
ø	NOMINAL DIAMETER
oz	OUNCE
lb	POUND
kíp	1,000 POUNDS
cal	CALORIE
ft	FOOT OR FEET
gal	GALLON

* For use on a sign panel only

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION


**ABBREVIATIONS
(SHEET 2 OF 2)**

NO SCALE


RSP A10B DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN A10B
DATED MAY 20, 2011 - PAGE 2 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A10B


EXIT RAMP NEUTRAL AREA (GORE) TREATMENT




ENTRANCE RAMP NEUTRAL AREA (MERGE) TREATMENT



ENTRANCE RAMP NEUTRAL AREA (ACCELERATION LANE) TREATMENT



MARKER DETAILS



LEGEND:

- MARKERS
- TYPE A WHITE NON-REFLECTIVE
 - ◻ TYPE C RED-CLEAR RETROREFLECTIVE
 - TYPE G ONE-WAY CLEAR RETROREFLECTIVE

RETROREFLECTIVE FACE

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	29	48



Registered Professional Engineer
Roberta L. McLaughlin
 No. C40375
 Exp. 3-31-15
 CIVIL
 STATE OF CALIFORNIA

July 19, 2013
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



TO ACCOMPANY PLANS DATED 01-08-15

LANE DROP AT EXIT RAMP



* The solid channelizing line shown may be omitted on short auxiliary lanes where weaving length is critical.

LANE DROP AT INTERSECTIONS



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKERS AND TRAFFIC LINE TYPICAL DETAILS

NO SCALE

RSP A20C DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN A20C DATED MAY 20, 2011 - PAGE 11 OF THE STANDARD PLANS BOOK DATED 2010.


REVISED STANDARD PLAN RSP A20C

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	30	48


Roberto L. McLaughlin
 REGISTERED CIVIL ENGINEER
 April 20, 2012
 PLANS APPROVAL DATE
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
 Roberto L. McLaughlin
 No. C40375
 Exp. 3-31-13
 CIVIL
 STATE OF CALIFORNIA


TO ACCOMPANY PLANS DATED 01-08-15




A=25 ft²
TYPE I 18'-0" ARROW




A=31 ft²
TYPE I 24'-0" ARROW




A=14 ft²
TYPE I 10'-0" ARROW




A=15 ft²
TYPE IV (L) ARROW
(For Type IV (R) arrow, use mirror image)




A=42 ft²
TYPE VI ARROW
Right lane drop arrow
(For left lane, use mirror image)




A=3.5 ft²
BIKE LANE ARROW



A=36 ft²
TYPE VIII ARROW



A=27 ft²
TYPE VII (L) ARROW
(For Type VII (R) arrow, use mirror image)



A=33 ft²
TYPE V ARROW

NOTE:
Minor variations in dimensions may be accepted by the Engineer.


STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
**PAVEMENT MARKINGS
ARROWS**
NO SCALE

RSP A24A DATED APRIL 20, 2012 SUPERSEDES STANDARD PLAN A24A DATED MAY 20, 2011 - PAGE 13 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A24A

2010 REVISED STANDARD PLAN RSP A24A


TO ACCOMPANY PLANS DATED 01-08-15




$A=24 \text{ ft}^2$




$A=27 \text{ ft}^2$




$A=21 \text{ ft}^2$




$A=22 \text{ ft}^2$




$A=14 \text{ ft}^2$




$A=23 \text{ ft}^2$




$A=24 \text{ ft}^2$



$A=20 \text{ ft}^2$




$A=16 \text{ ft}^2$



$A=17 \text{ ft}^2$

WORD MARKINGS			
ITEM	ft ²	ITEM	ft ²
LANE	24	NO	14
POOL	23	BIKE	21
CAR	17	BUS	20
CLEAR	27	ONLY	22
KEEP	24	FWY	16



$A=2 \text{ ft}^2$
See Notes 6 and 7



LIMIT LINE (STOP LINE)



YIELD LINE

NOTES:

- If a message consists of more than one word, it should read "UP", i.e., the first word should be nearest the driver.
- The space between words should be at least four times the height of the characters for low speed roads, but not more than ten times the height of the characters. The space may be reduced appropriately where there is limited space because of local conditions.
- Minor variations in dimensions may be accepted by the Engineer.
- Portions of a letter, number or symbol may be separated by connecting segments not to exceed 2" in width.
- The words "NO PARKING" pavement marking is to be used for parking facilities. For typical locations of markings, see Standard Plans A90A and A90B.
- The words "NO PARKING", shall be painted in white letters no less than 1'-0" high on a contrasting background and located so that it is visible to traffic enforcement officials.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**PAVEMENT MARKINGS
WORDS, LIMIT AND YIELD LINES**

NO SCALE





RSP A24E DATED JULY 20, 2012 SUPERSEDES STANDARD PLAN A24E
DATED MAY 20, 2011 - PAGE 17 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A24E

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	32	48

Roberta L. McLaughlin
 REGISTERED CIVIL ENGINEER
 July 20, 2012
 PLANS APPROVAL DATE
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


TO ACCOMPANY PLANS DATED 01-08-15



HIGHER VISIBILITY CROSSWALKS

NOTES:

1. Spaces between markings should be placed in wheel tracks of each lane.
2. Spacings not to exceed 2.5 times width of longitudinal line.
3. All crosswalk markings must be white except for those near schools must be yellow.



BASIC

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
**PAVEMENT MARKINGS
CROSSWALKS**

NO SCALE
RSP A24F DATED JULY 20, 2012 SUPPLEMENTS THE
STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A24F




DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	33	48

Randell D. Hiatt
REGISTERED CIVIL ENGINEER

July 19, 2013
PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


TO ACCOMPANY PLANS DATED 01-08-15



NOTES:


- For details of steel post installations, see Revised Standard Plan RSP A77L2.
- For details of standard hardware used to construct MGS, see Revised Standard Plan RSP A77M1.
- For details of wood posts and wood blocks used to construct MGS, see Revised Standard Plan RSP A77N1.
- For additional installation details, see Revised Standard Plan RSP A77N3.
- MGS post spacing to be 6'-3" center to center, except as otherwise noted.
- For MGS typical layouts, see the A77P, A77Q and A77R Series of Standard Plans.
- If railing is connected to terminal system end treatment, use 31" height terminal system end treatment.
- For MGS end anchor details, see Revised Standard Plans RSP A77S1 and RSP A77T2.
- For details of MGS transition to bridge railing, see Revised Standard Plan RSP A77U4.
- For additional details of MGS connection to bridge railing, see Revised Standard Plans RSP A77U1, RSP A77U2 and RSP A77V1.
- For MGS connection details to abutments and walls, see Revised Standard Plan RSP A77U3.
- For typical MGS delineation and dike positioning details, see Revised Standard Plan RSP A77N4.
- Slotted hole for bolted connection of rail element to block and post. See "Section Thru Rail Element".
- Slotted holes for splice bolts to overlap ends of rail element. See "Section Thru Rail Element".
- Additional hole in uppermost portion of line post is for potential future adjustments of railing height. See Revised Standard Plan RSP A77N1.
- Install posts in soil.

MIDWEST GUARDRAIL SYSTEM WITH WOOD POST AND BLOCKS



ELEVATION RAIL ELEMENT SPLICE DETAIL

- Connect the over lapped end of the rail elements with $5/8"$ ϕ \times $1 3/8"$ button head oval shoulder splice bolts inserted into the $7/32"$ \times $1 1/8"$ slots and bolted together with $5/8"$ ϕ recessed hex nuts. Recess of hex nut points toward rail element. A total of 8 bolts and nuts are to be used at each rail splice connection.
- The ends of the rail elements are to be overlapped in the direction of traffic (see details).
- Where end cap is to be attached to the end of a rail element, a total of 4 of the above described splice bolts and nuts are to be used.



SECTION A-A TYPICAL WOOD LINE POST INSTALLATION
See Note 4

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
**MIDWEST GUARDRAIL SYSTEM
STANDARD RAILING SECTION
(WOOD POST WITH
WOOD BLOCK)**

NO SCALE

RSP A77L1 DATED JULY 19, 2013 SUPPLEMENTS STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A77L1

2010 REVISED STANDARD PLAN RSP A77L1

DATE PLOTTED => 09-JAN-2015
TIME PLOTTED => 14:28

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	34	48




Randell D. Hiatt
REGISTERED CIVIL ENGINEER

July 19, 2013
PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 01-08-15


REGISTERED PROFESSIONAL ENGINEER
No. C50200
Exp. 6-30-15
CIVIL
STATE OF CALIFORNIA




MIDWEST GUARDRAIL SYSTEM WITH STEEL POSTS AND NOTCHED WOOD OR NOTCHED RECYCLED PLASTIC BLOCKS

NOTES:

- For details of wood post installations, see Revised Standard Plan RSP A77L1.
- For details of standard hardware used to construct MGS, see Revised Standard Plan RSP A77M1.
- For details of steel posts and notched wood blocks used to construct MGS, see Revised Standard Plan RSP A77N2.
- For additional installation details, see Revised Standard Plan RSP A77N3.
- MGS post spacing to be 6'-3" center to center, except as otherwise noted.
- For MGS typical layouts, see the A77P, A77Q and A77R Series of Standard Plans.
- If railing is connected to terminal system end treatment, use 31" height terminal system end treatment.
- For MGS end anchor details, see Revised Standard Plans RSP A77S1 and RSP A77T2.
- For details of MGS transition to bridge railing, see Revised Standard Plan RSP A77U4.
- For additional details of MGS connection to bridge railings, see Revised Standard Plans RSP A77U1, RSP A77U2 and RSP A77V1.
- For dike positioning and MGS delineation details, see Revised Standard Plan RSP A77N4.
- Notched face of block faces steel post.
- Slotted hole for bolted connection of rail element to block and post. See "Section Thru Rail Element".
- Slotted holes for splice bolts to overlap ends of rail element. See "Section Thru Rail Element".
- Install posts in soil.



- Connect the over lapped end of the rail elements with 5/8" ø x 1 3/8" button head oval shoulder splice bolts inserted into the 7/32" x 1 1/8" slots and bolted together with 5/8" ø recessed hex nuts. Recess of hex nut points toward rail element. A total of 8 bolts and nuts are to be used at each rail splice connection.
- The ends of the rail elements are to be overlapped in the direction of traffic (see details).
- Where end cap is to be attached to the end of a rail element, a total of 4 of the above described splice bolts and nuts are to be used.



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

MIDWEST GUARDRAIL SYSTEM STANDARD RAILING SECTION (STEEL POST WITH NOTCHED WOOD OR NOTCHED RECYCLED PLASTIC BLOCK)

NO SCALE

RSP A77L2 DATED JULY 19, 2013 SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.


REVISED STANDARD PLAN RSP A77L2

2010 REVISED STANDARD PLAN RSP A77L2

DATE PLOTTED => 09-JAN-2015
TIME PLOTTED => 14:28




TO ACCOMPANY PLANS DATED 01-08-15




TYPICAL RAIL ELEMENT

NOTE:

1. Slotted holes for splice bolts to overlap ends of rail element.



5/8" Ø RECESS NUT




5/8" Ø BUTTON HEAD BOLT


BUTTON HEAD BOLT

L	THREAD LENGTH
1 3/8"	FULL THREAD LENGTH
2"	FULL THREAD LENGTH
10"	4" Min THREAD LENGTH
18"	4" Min THREAD LENGTH
20"	4" Min THREAD LENGTH
22"	4" Min THREAD LENGTH
26"	4" Min THREAD LENGTH
36"	4" Min THREAD LENGTH
** 2 3/4"	2" Min THREAD LENGTH
** 19"	4" Min THREAD LENGTH

** For nested rail applications.



PLAN



ELEVATION
END CAP
(TYPE A)

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**MIDWEST GUARDRAIL SYSTEM
STANDARD HARDWARE**

NO SCALE

RSP A77M1 DATED JULY 19, 2013 SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A77M1

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	36	48




Randell D. Hiatt
REGISTERED CIVIL ENGINEER

July 19, 2013
PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.





REGISTERED PROFESSIONAL ENGINEER
No. C50200
Exp. 6-30-15
CIVIL
STATE OF CALIFORNIA

TO ACCOMPANY PLANS DATED 01-08-15



NOTES:

1. All holes in wood posts and blocks shall be 3/4" Dia ± 1/16".
2. Dimensions shown for wood post are nominal.
3. This post and block combination used for standard line post sections of MGS.
4. This post and 8" x 12" block combination used for line post sections of MGS on narrow roadways.
5. This post and 8" x 12" block combination is typically used where strengthened line post sections of MGS are warranted to shield fixed objects.
6. See Revised Standard Plan RSP A77L3 for use of 6" x 8" and 8" x 8" wood blocks.



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**MIDWEST GUARDRAIL SYSTEM
WOOD POST AND
WOOD BLOCK DETAILS**

NO SCALE

RSP A77N1 DATED JULY 19, 2013 SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A77N1

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	37	48

Randell D. Hiatt
REGISTERED CIVIL ENGINEER

November 15, 2013
PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


REGISTERED PROFESSIONAL ENGINEER
No. C50200
Exp. 6-30-15
CIVIL
STATE OF CALIFORNIA

TO ACCOMPANY PLANS DATED 01-08-15


NOTES:

1. All holes in steel post shall be $\frac{3}{8}$ " Dia maximum.
2. Dimensions shown for wood block are nominal.
3. Notched face of block faces steel post.
4. 6'-0" length posts to be used for typical roadway installation. See Revised Standard Plan RSP A77N3.
5. See Revised Standard Plan RSP A77L3 for use of 6" x 8" and 8" x 8" notched wood blocks.
6. This post and 8" x 12" block combination to be used for line post sections of MGS on narrow roadways and where strengthened line post sections of MGS are warranted to shield fixed objects.


2010 REVISED STANDARD PLAN RSP A77N2




**W6 x 9 OR W6 x 8.5
STEEL POST**
See Note 4




**6" x 12"
NOTCHED WOOD BLOCK**
See Notes 2 and 3




**6" x 8"
NOTCHED WOOD BLOCK**
Only for use with metal beam guard railing. See Note 5



**W6 x 15
STEEL POST**
See Note 6



**8" x 12"
NOTCHED WOOD BLOCK**
See Notes 2 and 3



**8" x 8"
NOTCHED WOOD BLOCK**
Only for use with metal beam guard railing. See Note 5

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**MIDWEST GUARDRAIL SYSTEM
STEEL POST AND
NOTCHED WOOD BLOCK DETAILS**


NO SCALE

RSP A77N2 DATED NOVEMBER 15, 2013 SUPERSEDES RSP A77N2
DATED JULY 19, 2013 THAT SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.


REVISED STANDARD PLAN RSP A77N2




TO ACCOMPANY PLANS DATED 01-08-15




TYPE A
See Note 3




TYPE C



TYPE D




TYPE E




TYPE F
See Note 5


DIKES




CASE C-1
Cut Slope



CASE C-2
Cut Slope



CASE F



CASE R
See Note 2

TYPE D AND E BACKFILL DETAILS

NOTES:

1. For HMA shoulders only, extend top layer of HMA placed on the shoulder under dike with no joint at the ES. For projects with OGFC shoulders, do not extend OGFC under dike. See project plans for modified dike detail.
2. Case R applies to retrofit only projects where restrictive conditions do not provide enough width for Case F backfill.
3. Type A dike only to be used where restrictive slope conditions do not provide enough width to use Type D or Type E dike.
4. Fill and compact with excavated material to top of dike.
5. Use Type F dike, where dike is required with guard railing installations. See Revised Standard Plan RSP A77N4 for dike positioning details.

DIKE QUANTITIES

TYPE	CUBIC YARDS PER LINEAR FOOT
A	0.0135
C	0.0038
D	0.0293
E	0.0130
F	0.0066

Quantities based on 5% cross slope.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION


HOT MIX ASPHALT DIKES

NO SCALE

RSP A87B DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN A87B
DATED MAY 20, 2011 - PAGE 120 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A87B

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	39	48


 REGISTERED CIVIL ENGINEER
 July 19, 2013
 PLANS APPROVAL DATE



THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 01-08-15

TABLE 1

SPEED (S)	MINIMUM TAPER LENGTH * FOR WIDTH OF OFFSET 12 FEET (W)				MAXIMUM CHANNELIZING DEVICE SPACING		
	TANGENT 2L	MERGING L	SHIFTING L/2	SHOULDER L/3	X	Y	Z **
					TAPER	TANGENT	CONFLICT
mph	ft	ft	ft	ft	ft	ft	ft
20	160	80	40	27	20	40	10
25	250	125	63	42	25	50	12
30	360	180	90	60	30	60	15
35	490	245	123	82	35	70	17
40	640	320	160	107	40	80	20
45	1080	540	270	180	45	90	22
50	1200	600	300	200	50	100	25
55	1320	660	330	220	55	110	27
60	1440	720	360	240	60	120	30
65	1560	780	390	260	65	130	32
70	1680	840	420	280	70	140	35

* - For other offsets, use the following merging taper length formula for L:
 For speed of 40 mph or less, $L = WS^2/60$
 For speed of 45 mph or more, $L = WS$

Where: L = Taper length in feet
 W = Width of offset in feet
 S = Posted speed limit, off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed in mph

** - Use for taper and tangent sections where there are no pavement markings or where there is a conflict between existing pavement markings and channelizers (CA).

TABLE 2

SPEED *	Min D **	DOWNGRADE Min D ***		
		-3%	-6%	-9%
		ft	ft	ft
mph	ft	ft	ft	ft
20	115	116	120	126
25	155	158	165	173
30	200	205	215	227
35	250	257	271	287
40	305	315	333	354
45	360	378	400	427
50	425	446	474	507
55	495	520	553	593
60	570	598	638	686
65	645	682	728	785
70	730	771	825	891

* - Speed is posted speed limit, off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed in mph
 ** - Longitudinal buffer space or flagger station spacing
 *** - Use on sustained downgrade steeper than -3 percent and longer than 1 mile.

TABLE 3

ROAD TYPE	DISTANCE BETWEEN SIGNS *		
	A	B	C
	ft	ft	ft
URBAN - 25 mph OR LESS	100	100	100
URBAN - MORE THAN 25 mph TO 40 mph	250	250	250
URBAN - MORE THAN 40 mph	350	350	350
RURAL	500	500	500
EXPRESSWAY / FREEWAY	1000	1500	2640

* - The distances are approximate, are intended for guidance purposes only, and should be applied with engineering judgment. These distances should be adjusted by the Engineer for field conditions, if necessary, by increasing or decreasing the recommended distances.

STATE OF CALIFORNIA
 DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL SYSTEM TABLES FOR LANE AND RAMP CLOSURES

NO SCALE

RSP T9 DATED JULY 19, 2013 SUPERSEDES RSP T9 DATED APRIL 19, 2013 THAT SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP T9

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	40	48


REGISTERED CIVIL ENGINEER
 April 19, 2013
 PLANS APPROVAL DATE
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
 Gurinderpal Bhullar
 No. C48815
 Exp. 9-30-14
 CIVIL
 STATE OF CALIFORNIA

TO ACCOMPANY PLANS DATED 01-08-15

NOTES:

See Revised Standard Plan RSP T9 for tables.
 Use cone spacing X for taper segment, Y for tangent segment or Z for conflict situations, as appropriate, per Table 1, unless X, Y, or Z cone spacing is shown on this sheet.
 Unless otherwise specified in the special provisions, all temporary warning signs shall have black legend on fluorescent orange background.
 California codes are designated by (CA). Otherwise, Federal (MUTCD) codes are shown.



NOTES:

- Median lane closures shall conform to the details as shown except that C20(CA)L and W4-2L signs shall be used.
- At least one person shall be assigned to provide full time maintenance of traffic control devices for lane closures.
- Duplicate sign installations are not required:
 - On opposite shoulder if at least one-half of the available lanes remain open to traffic.
 - In the median if the width of the median shoulder is less than 8' and the outside lanes are to be closed.
- Each advance warning sign on each side of the roadway shall be equipped with at least two flags for daytime closure. Each flag shall be at least 16" x 16" in size and shall be orange or fluorescent red-orange in color. Flashing beacons shall be placed at the locations indicated for lane closure during hours of darkness.
- A G20-2 "END ROAD WORK" sign, with minimum size of 48" x 24" as appropriate, shall be placed at the end of the lane closure unless the end of work area is obvious or ends within a larger project's limits.

SHOULDER CLOSURE

- If the W20-1 sign would follow within 2000' of a stationary W20-1 or G20-1 "ROAD WORK NEXT x MILES", use a C20(CA)L sign for the first advance warning sign.
- Place a C30(CA) sign every 2000' throughout length of lane closure.
- One flashing arrow sign for each lane closed. The flashing arrow signs shall be Type I.
- A minimum 1500' of sight distance shall be provided where possible for vehicles approaching the first flashing arrow sign. Lane closures shall not begin at top of crest vertical curve or on a horizontal curve.
- All cones used for lane closures during the hours of darkness shall be fitted with retroreflective bands (or sleeves) as specified in the specifications.
- Portable delineators, placed at one-half the spacing indicated for traffic cones may be used instead of cones for daytime closures only.

- Unless otherwise specified in the special provisions, a minimum of 3 cones shall be placed transversely across each closed lane and shoulder at each location where a taper across a traffic lane ends and every 2000' as shown on the "Lane Closure" detail. Two Type II barricades may be used instead of the 3 cones. The transverse alignment of the cones or barricades on the closed shoulder may be shifted from the transverse alignment to provide access to the work.
- Unless otherwise specified in the special provisions, the 2L tangent shown along lane lines shall be used between the L tapers required for each closed traffic lane.
- Unless otherwise specified in the special provisions, the E5-1 or SC18(CA) and W4-1 signs shall be used as shown.
- A W7-3aP "NEXT x MILES" plaque must be used if the shoulder closure extends beyond the distance that can be perceived by road users.

LEGEND

- TRAFFIC CONE
- TRAFFIC CONE (OPTIONAL TAPER)
- † TEMPORARY TRAFFIC CONTROL SIGN
- ⬢ FLASHING ARROW SIGN (FAS)
- ⬢ FAS SUPPORT OR TRAILER
- ⚡ PORTABLE FLASHING BEACON

SIGN PANEL SIZE (Min)

- A 48" x 48"
- B 72" x 60"
- C 36" x 30"

TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE ON FREEWAYS AND EXPRESSWAYS

NO SCALE
 RSP T10 DATED APRIL 19, 2013 SUPERSEDES STANDARD PLAN T10 DATED MAY 20, 2011 - PAGE 237 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP T10

TYPICAL RAMP CLOSURES

SIGN PANEL SIZE (Min)

- A 48" x 48"
- B 48" x 30"
- C 36" x 36"
- D 48" x 36"

LEGEND

- TRAFFIC CONE
- † TEMPORARY TRAFFIC CONTROL SIGN
- ‡ BARRICADES
- ⚡ PORTABLE FLASHING BEACON


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	41	48

Gurinderpal Bhullar
 REGISTERED CIVIL ENGINEER
 April 19, 2013
 PLANS APPROVAL DATE
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


TO ACCOMPANY PLANS DATED 01-08-15

NOTES:


- Barricades shall be Type I, II, or III for closures lasting one week or less and Type III for closures lasting longer than one week.
- In addition to placing the C19(CA) "RAMP CLOSED AHEAD" and C30(CA) "RAMP CLOSED" signs, black on orange overlay plates with the word "CLOSED" may be mounted, as directed by the Engineer, on all guide signs that refer to the closed ramp. The letter size on the overlay shall be the same as the guide sign.
- Each advance C19(CA) "RAMP CLOSED AHEAD" sign shall be equipped with at least two flags for daytime closure. Each flag shall be at least 16" x 16" in size and shall be orange or fluorescent red-orange in color. A flashing beacon shall be placed on top of the first C19(CA) sign during hours of darkness.
- All cones used for ramp closures during the hours of darkness shall be fitted with retroreflective bands (or sleeves) as specified in the specifications.
- Portable delineators, placed at one-half the spacing indicated for traffic cones, may be used instead of cones for daytime ramp closures only.
- At least one person shall be assigned to provide full time maintenance of traffic control devices, unless otherwise directed by the Engineer.
- The existing "EXIT" signs shall be covered during ramp closures.
- A minimum of 3 cones shall be placed transversely across each closed lane and shoulder.




EXIT RAMP OR CONNECTOR



EXIT RAMP OR CONNECTOR WITH ADDITIONAL LANE



ENTRANCE RAMP WITH TURNING POCKETS



ENTRANCE RAMP WITHOUT TURNING POCKETS

NOTES:

- See Revised Standard Plan RSP T9 for tables.
- Use cone spacing X for taper segment, Y for tangent segment or Z for conflict situations, as appropriate, per Table 1, unless X, Y, or Z cone spacing is shown on this sheet.
- Unless otherwise specified in the special provisions, all temporary warning signs shall have black legend on fluorescent orange background.
- California codes are designated by (CA). Otherwise, Federal (MUTCD) codes are shown.

STATE OF CALIFORNIA
 DEPARTMENT OF TRANSPORTATION
**TRAFFIC CONTROL SYSTEM
 FOR RAMP CLOSURE**
 NO SCALE

RSP T14 DATED APRIL 19, 2013 SUPERSEDES STANDARD PLAN T14
 DATED MAY 20, 2011 - PAGE 242 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP T14

LEGEND:

- AB** ABANDON. IF APPLIED TO CONDUIT, REMOVE CONDUCTORS
- BC** INSTALL PULL BOX IN EXISTING CONDUIT RUN
- BP** PEDESTRIAN BARRICADE, TYPE AS INDICATED ON PLAN
- CB** INSTALL CONDUIT INTO EXISTING PULL BOX
- CC** CONNECT NEW AND EXISTING CONDUIT. REMOVE EXISTING CONDUCTORS AND INSTALL CONDUCTORS AS INDICATED
- CF** CONDUIT TO REMAIN FOR FUTURE USE. REMOVE CONDUCTORS. INSTALL PULL TAPE
- DH** DETECTOR HANDHOLE
- FA** FOUNDATION TO BE ABANDONED
- IS** INSTALL SIGN ON SIGNAL MAST ARM
- NS** NO SLIP BASE ON STANDARD
- PEC** PHOTOELECTRIC CONTROL
- PEU** PHOTOELECTRIC UNIT
- RC** EQUIPMENT OR MATERIAL TO BE REMOVED AND BECOME THE PROPERTY OF THE CONTRACTOR
- RE** REMOVE ELECTROLIER, FUSES AND BALLAST. TAPE ENDS OF CONDUCTORS
- RL** RELOCATE EQUIPMENT
- RR** REMOVE AND REUSE EQUIPMENT
- RS** REMOVE AND SALVAGE EQUIPMENT
- SC** SPLICE NEW TO EXISTING CONDUCTORS
- SD** SERVICE DISCONNECT
- TSP** TELEPHONE SERVICE POINT

ABBREVIATIONS

- | | | | |
|-------|---|-------|--------------------------------------|
| APS | ACCESSIBLE PEDESTRIAN SIGNAL | M/M | MULTIPLE TO MULTIPLE TRANSFORMER |
| BBS | BATTERY BACKUP SYSTEM | Mtg | MOUNTING |
| BC | BOLT CIRCLE | MV | MERCURY VAPOR LIGHTING FIXTURE |
| BPB | BICYCLE PUSH BUTTON | MVDS | MICROWAVE VEHICLE DETECTION SYSTEM |
| C | CONDUIT | N | NEUTRAL (GROUNDED CONDUCTOR) |
| CB | CIRCUIT BREAKER | NB | NEUTRAL BUS |
| CCTV | CLOSED CIRCUIT TELEVISION | NC | NORMALLY CLOSE |
| Ck+ | CIRCUIT | NO | NORMALLY OPEN |
| CMS | CHANGEABLE MESSAGE SIGN | P | CIRCUIT BREAKER'S POLE |
| Ctid | CALTRANS IDENTIFICATION | PB | PULL BOX |
| Comm | COMMUNICATION | PBA | PUSH BUTTON ASSEMBLY |
| DLC | LOOP DETECTOR LEAD-IN CABLE | PEC | PHOTOELECTRIC CONTROL |
| EMS | EXTINGUISHABLE MESSAGE SIGN | Ped | PEDESTRIAN |
| EVUC | EMERGENCY VEHICLE UNIT CABLE | PEU | PHOTOELECTRIC UNIT |
| EVUD | EMERGENCY VEHICLE UNIT DETECTOR | PT | CONDUIT WITH PULL TAPE |
| FB | FLASHING BEACON | RE | RELOCATED EQUIPMENT |
| FBCA | FLASHING BEACON CONTROL ASSEMBLY | RM | RAMP METERING |
| FBS | FLASHING BEACON WITH SLIP BASE | RWIS | ROADSIDE WEATHER INFORMATION SYSTEM |
| FO | FIBER OPTIC | SB | SLIP BASE |
| G | EQUIPMENT GROUNDING CONDUCTOR | SIC | SIGNAL INTERCONNECT CABLE |
| GB | GROUND BUS | Sig | SIGNAL |
| GFCI | GROUND FAULT CIRCUIT INTERRUPTER | SMA | SIGNAL MAST ARM |
| HAR | HIGHWAY ADVISORY RADIO | SNS | STREET NAME SIGN |
| Hex | HEXAGONAL | SP | SERVICE POINT |
| HPS | HIGH PRESSURE SODIUM | TDC | TELEPHONE DEMARCATION CABINET |
| IISNS | INTERNALLY ILLUMINATED STREET NAME SIGN | TMS | TRAFFIC MONITORING STATION |
| ISL | INDUCTION SIGN LIGHTING | TOS | TRAFFIC OPERATIONS SYSTEM |
| LED | LIGHT EMITTING DIODE | Veh | VEHICLE |
| LMA | LUMINAIRE MAST ARM | VIVDS | VIDEO IMAGE VEHICLE DETECTION SYSTEM |
| LPS | LOW PRESSURE SODIUM | WIM | WEIGH-IN-MOTION |
| Ltg | LIGHTING | Xfmr | TRANSFORMER |
| Lum | LUMINAIRE | | |
| M | METERED | | |
| MAT | MAST ARM MOUNTING TOP ATTACHMENT | | |
| MAS | MAST ARM MOUNTING SIDE ATTACHMENT | | |

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	42	48

Theresa Gabriel
REGISTERED ELECTRICAL ENGINEER

July 19, 2013
PLANS APPROVAL DATE

Theresa
Aziz Gabriel
No. E15129
Exp. 6-30-14
ELECTRICAL
STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 01-08-15

SOFFIT AND WALL MOUNTED LUMINAIRES

- PENDANT, 70 W HPS UNLESS OTHERWISE SPECIFIED
- FLUSH, 70 W HPS UNLESS OTHERWISE SPECIFIED
- WALL SURFACE, 70 W HPS UNLESS OTHERWISE SPECIFIED
- EXISTING SOFFIT OR WALL LUMINAIRE TO REMAIN UNMODIFIED
- EXISTING SOFFIT OR WALL LUMINAIRE TO BE MODIFIED AS SPECIFIED

NOTE:
Arrow indicates "street side" of luminaire.

COMMONLY USED SYMBOLS FOR UNITED STATES CUSTOMARY UNITS OF MEASUREMENT:

SYMBOL USED	DEFINITIONS
Ω	OHMS
min	MINUTE
s	SECOND
bps	BITS PER SECOND
Bps	BYTES PER SECOND
A	AMPERE
V	VOLT
V(dc)	VOLT (DIRECT CURRENT)
V(ac)	VOLT (ALTERNATING CURRENT)
FC	FOOT - CANDLE
W	WATTS
VA	VOLT-AMPERE
M	MEGA
k	KILO
m	MILLI
μ	MICRO
P	PICO
Hz	HERTZ

MISCELLANEOUS ELECTROLIERS

NEW	EXISTING	
		LUMINAIRE ON WOOD POLE
		NON-STANDARD ELECTROLIER (SEE PROJECT NOTES OR PROJECT PLANS)
		CITY ELECTROLIER
		ELECTROLIER FOUNDATION (FUTURE INSTALLATION)

- NOTES:**
- HPS luminaires shall be 310 W HPS when installed on Type 21, 21D, 30, 31 and 32 Standards, unless otherwise specified. HPS luminaires shall be 200 W when installed on other type standards or poles, unless otherwise specified.
 - LED luminaires shall be 235 W when installed on Type 21, 21D, 30, 31 and 32 Standards, unless otherwise specified. LED luminaires shall be 165 W when installed on other type standards or poles, unless otherwise specified.
 - Luminaires shall be the cutoff type, ANSI Type III medium cutoff lighting distribution, unless otherwise specified.

STANDARD ELECTROLIER

NEW	EXISTING	STANDARD TYPE
		15
		15D
		15 STRUCTURE
		15D STRUCTURE
		21
		21D
		21 STRUCTURE
		21D STRUCTURE
		30
		31
		32

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**ELECTRICAL SYSTEMS
(LEGEND AND ABBREVIATIONS)**

NO SCALE

RSP ES-1A DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-1A DATED MAY 20, 2011 - PAGE 425 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP ES-1A

2010 REVISED STANDARD PLAN RSP ES-1A

DATE PLOTTED => 09-JAN-2015
TIME PLOTTED => 14:29

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	43	48

Theresa Gabriel
 REGISTERED ELECTRICAL ENGINEER
 July 19, 2013
 PLANS APPROVAL DATE
 No. E15129
 Exp. 6-30-14
 ELECTRICAL
 STATE OF CALIFORNIA

TO ACCOMPANY PLANS DATED 01-08-15

CONDUIT

NEW	EXISTING	
---	---	LIGHTING CONDUIT, UNLESS OTHERWISE INDICATED OR NOTED
---	---	TRAFFIC SIGNAL CONDUIT
---C---	---c---	COMMUNICATION CONDUIT
---T---	---t---	TELEPHONE CONDUIT
---F---	---f---	FIRE ALARM CONDUIT
---FO---	---fo---	FIBER OPTIC CONDUIT
---	---	CONDUIT TERMINATION
		CONDUIT RISER ATTACHED TO THE STRUCTURE OR SERVICE POLE

SIGNAL EQUIPMENT

NEW	EXISTING	
		PEDESTRIAN SIGNAL HEAD "C" INDICATES COUNTDOWN PEDESTRIAN HEAD
		PUSH BUTTON ASSEMBLY POST
		PEDESTRIAN BARRICADE
		VEHICLE SIGNAL HEAD (WITH BACKPLATE AND 3-SECTIONS: RED, YELLOW AND GREEN)
		VEHICLE SIGNAL HEAD WITH ANGLE VISOR
		MODIFICATIONS OF BASIC SYMBOL: "L" INDICATES ALL NON-ARROW SECTIONS LOUVERED "LG" INDICATES LOUVERED GREEN SECTION ONLY "PV" INDICATES ALL 12" SECTIONS PROGRAMMED VISIBILITY "8" INDICATES ALL 8" SECTIONS (ONLY WHEN SPECIFIED)
		VEHICLE SIGNAL HEAD CONSISTING OF RED, YELLOW AND GREEN LEFT ARROW SECTIONS
		VEHICLE SIGNAL HEAD CONSISTING OF RED AND YELLOW SECTIONS WITH AN UP GREEN ARROW SECTION
		VEHICLE SIGNAL HEAD (5 SECTION) CONSISTING OF RED, YELLOW AND GREEN SECTIONS WITH YELLOW AND GREEN RIGHT ARROW SECTIONS
		TYPE 15TS STANDARD WITH VEHICLE SIGNAL HEAD AND LUMINAIRE
		TYPE 21TS STANDARD WITH VEHICLE SIGNAL HEAD AND LUMINAIRE
		STANDARD WITH LUMINAIRE AND SIGNAL MAST ARMS AND ATTACHED VEHICLE SIGNAL HEADS
		TYPE 1 STANDARD WITH ATTACHED VEHICLE SIGNAL HEADS
		STANDARD WITH A SIGNAL MAST ARM, ATTACHED VEHICLE SIGNAL HEADS AND INTERNALLY ILLUMINATED STREET NAME SIGN
		CONTROLLER ASSEMBLY. DOOR INDICATES FRONT OF CABINET

SIGNAL EQUIPMENT Cont

NEW	EXISTING	
		GUARD POST
		TYPE 1 STANDARD WITH RAMP METERING SIGN
		OPTICAL DETECTOR FOR THE EMERGENCY VEHICLE DETECTION SYSTEM

NOTES:

- All signal sections shall be 12" unless shown otherwise.
- Signal heads shall be provided with backplates unless shown otherwise.

SERVICE EQUIPMENT

NEW	EXISTING	
---OH---	---oh---	OVERHEAD LINES
		WOOD POLE, "U" INDICATES UTILITY OWNED
		POLE GUY WITH ANCHOR
		UTILITY TRANSFORMER - GROUND MOUNTED
		SERVICE EQUIPMENT ENCLOSURE TYPE. DOOR INDICATES FRONT OF ENCLOSURE
		TELEPHONE DEMARCATION CABINET

POLE-MOUNTED SERVICE DESIGNATION

	TYPE H SERVICE, 28'-10"	TYPE OF INSTALLATION AND POLE HEIGHT ABOVE GRADE
--	-------------------------	--

FLASHING BEACON

NEW	EXISTING	
		FLASHING BEACON (ONE VEHICLE SIGNAL HEAD WITH BACKPLATE AND VISOR) "R" INDICATES RED INDICATION, "Y" INDICATES YELLOW INDICATION
		FLASHING BEACON WITH TYPE 15-FBS STANDARD AND A SIGN.
		FLASHING BEACON WITH TYPES 9, 9A OR 9B SIGN UNLESS OTHERWISE SPECIFIED OR INDICATED

ILLUMINATED OVERHEAD SIGN

NEW	EXISTING	
		SINGLE POST, SINGLE ILLUMINATED SIGN, BALANCED BUTTERFLY
		SINGLE POST, DOUBLE ILLUMINATED SIGN, BALANCED BUTTERFLY
		SINGLE POST, SINGLE ILLUMINATED SIGN, FULL CANTILEVER
		DOUBLE POST, SINGLE ILLUMINATED SIGN
		SINGLE ILLUMINATED SIGN MOUNTED ON STRUCTURE
		DOUBLE POST, SINGLE ILLUMINATED SIGN WITH ELECTROLIER

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

ELECTRICAL SYSTEMS (LEGEND AND ABBREVIATIONS)


NO SCALE

RSP ES-1B DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-1B DATED MAY 20, 2011 - PAGE 426 OF THE STANDARD PLANS BOOK DATED 2010.


REVISED STANDARD PLAN RSP ES-1B

EQUIPMENT IDENTIFICATION


ILLUMINATED SIGN IDENTIFICATION NUMBER:




ELECTROLIER OR EQUIPMENT IDENTIFICATION NUMBER:




CONDUIT AND CONDUCTOR IDENTIFICATION:




SIGNAL AND LIGHTING STANDARD (TYPICAL DESIGNATION):




MISCELLANEOUS EQUIPMENT





WIRING DIAGRAM LEGEND



PULL BOXES



VEHICLE DETECTORS



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

ELECTRICAL SYSTEMS (LEGEND AND ABBREVIATIONS)

NO SCALE

RSP ES-1C DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-1C DATED MAY 20, 2011 - PAGE 427 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP ES-1C

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	45	48


Theresa Gabriel
REGISTERED ELECTRICAL ENGINEER

July 19, 2013
PLANS APPROVAL DATE

Theresa Aziz Gabriel
No. E15129
Exp. 6-30-14
ELECTRICAL
STATE OF CALIFORNIA


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 01-08-15




WINDING DETAIL SAWCUT DETAIL

TYPE A LOOP DETECTOR CONFIGURATION




WINDING DETAIL SAWCUT DETAIL

TYPE B LOOP DETECTOR CONFIGURATION




WINDING DETAIL SAWCUT DETAIL

TYPE C LOOP DETECTOR CONFIGURATION




WINDING DETAIL SAWCUT DETAIL

TYPE D LOOP DETECTOR CONFIGURATION




WINDING DETAIL SAWCUT DETAIL

TYPE E LOOP DETECTOR CONFIGURATION



WINDING DETAIL SAWCUT DETAIL

TYPE Q LOOP DETECTOR CONFIGURATION



PLAN VIEW OF DIAGONAL SLOT AT CORNERS

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

ELECTRICAL SYSTEMS (DETECTORS)

NO SCALE

RSP ES-5B DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-5B DATED MAY 20, 2011 - PAGE 449 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP ES-5B

- NOTES:**
1. Round corners of acute angle sawcuts to prevent damage to conductors.
 2. Typical distance separating loops from edge to edge is 10' for Type A, B, D and E installation in single lane.

2010 REVISED STANDARD PLAN RSP ES-5B

DATE PLOTTED => 08-JAN-2015
TIME PLOTTED => 14:29

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	46	48


Theresa Gabriel
 REGISTERED ELECTRICAL ENGINEER
 July 19, 2013
 PLANS APPROVAL DATE
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
 Theresa Aziz Gabriel
 No. E15129
 Exp. 6-30-14
 ELECTRICAL
 STATE OF CALIFORNIA


TO ACCOMPANY PLANS DATED 01-08-15

NOTES:


1. Back casting shape to fit curvature of pole.
2. Provide cover fitting for top of post, when PBA is mounted on push button assembly post.
3. Install push button on crosswalk side of standard.
4. Use R10 series regulatory signs and plaques for pedestrian and bicycle facilities.





ACCESSIBLE PEDESTRIAN SIGNAL
DETAIL A
 (See note 1 to 4)




TYPE B PUSH BUTTON ASSEMBLY
DETAIL B
 (See note 1 to 4)



TYPE C PUSH BUTTON ASSEMBLY
DETAIL C
 (See note 1 to 4)



MAGNETIC VEHICLE DETECTOR
INSTALLATION DETAILS
DETAIL D



STATE OF CALIFORNIA
 DEPARTMENT OF TRANSPORTATION
ELECTRICAL SYSTEMS
(ACCESSIBLE PEDESTRIAN SIGNAL,
PUSH BUTTON ASSEMBLIES AND
MAGNETIC VEHICLE DETECTOR)
 NO SCALE

RSP ES-5C DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-5C
 DATED MAY 20, 2011 - PAGE 450 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP ES-5C

2010 REVISED STANDARD PLAN RSP ES-5C


DATE PLOTTED => 08-JAN-2015
 TIME PLOTTED => 14:30

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	47	48


Theresa Gabriel
 REGISTERED ELECTRICAL ENGINEER
 July 19, 2013
 PLANS APPROVAL DATE
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
 Theresa Aziz Gabriel
 No. E15129
 Exp. 6-30-14
 ELECTRICAL
 STATE OF CALIFORNIA


TO ACCOMPANY PLANS DATED 01-08-15




**TYPE A
CURB TERMINATION DETAIL**




**"T" TRENCH
DETAIL T**



CROSS SECTION




PLAN VIEW



SECTION C-C


**TYPE B
CURB TERMINATION DETAIL**




CROSS SECTION




**PLAN VIEW
SHOULDER TERMINATION DETAILS**




DETECTOR HANDHOLE DETAIL



SECTION A-A



**PLAN VIEW
TYPICAL LOOP LEAD-IN DETAIL
AT PAVEMENT JOINT**



LOCKING GRADE RING

NOTES:

- Bushing shall be used at end of conduit.
- Tape detector conductors or cables 3" each side of bushings.
- Install duct seal compound to each end of termination conduit before installing sealant.
- Round all sharp edges where detector conductors or cables have to pass.
- End of conduit shall be 3/8" below roadway surface.
- | | |
|-----------------|-----------------|
| Conduit size | Loop conductors |
| 1"C minimum | 1 to 2 pairs |
| 1 1/2"C minimum | 3 to 4 pairs |
| 2"C minimum | 5 or more pairs |
- Splice detector conductors or cables to detector lead-in-cable.
- Location of detector handhole when shown on plans.
- When the shoulder and traveled way are paved with the same material and there is no joint between them, the conduit shall extend only 2'-0" into the shoulder pavement.
- 3/4"C, Type 3 conduit 6" long minimum, plug both ends with duct compound to keep out sealant.
- 1/2" Minimum between top of conduit and pavement surface.
- Sawcut shall not exceed 1" in width and 1/8" longer than conduit to be installed.
- Conductors with 1/2" minimum slack inside conduit.
- Inductive loop detector saw slot.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
**ELECTRICAL SYSTEMS
(CURB TERMINATION
AND HANDHOLE)**
NO SCALE

RSP ES-5D DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-5D
DATED MAY 20, 2011 - PAGE 451 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP ES-5D

2010 REVISED STANDARD PLAN RSP ES-5D

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
02	Sha	5,273	R16.2/R19.0 19.7/20.0	48	48


Theresa Gabriel
REGISTERED ELECTRICAL ENGINEER

July 19, 2013
PLANS APPROVAL DATE




Theresa Aziz Gabriel
No. E15129
Exp. 6-30-14
ELECTRICAL
STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 01-08-15



INSTALLATION DETAILS
DETAIL A



NOTES:

- Pull box covers shall be marked as follows: "SERVICE" Service circuits between service point and service disconnect; "SPRINKLER-CONTROL" sprinkler control circuits, 50 V or less; "CALTRANS" on all pull boxes, except pull boxes marked "SPRINKLER-CONTROL"; and "TELEPHONE" Telephone service;
 - No. 3 1/2 pull box.
 - "SIGNAL" - Traffic signal circuits with or without lighting or sign lighting circuits.
 - "LIGHTING" - Lighting or sign lighting circuits where voltage is under 600 V.
 - No. 5, 6, 9 or 9A pull box.
 - "TRAFFIC SIGNAL" - Traffic signal circuits with or without lighting or sign lighting circuits.
 - "LIGHTING" - Lighting or sign lighting circuits where voltage is under 600 V.
 - "LIGHTING-HIGH VOLTAGE" - Lighting or sign lighting circuits where voltage is above 600 V.
 - "IRRIGATION" - Circuits to irrigation controller 120 V or more.
 - "RAMP METER" - Ramp meter circuits.
 - "COUNT STATION" - Count or speed monitor circuits.
 - "COMMUNICATIONS" - Communication circuits.
 - "TOS COMMUNICATIONS" - TOS communication line.
 - "TOS POWER" - TOS power.
 - "TDC POWER" - Telephone demarcation cabinet power.
 - "CCTV" - Closed circuit television circuits.
 - "TMS" - Traffic monitoring station circuits.
 - "CMS" - Changeable message sign circuits.
 - "HAR" - Highway advisory radio circuits.
 - "BOOSTER PUMP" - Booster pump circuit.
- The nominal dimensions of the opening in which the cover sets shall be the same as the cover dimensions except the length and width dimensions shall be 1/8" greater.
- Covers and boxes shall be interchangeable with California standard male and female gages. When interchanged with a standard male or female gage, the top surfaces shall be flush within 1/8". Top outside radius of covers and pull boxes shall have a 1/8" radius.
- Pull box extension may be another pull box as long as the bottom edge of the pull box can fit into the cover opening.
- All dimensions for the cover for non-traffic pull box are nominal values.

DIMENSION TABLE										
PULL BOX	PULL BOX			COVER						
	MINIMUM DEPTH BOX	MINIMUM DEPTH EXTENSION	MAXIMUM WEIGHT	L	W	R	TE	TA	D	MAXIMUM WEIGHT
No. 3 1/2	12"	N/A	40 lb	1' - 3 3/8"	10 1/8"	1 3/8"	2"	1/8"	1 3/4"	30 lb
No. 5	12"	10"	55 lb	1' - 11 1/4"	1' - 1 3/4"	1 3/8"	2"	1/8"	1 3/4"	60 lb
No. 6	12"	10"	70 lb	2' - 6 1/2"	1' - 5 1/2"	1 3/8"	2"	1/8"	2"	85 lb

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
ELECTRICAL SYSTEMS
(NON-TRAFFIC PULL BOX)
NO SCALE

RSP ES-8A DATED JULY 19, 2013 SUPERSEDES RSP ES-8A DATED JANUARY 20, 2012 THAT SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP ES-8A