

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that Caltrans does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders and non-bidder packages, write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone and fax number, P.O. Box and street address so that you can receive addenda.

Note: Addenda information is NOT included with the electronic documents available via electronic file transfer. Only bidder or non-bidder package holders listed with the Caltrans Plans and Bid Documents section as described above will receive addenda information.



STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

**NOTICE TO CONTRACTORS
AND
SPECIAL PROVISIONS**

FOR BUILDING CONSTRUCTION IN

PLUMAS COUNTY IN QUINCY AT THE QUINCY MAINTENANCE STATION AT 1555 EAST MAIN STREET

DISTRICT 02, ROUTES 5727

For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labor Surcharge and Equipment Rental Rates.

CONTRACT NO. 02-341804

02-Plu-5727-

Bids Open: October 3, 2000
Dated: August 28, 2000

OSD

IMPORTANT SPECIAL NOTICES

- Attention is directed to the Notice to Contractor and Section 1, "Plans and Specifications," of the special provisions regarding references to the District and District Director's Office. The Office of the District Director for the Northern Region is located at Marysville.

- **SURETY 2000**

Caltrans is conducting a pilot program in cooperation with Surety 2000, to test electronic bond verification systems. The purpose of the pilot program is to test the use of Surety 2000 for verifying a bidder's bond electronically.

Surety 2000 is an Internet-based surety verification and security system, developed in conjunction with the surety industry. Surety agents may contact Surety 2000 at 1-800-660-3263.

Bidders are encouraged to participate in the pilot program. To participate, the bidder is asked to provide the "Authorization Code" provided by Surety 2000, on a separate sheet, together with the standard bidder's bond required by the specifications. The bidder's surety agent may obtain the "Authorization Code" from Surety 2000.

The Department will use the "Authorization Code" to access the Surety 2000 database, and independently verify the actual bidder's bond and document the functioning of the Surety 2000 system.

"Authorization Codes" will be used only to verify bidder's bonds, and only as part of the pilot program. The use of "Authorization Codes" will not be accepted in lieu of the bidder's bond or other bidder's security required in the specifications during the pilot study.

The function of the Surety 2000 system is to provide an easier way for Contractors to protect their bid security, and to discourage fraud. This system is available to all California admitted sureties and surety agents.

The results of the pilot study will be tabulated, and at some time in the future, the Department may consider accepting electronic bidder's bond verification in lieu of the bidder's bond specified.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS.....	1
COPY OF ENGINEER'S ESTIMATE	3
SPECIAL PROVISIONS	4
SECTION 1. SPECIFICATIONS AND PLANS.....	4
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS.....	4
2-1.01 GENERAL.....	4
2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE).....	4
2-1.03 DVBE GOAL FOR THIS PROJECT.....	5
2-1.04 SUBMISSION OF DVBE INFORMATION	6
2-1.05 SMALL BUSINESS PREFERENCE.....	6
2-1.06 CALIFORNIA COMPANY PREFERENCE.....	7
SECTION 3. AWARD AND EXECUTION OF CONTRACT.....	7
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES.....	8
SECTION 5. GENERAL	8
SECTION 5-1. MISCELLANEOUS	8
5-1.01 PLANS AND WORKING DRAWINGS	8
5-1.015 LABORATORY	8
5-1.02 LABOR NONDISCRIMINATION.....	8
5-1.03 INTEREST ON PAYMENTS	9
5-1.04 PUBLIC SAFETY	9
5-1.05 SURFACE MINING AND RECLAMATION ACT.....	10
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES.....	10
5-1.07 YEAR 2000 COMPLIANCE.....	10
5-1.08 SUBCONTRACTOR AND DVBE RECORDS.....	11
5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS	11
5-1.09 SUBCONTRACTING	11
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS	12
5-1.11 PARTNERING	12
5-1.12 PAYMENTS	12
SECTION 6. (BLANK).....	12
SECTION 7. (BLANK).....	12
SECTION 8. MATERIALS	12
SECTION 8-1. MISCELLANEOUS	12
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	12
8-1.02 APPROVED TRAFFIC PRODUCTS.....	18
PAVEMENT MARKERS, PERMANENT TYPE.....	18
PAVEMENT MARKERS, TEMPORARY TYPE.....	19
STRIPING AND PAVEMENT MARKING MATERIALS	19
CLASS 1 DELINEATORS.....	20
CHANNELIZERS	20
CONICAL DELINEATORS, 1070 mm.....	20
OBJECT MARKERS.....	20
TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS	21
THRIE BEAM BARRIER MARKERS.....	21
CONCRETE BARRIER DELINEATORS, 400 mm	21
CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm).....	21
SOUND WALL DELINEATOR.....	21
GUARD RAILING DELINEATOR.....	21
RETROREFLECTIVE SHEETING.....	22
SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS	22
8-1.03 ASPHALT	23
SECTION 8-2. CONCRETE.....	25
8-2.01 PORTLAND CEMENT CONCRETE.....	25
8-2.02 FREEZING CONDITION REQUIREMENTS	34

SECTION 8-3. WELDING	35
8-3.01 WELDING ELECTRODES	35
SECTION 9. (BLANK).....	35
SECTION 10. CONSTRUCTION DETAILS.....	35
SECTION 10-1. GENERAL	35
10-1.01 ORDER OF WORK.....	35
10-1.02 WATER POLLUTION CONTROL.....	35
WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES	36
WPCP IMPLEMENTATION.....	37
MAINTENANCE	37
PAYMENT	38
10-1.03 TEMPORARY EROSION CONTROL.....	38
MATERIALS.....	38
APPLICATION	38
MEASUREMENT AND PAYMENT	38
10-1.04 PRESERVATION OF PROPERTY.....	39
10-1.05 TEMPORARY STRAW BALE BARRIER.....	39
MATERIALS.....	39
INSTALLATION	39
MEASUREMENT AND PAYMENT	39
10-1.06 PROGRESS SCHEDULE (CRITICAL PATH).....	40
DEFINITIONS.....	40
MATERIALS (COMPUTER SYSTEM)	41
GENERAL.....	41
PRE-CONSTRUCTION SCHEDULING CONFERENCE	43
NETWORK DIAGRAM AND PROJECT SCHEDULE REPORTS	44
BASELINE SCHEDULE REQUIREMENTS	45
MONTHLY SCHEDULE UPDATES.....	45
SCHEDULE REVISIONS.....	45
SCHEDULE TIME ADJUSTMENT.....	46
FINAL SCHEDULE UPDATE	46
PAYMENT	46
RETENTION.....	46
10-1.07 OBSTRUCTIONS	47
10-1.08 TEMPORARY CRASH CUSHION MODULE.....	47
GENERAL.....	48
MATERIALS.....	48
INSTALLATION	48
MEASUREMENT AND PAYMENT	49
10-1.09 EXISTING HIGHWAY FACILITIES	49
ABANDON SEWER LINE.....	49
REMOVE FENCE.....	49
REMOVE ASPHALT CONCRETE SURFACING.....	49
REMOVE CONCRETE.....	49
10-1.10 CLEARING AND GRUBBING.....	49
10-1.11 DEMOLITION	50
SCOPE.....	50
SALVAGE.....	50
PREPARATION.....	50
DISPOSAL	50
MEASUREMENT	50
PAYMENT	50
10-1.12 EARTHWORK.....	50
10-1.13 CONTROLLED LOW STRENGTH MATERIAL	51
10-1.14 AGGREGATE SUBBASE.....	52
10-1.15 AGGREGATE BASE.....	52
10-1.16 FOG SEAL COAT.....	52
10-1.17 ASPHALT CONCRETE	52
10-1.18 CONCRETE STRUCTURES.....	54

10-1.19 CORRUGATED METAL PIPE	54
10-1.20 MISCELLANEOUS CONCRETE CONSTRUCTION	54
SECTION 11. (BLANK).....	54
SECTION 12. BUILDING WORK.....	54
SECTION 12-1. GENERAL REQUIREMENTS	54
12-1.01 SCOPE.....	54
12-1.02 ABBREVIATIONS	54
12-1.03 GUARANTEE	55
12-1.04 AREAS FOR CONTRACTOR'S USE	55
12-1.05 COOPERATION	55
12-1.06 SUBMITTALS	55
12-1.07 PROGRESS SCHEDULE	56
12-1.08 SCHEDULE OF VALUES.....	56
12-1.09 INSPECTION	56
12-1.10 UTILITY CONNECTION.....	56
12-1.11 TEMPORARY UTILITIES.....	57
12-1.12 SANITARY FACILITIES.....	57
12-1.13 MEASUREMENT AND PAYMENT	57
12-1.14 FIELD ENGINEERING.....	57
12-1.15 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	58
SECTION 12-2. SITEWORK.....	67
12-2.01 REMOVING PORTIONS OF EXISTING FACILITIES	67
12-2.02 RELOCATING MATERIALS AND EQUIPMENT	68
12-2.03 EARTHWORK FOR BUILDING WORK.....	69
12-2.04 AGGREGATE BASE.....	71
12-2.05 FREE DRAINING GRANULAR MATERIAL.....	72
12-2.06 GEOTEXTILE FABRIC	72
12-2.07 PAINTED PAVEMENT MARKINGS	73
12-2.08 SANITARY SEWAGE DISPOSAL SYSTEM.....	74
12-2.09 TRAILER SANITARY STATION	77
12-2.10 GUARD POSTS	78
12-2.11 PARKING BUMPERS.....	78
12-2.12 DISABLED PARKING AND AUTHORIZATION SIGNS.....	79
SECTION 12-3. CONCRETE AND REINFORCEMENT	80
12-3.01 CAST-IN-PLACE CONCRETE.....	80
SECTION 12-4. (BLANK)	86
SECTION 12-5. METALS.....	86
12-5.01 STRUCTURAL STEEL FOR BUILDINGS.....	86
12-5.02 BUILDING MISCELLANEOUS METAL.....	89
12-5.03 ALUMINUM GATE	91
SECTION 12-6. WOOD AND PLASTICS	93
12-6.01 ROUGH CARPENTRY	93
12-6.02 PRE-ENGINEERED WOOD TRUSSES.....	96
12-6.03 LAMINATED VENEER LUMBER	97
12-6.04 FINISH CARPENTRY.....	98
SECTION 12-7. THERMAL AND MOISTURE PROTECTION	100
12-7.01 WATER REPELLENT SEALANT.....	100
12-7.02 INSULATION (GENERAL).....	102
12-7.02A BATT INSULATION.....	102
12-7.02B INSULATION FOR PRE-ENGINEERED STEEL BUILDING	104
12-7.02C LOOSE-FILL INSULATION.....	105
12-7.03 METAL ROOF AND SIDING.....	106
12-7.04 SHEET METAL FLASHING	109
SECTION 12-8. DOORS AND WINDOWS.....	110
12-8.01 HINGED DOORS.....	110
12-8.02 SECTIONAL OVERHEAD DOORS.....	112
12-8.03 WINDOWS.....	114
12-8.04 FINISH HARDWARE	115
12-8.05 GLAZING.....	118

SECTION 12-9. FINISHES	120
12-9.01 GYPSUM WALLBOARD	120
12-9.02 RUBBER STAIR STRIPS	121
12-9.03 PAINTING.....	121
12-9.04 FIBERGLASS REINFORCED PLASTIC PANELS	126
SECTION 12-10. SPECIALTIES	126
12-10.01 LOUVERS.....	126
12-10.02 METAL SIGNS	127
12-10.03 SIGNS.....	127
12-10.04 FIRE EXTINGUISHERS	128
12-10.05 FREE STANDING STEEL SHELVING	129
12-10.06 TOILET ACCESSORIES.....	130
SECTION 12-11. EQUIPMENT.....	131
12-11.01 LUBRICATION AND COMPRESSED AIR SYSTEMS.....	131
12-11.02 CLARIFIER TANK.....	134
12-11.03 WORKBENCH.....	135
SECTION 12-12. (BLANK)	136
SECTION 12-13. SPECIAL CONSTRUCTION.....	136
12-13.01 PRE-ENGINEERED STEEL BUILDING	136
SECTION 12-14. CONVEYING SYSTEMS.....	139
12-14.01 MOBILE VEHICLE LIFT.....	139
12-14.02 BRIDGE CRANE AND HOIST.....	142
SECTION 12-15. MECHANICAL	145
12-15.01 MECHANICAL WORK.....	145
12-15.02 PIPE, FITTINGS AND VALVES	147
12-15.03 MECHANICAL INSULATION.....	155
12-15.04 AUTOMATIC FIRE SPRINKLER SYSTEM (DRY)	157
12-15.05 PLUMBING FIXTURES	159
12-15.06 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS	161
SECTION 12-16. ELECTRICAL	165
12-16.01 ELECTRICAL WORK.....	165
12-16.02 BASIC MATERIALS AND METHODS.....	166
12-16.03 SERVICE AND DISTRIBUTION	173
12-16.04 ELECTRICAL EQUIPMENT	174
12-16.05 LIGHTING	178

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
A62F	Excavation and Backfill - Metal and Plastic Culverts
T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
T1B	Temporary Crash Cushion, Sand Filled (Bidirectional)
T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)

State Project with DVBE Goals (06-14-00)

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 02-341804

02-Plu-5727-

Sealed proposals for the work shown on the plans entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR BUILDING CONSTRUCTION IN PLUMAS COUNTY IN QUINCY AT THE QUINCY MAINTENANCE STATION AT 1555 EAST MAIN STREET

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on October 3, 2000, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR BUILDING CONSTRUCTION IN PLUMAS COUNTY IN QUINCY AT THE QUINCY MAINTENANCE STATION AT 1555 EAST MAIN STREET

General work description: Constructing resident mechanic facility, enclosed storage building, salt storage building, covered storage canopy, covered material bins, trailer sanitary station and accessible parking.

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation. No prebid meeting is scheduled for this project.

Contract No. 02-341804

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A or Class B license or a combination of Class C licenses which constitutes a majority of the work.

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in conformance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Preference will be granted to bidders properly certified as a "Small Business" as determined by the Department of General Services, Office of Small Business Certification and Resources at the time of bid opening in conformance with the provisions in Section 2-1.05, "Small Business Preference," of the special provisions, and Section 1896 et seq, Title 2, California Code of Regulations. A form for requesting a "Small Business" preference is included with the bid documents. Applications for status as a "Small Business" must be submitted to the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, Telephone No. (916) 322-5060.

A reciprocal preference will be granted to "California company" bidders in conformance with Section 6107 of the Public Contract Code. (See Sections 2 and 3 of the special provisions.) A form for indicating whether bidders are or are not a "California company" is included in the bid documents and is to be filled in and signed by all bidders.

The District in which the work for this project is located has been incorporated into the Department's Northern Region. References in the Standard Specifications or in the special provisions to the district shall be deemed to mean the Northern Region. The office of the District Director for the Northern Region is located at Marysville.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. Future effective general prevailing wage rates which have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated August 28, 2000

FTN

COPY OF ENGINEER'S ESTIMATE
(NOT TO BE USED FOR BIDDING PURPOSES)
02-341804

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	070010	PROGRESS SCHEDULE (CRITICAL PATH)	LS	LUMP SUM
2	019631	TEMPORARY STRAW BALE BARRIER	EA	72
3	074023	TEMPORARY EROSION CONTROL	M2	200
4	150241	ABANDON SEWER LINE	EA	1
5	150605	REMOVE FENCE	M	60
6	150857	REMOVE ASPHALT CONCRETE SURFACING	M2	9400
7	153210	REMOVE CONCRETE	M3	5
8	160101	CLEARING AND GRUBBING	LS	LUMP SUM
9	019634	DEMOLITION	LS	LUMP SUM
10	190101	ROADWAY EXCAVATION	M3	3060
11	250101	CLASS 1 AGGREGATE SUBBASE	M3	960
12	260201	CLASS 2 AGGREGATE BASE	M3	2010
13	374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TONN	6.5
14	390155	ASPHALT CONCRETE (TYPE A)	TONN	2400
15 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	5
16	664014	450 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	5
17	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	M3	140
18	994650	BUILDING WORK	LS	LUMP SUM

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 02-341804

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the indented text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

The District in which the work for this project is located has been incorporated into the Department's Northern Region. References in the Standard Specifications or in these special provisions to the district shall be deemed to mean the Northern Region. The office of the District Director for the Northern Region is located at Marysville.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the name and address of each DVBE subcontractor to be used for credit in meeting the goal, and to whom the bidder proposes to directly subcontract portions of the work. The list of subcontractors shall also set forth the portion of work that will be performed by each subcontractor listed. A sheet for listing the subcontractors is included in the Proposal.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, P.O. Box 911, Marysville, CA 95901, Attn: NRCO/Contract Administration Engineer, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veterans Business Enterprise (DVBE) in contracts.

It is the policy of the Department that Disabled Veteran Business Enterprise (DVBE) shall have the maximum opportunity to participate in the performance of contracts financed solely with state funds. The Contractor shall ensure that DVBEs have the maximum opportunity to participate in the performance of this contract and shall take all necessary and reasonable steps for this assurance. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts. Failure to carry out the requirements of this paragraph shall constitute a breach of contract and may result in termination of this contract or other remedy the Department may deem appropriate.

Bidder's attention is directed to the following:

- A. "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business Certification and Resources, Department of General Services.
- B. A DVBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, or vendor of material or supplies.
- C. Credit for DVBE prime contractors will be 100 percent.
- D. A DVBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks and profits of the joint venture. The DVBE joint venturer must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Section 2-1.04, "Submission of DVBE Information," elsewhere in these special provisions.
- E. A DVBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. Credit for DVBE vendors of materials or supplies is limited to 60 percent of the amount to be paid to the vendor for the material unless the vendor manufactures or substantially alters the goods.
- G. Credit for trucking by DVBEs will be as follows:
 - 1. One hundred percent of the amount to be paid when a DVBE trucker will perform the trucking with his/her own trucks, tractors and employees.
 - 2. Twenty percent of the amount to be paid to DVBE trucking brokers who do not have a "certified roster."
 - 3. One hundred percent of the amount to be paid to DVBE trucking brokers who have signed agreements that all trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that all trucks are owned by DVBEs, and a signed statement on the "certified roster" that indicates that 100 percent of revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."
 - 4. Twenty percent of the amount to be paid to trucking brokers who are not a DVBE but who have signed agreements with DVBE truckers assuring that at least 20 percent of the trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that at least 20 percent of the number of trucks are owned by DVBE truckers, and a signed statement on the "certified roster" that indicates that at least 20 percent of the revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."

The "certified roster" referred to herein shall conform to the requirements in Section 2-1.04, "Submission Of DVBE Information," elsewhere in these special provisions.

- H. DVBEs and DVBE joint venture partners must be certified DVBEs as determined by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, on the date bids for the project are opened before credit may be allowed toward the DVBE goal. It is the Contractor's responsibility to verify that DVBEs are certified.
- I. Noncompliance by the Contractor with these requirements constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

2-1.03 DVBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disabled Veteran Business Enterprise (DVBE) participation for this project:

Disabled Veteran Business Enterprise (DVBE): 3 percent.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation.

The Office of Small Business Certification and Resources, Department of General Services, may be contacted at (916) 322-5060 or visit their internet web site at <http://www.osmb.dgs.ca.gov/> for program information and certification status. The Department's Business Enterprise Program may also be contacted at (916) 227-9599 or the internet web site at <http://www.dot.ca.gov/hq/bep/>.

2-1.04 SUBMISSION OF DVBE INFORMATION

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DVBEs and to select those portions of the work or material needs consistent with the available DVBEs to meet the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DVBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that good faith efforts to meet the DVBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their adequate good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DVBE information shall include the names of DVBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DVBE transaction, and a written confirmation from the DVBE that it is participating in the contract. A copy of the DVBE's quote will serve as written confirmation that the DVBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work. The work that a DVBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DVBE subcontractors, suppliers and trucking companies will count toward the goal.

If credit for trucking by a DVBE trucking broker is shown on the bidder's information as 100 percent of the revenue to be paid by the broker is to be paid to DVBE truckers, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that all the trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification numbers. The roster must indicate that all revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

If credit for trucking by a trucking broker who is not a DVBE is shown in the bidder's information, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that at least 20 percent of the broker's trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification number. The roster must indicate that at least 20 percent of the revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

A bidder shall be deemed to have made good faith efforts upon submittal, within time limits specified by the Department, of documentary evidence that all of the following actions were taken:

- A. Contact was made with the Office of Small Business Certification and Resources (OSBCR), Department of General Services or their web site at <http://www.osmb.dgs.ca.gov/> to identify Disabled Veteran Business Enterprises.
- B. Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.
- C. Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.
- D. Available Disabled Veteran Business Enterprises were considered.

2-1.05 SMALL BUSINESS PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

Attention is also directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq and Title 2, California Code of Regulations, Section 1896, et seq.

Bidders who wish to be classified as a Small Business under the provisions of those laws and regulations, shall be certified as Small Business by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814.

To request Small Business Preference, bidders shall fill out and sign the Request for Small Business Preference form in the Proposal and shall attach a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form. The bidder's signature on the Request for Small Business Preference certifies, under penalty of perjury, that the bidder is certified as Small Business at the time of bid opening and further certifies, under penalty of perjury, that under the following conditions, at least 50 percent of the subcontractors to be utilized on the project are either certified Small Business or have applied for Small Business certification by bid opening date and are subsequently granted Small Business certification.

The conditions requiring the aforementioned 50 percent level of subcontracting by Small Business subcontractors apply if:

- A. The lowest responsible bid for the project exceeds \$100,000; and
- B. The project work to be performed requires a Class A or a Class B contractor's license; or a combination of Class C licenses which constitutes a majority of the work and
- C. Two or more subcontractors will be used.

If the above conditions apply and Small Business Preference is granted in the award of the contract, the 50 percent Small Business subcontractor utilization level shall be maintained throughout the life of the contract.

2-1.06 CALIFORNIA COMPANY PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

In conformance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

- A. Has its principal place of business in California.
- B. Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
- C. Has its principal place of business in a state in which there is a local contractor construction preference and the contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DVBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business Preference" of these special provisions. Any bidder who is certified as a Small Business by the Department of General Services, Office of Small Business Certification and Resources will be allowed a preference in the award of this contract, if it be awarded, under the following conditions:

- A. The apparent low bidder is not certified as a Small Business, or has not filled out and signed the Request for Small Business Preference included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form; and
- B. The bidder filled out and signed the Request for Small Business Preference form included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form.

The small business preference will be a reduction in the bid submitted by the small business contractor, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the small business contractor becoming the low bidder, then the contract will be awarded to the small business contractor on the basis of the actual bid of the small business contractor notwithstanding the reduced bid price used for bid comparison purposes.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California Small Business Preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small business bidders shall have precedence over nonsmall business bidders in that the application of the "California company" preference for which nonsmall business bidders may be eligible shall not result in the denial of the award to a small business bidder.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of **330 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$400 per day, for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed above.

SECTION 5. GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.01 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

5-1.015 LABORATORY

When a reference is made in the specifications to the "Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

5-1.02 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

**NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM
(GOV. CODE, SECTION 12990)**

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

5-1.03 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.04 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
 - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - 2. Excavations less than 0.3-m deep.
 - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
 - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
 - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m

minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.05 SURFACE MINING AND RECLAMATION ACT

Attention is directed to the Surface Mining and Reclamation Act of 1975, commencing in Public Resources Code, Mining and Geology, Section 2710, which establishes regulations pertinent to surface mining operations.

Material from mining operations furnished for this project shall only come from permitted sites in compliance with the Surface Mining and Reclamation Act of 1975.

The requirements of this section shall apply to materials furnished for the project, except for acquisition of materials in conformance with the provisions in Section 4-1.05, "Use of Materials Found on the Work," of the Standard Specifications.

5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.07 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is

recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

5-1.08 SUBCONTRACTOR AND DVBE RECORDS

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (S) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer.

5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS

The DVBEs listed by the Contractor in response to the provisions in Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to utilize other forces or sources of materials may be requested for the following reasons:

- A. The listed DVBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when the written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of the subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DVBE becomes bankrupt or insolvent.
- C. The listed DVBE fails or refuses to perform the subcontract or furnish the listed materials.
- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DVBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. The listed DVBE subcontractor is not licensed pursuant to the Contractor's License Law.
- G. It would be in the best interest of the State.

The Contractor shall not be entitled to payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

5-1.09 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, Section 2, "Proposal Requirements and Conditions," Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions and these special provisions.

Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>.

The third paragraph of Section 8-1.01 of the Standard Specifications shall not apply to this contract.

The DVBE information furnished under Section 3-1.01A, "DVBE Information," of these special provisions is in addition to the subcontractor information required to be furnished in Section 8-1.01, "Subcontracting," and Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications.

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in highway contracts that are State funded. As a part of this requirement:

- A. No substitution of a DVBE subcontractor shall be made at any time without the written consent of the Department, and

- B. If a DVBE subcontractor is unable to perform successfully and is to be replaced, the Contractor shall make good faith efforts to replace the original DVBE subcontractor with another DVBE subcontractor.

The provisions in Section 2-1.02, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs shall be certified on the date bids are opened does not apply to DVBE substitutions after award of the contract.

5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

5-1.11 PARTNERING

The State will promote the formation of a "Partnering" relationship with the Contractor in order to effectively complete the contract to the benefit of both parties. The purpose of this relationship will be to maintain cooperative communication and mutually resolve conflicts at the lowest possible management level.

The Contractor may request the formation of such a "Partnering" relationship by submitting a request in writing to the Engineer after approval of the contract. If the Contractor's request for "Partnering" is approved by the Engineer, scheduling of a "Partnering" workshop, selecting the "Partnering" facilitator and workshop site, and other administrative details shall be as agreed to by both parties.

The costs involved in providing a facilitator and a workshop site will be borne equally by the State and the Contractor. The Contractor shall pay all compensation for the wages and expenses of the facilitator and of the expenses for obtaining the workshop site. The State's share of such costs will be reimbursed to the Contractor in a change order written by the Engineer. Markups will not be added. All other costs associated with the "Partnering" relationship will be borne separately by the party incurring the costs.

The establishment of a "Partnering" relationship will not change or modify the terms and conditions of the contract and will not relieve either party of the legal requirements of the contract.

5-1.12 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

- A. Clearing and Grubbing \$7,000

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

No partial payment will be made for any materials on hand which are furnished but not incorporated in the work.

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (Imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.

- B. Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material as specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS
ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT, ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS mm ²	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

SUBSTITUTION TABLE FOR BAR REINFORCEMENT

METRIC BAR DESIGNATION NUMBER SHOWN ON THE PLANS	EQUIVALENT IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

CONVERSION TABLE FOR SIZES OF:

- (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and
- (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449

METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT US STANDARD GAGE	METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT GALVANIZED SHEET GAGE
mm	inch	mm	inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----

CONVERSION TABLE FOR WIRE

METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT USA STEEL WIRE THICKNESS inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

CONVERSION TABLE FOR PIPE PILES

METRIC SIZE SHOWN ON THE PLANS mm x mm	EQUIVALENT IMPERIAL SIZE inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in inches (T") represents an exact conversion of the metric thickness in millimeters (T).

CONVERSION TABLE FOR STRUCTURAL TIMBER AND LUMBER

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	EQUIVALENT NOMINAL US SIZE inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

CONVERSION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	EQUIVALENT IMPERIAL SIZE Penny-weight
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

CONVERSION TABLE FOR IRRIGATION COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	EQUIVALENT NOMINAL US SIZE inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

8-1.02 APPROVED TRAFFIC PRODUCTS

The Department maintains the following list of Approved Traffic Products. The Engineer shall not be precluded from sampling and testing products on the list of Approved Traffic Products.

The manufacturer of products on the list of Approved Traffic Products shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

Signing and delineation materials and products shall not be used in the work unless the material or product is on the list of Approved Traffic Products.

Materials and products may be added to the list of Approved Traffic Products if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective

- A. Apex, Model 921 (100 mm x 100 mm)
- B. Ray-O-Lite, Models SS (100 mm x 100 mm), RS (100 mm x 100 mm) and AA (100 mm x 100 mm)
- C. Stimsonite, Models 88 (100 mm x 100 mm), 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

- A. Ray-O-Lite "AA" ARS (100 mm x 100 mm)
- B. Stimsonite, Models 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- C. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

(Used for recessed applications)

- A. Stimsonite, Model 948 (58 mm x 119 mm)
 - B. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
 - C. Stimsonite, Model 944SB (51 mm x 100 mm)*
 - D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)*
- *For use only in 114 mm wide (older) recessed slots

Non-Reflective For Use With Epoxy Adhesive, 100 mm Round

- A. Apex Universal (Ceramic)
- B. Highway Ceramics, Inc. (Ceramic)

Non-Reflective For Use With Bitumen Adhesive, 100 mm Round

- A. Apex Universal (Ceramic)
- B. Apex Universal, Model 929 (ABS)
- C. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
- D. Highway Ceramics, Inc. (Ceramic)
- E. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
- F. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
- G. Alpine Products, D-Dot (ABS)
- H. Road Creations, Model RCB4NR (Acrylic)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (6 months or less)

- A. Apex Universal, Model 924 (100 mm x 100 mm)
- B. Davidson Plastics Corp., Model 3.0 (100 mm x 100 mm)
- C. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
- D. Road Creations, Model R41C (100 mm x 100 mm)
- E. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

- A. Apex Universal, Model 932
- B. Davidson Plastics, Models T.O.M., T.R.P.M., and "HH" (High Heat)
- C. Hi-Way Safety, Inc., Model 1280/1281

STRIPING AND PAVEMENT MARKING MATERIALS

Permanent Traffic Striping and Pavement Marking Tape

- A. Advanced Traffic Marking, Series 300 and 400
- B. Brite-Line, Series 1000
- C. Swarco Industries, "Director 35" (For transverse application only)
- D. Swarco Industries, "Director 60"
- E. 3M, "Stamark" Series 380 and 5730
- F. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)

- A. Brite-Line, Series 100
- B. P.B. Laminations, Aztec, Grade 102
- C. Swarco Industries, "Director-2"
- D. 3M, "Stamark," Series 620
- E. 3M Series A145 Removable Black Line Mask
(Black Tape: For use only on Asphalt Concrete Surfaces)
- F. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: For use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

- A. Flint Trading, "Premark" and "Premark 20/20 Flex"
- B. Pavemark, "Hotape"

Removable Traffic Paint

- A. Belpro, Series 250/252 and No. 93 Remover

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 1700 mm

- A. Carsonite, Curve-Flex CFRM-400
- B. Carsonite, Roadmarker CRM-375
- C. Davidson Plastics, "Flexi-Guide Models 400 and 566"
- D. FlexStake, Model 654TM
- E. GreenLine Models HWD1-66 and CGD1-66
- F. J. Miller Industries, Model JMI-375 (with soil anchor)

Special Use Flexible Type, 1700 mm

- A. Carsonite, "Survivor" (with 450 mm U-Channel base)
- B. FlexStake, Model 604
- C. GreenLine Models HWD and CGD (with 450 mm U-Channel base)
- D. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
- E. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

Surface Mount Flexible Type, 1200 mm

- A. Bent Manufacturing Company, "Masterflex" Model MF-180EX-48
- B. Carsonite, "Super Duck II"
- C. FlexStake, Surface Mount, Models 704 and 754TM

CHANNELIZERS

Surface Mount Type, 900 mm

- A. Bent Manufacturing Company, "Masterflex" Models MF-360-36 (Round) and MF-180-36 (Flat)
- B. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
- C. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
- D. Davidson Plastics, Flex-Guide Models FG300LD and FG300UR
- E. FlexStake, Surface Mount, Models 703 and 753TM
- F. GreenLine, Model SMD-36
- G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
- H. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
- I. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
- J. Repo, Models 300 and 400
- K. Safe-Hit, Guide Post, Model SH236SMA

CONICAL DELINEATORS, 1070 mm

(For 700 mm Traffic Cones, see Standard Specifications)

- A. Bent Manufacturing Company "T-Top"
- B. Plastic Safety Systems "Navigator-42"
- C. Roadmaker Company "Stacker"
- D. Traffix Devices "Grabber"

OBJECT MARKERS

Type "K", 450 mm

- A. Carsonite, Model SMD-615
- B. FlexStake, Model 701KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Model SH718SMA
- E. The Line Connection, Model DP21-4K

Type "K-4" / "Q", 600 mm

(Shown as Type "Q" in the Traffic Manual)

- A. Bent Manufacturing "Masterflex" Model MF-360-24
- B. Carsonite, Super Duck II
- C. FlexStake, Model 701KM
- D. Repo, Models 300 and 400
- E. Safe-Hit, Models SH8 24SMA_WA and SH8 24GP3_WA
- F. The Line Connection, Model DP21-4Q

TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS

Impactable Type

- A. ARTUK, "FB"
- B. Davidson Plastics, Model PCBM-12
- C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
- D. Hi-Way Safety, Inc., Model GMKRM100

Non-Impactable Type

- A. ARTUK, JD Series
- B. Stimsonite, Model 967 (with 83 mm Acrylic cube corner reflector)
- C. Stimsonite, Model 967LS
- D. Vega Molded Products, Models GBM and JD

THREE BEAM BARRIER MARKERS

(For use to the left of traffic)

- A. Duraflex Corp., "Railrider"
- B. Davidson Plastics, "Mini" (75 mm x 254 mm)

CONCRETE BARRIER DELINEATORS, 400 mm

(For use to the right of traffic. When mounted on top of barrier, places top of reflective element at 1200 mm)

- A. Davidson Plastics, Model PCBM T-16
- B. Safe-Hit, Model SH216RBM

CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)

- A. Stinson Equipment Company "SaddleMarker"

SOUND WALL DELINEATOR

(Applied to a vertical surface. Top of reflective element at 1200 mm)

- A. Davidson Plastics, PCBM S-36

GUARD RAILING DELINEATOR

(Top of reflective element at 1200 mm above plane of roadway)

Wood Post Type, 686 mm

- A. Carsonite, Model 427
- B. Davidson Plastics FG 427 and FG 527
- C. FlexStake, Model 102 GR
- D. GreenLine GRD 27
- E. J.Miller Model JMI-375G
- F. Safe-Hit, Model SH227GRD

Steel Post Type

- A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

- A. 3M, High Intensity
- B. Reflexite, PC-1000 Metalized Polycarbonate
- C. Reflexite, AC-1000 Acrylic
- D. Reflexite, AP-1000 Metalized Polyester
- E. Reflexite, AR-1000 Abrasion Resistant Coating
- F. Stimsonite, Series 6200 (For rigid substrate devices only)

Traffic Cones, 330 mm Sleeves

- A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

Traffic Cones, 100 mm and 150 mm Sleeves

- A. 3M Series 3840
- B. Reflexite Vinyl, "TR" (Semi-transparent) or "Conformalite"

Barrels and Drums

- A. Reflexite, "Super High Intensity" or "High Impact Drum Sheeting"
- B. 3M Series 3810

Barricades: Type I, Engineer Grade

- A. American Decal, Adcolite
- B. Avery Dennison, 1500 and 1600
- C. 3M, Scotchlite, Series CW

Barricades: Type II, Super Engineer Grade

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite Type II
- C. Nikkalite 1800 Series

Signs: Type II, Super Engineer Grade

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite, Type II
- C. Nikkalite 1800 Series

Signs: Type III, High-Intensity Grade

- A. 3M Series 3800
- B. Nippon Carbide, Nikkalite Brand Ultralite Grade II

Signs: Type IV, High-Intensity Prismatic Grade

- A. Stimsonite Series 6200

Signs: Type VII, High-Intensity Prismatic Grade

- A. 3M Series 3900

Signs: Type VI, Roll-Up Signs

- A. Reflexite, Vinyl (Orange), Reflexite "SuperBright" (Fluorescent orange)
- B. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS

Aluminum

Fiberglass Reinforced Plastic (FRP)

- A. Sequentia, "Polyplate"
- B. Fiber-Brite

8-1.03 ASPHALT

The first paragraph and tables following the first paragraph in Section 92-1.02, "Grades," of the Standard Specifications shall not apply.

The grade of asphalt to be used will be specified in "Asphalt Concrete" of these special provisions. The safe transportation, storage, use, and disposal of the asphalt specified shall be the responsibility of the Contractor.

A Certificate of Compliance, as specified in Section 92-1.03, "Test Report," of the Standard Specifications, shall accompany each shipment of asphalt to the project. When PBA Grade 6a, 6b or 7 is specified, the Certificate of Compliance shall include actual results of tests completed by the producer in addition to the items enumerated in Section 92-1.03 of the Standard Specifications. The Certificate of Compliance shall verify that the results of AASHTO Test Method T240 (Mass Loss after Rolling Thin Film Oven Test) indicate a maximum mass loss of 0.6 percent and that AASHTO Test Method T48 (Flash Point, Cleveland Open Cup) indicate a minimum flash point of 232°C. The actual formulation used by the asphalt producer shall be available to the Department upon written request. The Department will execute a non-disclosure agreement if requested by the asphalt producer.

For PBA Grades 6a, 6b or 7, if the results of mass loss after Rolling Thin Film Oven Test (AASHTO Test Method T240) or Flash Point, Cleveland Open Cup (AASHTO Test Method T48), shown on the Certificate of Compliance are not within the limits specified in the table entitled "PERFORMANCE BASED ASPHALT BINDER GRADES" or if the results are not shown on the Certificate of Compliance, the individual shipment of asphalt will be rejected. Rejected asphalt shall not be used on the project. Should rejected asphalt be unloaded into bulk storage tanks, asphalt from the tanks shall not be used on the project until tests and a Certificate of Compliance are furnished for the material and indicate compliance with the specifications.

Asphalt to be used as a binder for asphalt concrete will be sampled using the sampling device specified in Section 39-3.01C, "Asphalt Binder Storage," of the Standard Specifications. Two samples per operating day, each consisting of 2 one-liter containers, will be taken from the bulk storage tank feeder line.

For PBA Grades 6a, 6b or 7, if the test result of samples taken from the bulk storage tank, indicate mass loss greater than 0.6 percent, the material containing the paving asphalt represented by the tests shall be removed. However, if requested in writing by the Contractor and approved by the Engineer, the material containing the paving asphalt with mass loss greater than 0.6 percent may remain in place, and the Contractor shall pay to the State the amount calculated by the formulae listed below.

- A. For mass loss test results over 0.6 percent but less than or equal to 1.0 percent:
 - 1. (25 percent multiplied by 25 tonne average multiplied by the invoice price of paving asphalt)
- B. For mass loss test results over 1.0 percent:
 - 1. (100 percent multiplied by 25 tonne average multiplied by the invoice price of paving asphalt).
- C. The Department may deduct this amount from any moneys due, or that may become due, the Contractor under the contract. Each sample from the bulk storage shall represent 25 tonne average. The delivered price of the paving asphalt shall be based on a certified invoice provided by the Contractor.

PERFORMANCE BASED ASPHALT BINDER GRADES

Specification Designation	AASHTO Test Method	PBA Grade				
		1	4	6a	6b	7
Penetration (25°C, 100g, 5s),dmm RTFO Aged Residue, Min (Note 1)	T49	25	20	—	----	----
Absolute Viscosity (60°C), Pa•s(x10 ⁻¹) (Note 2) Original Binder, Min RTFO Aged Residue	T202 T202	800 2500-5000 (Note 3)	2800 14 000 Max	2000 5000 Min	2000 5000 Min	1100 3000 Min
Kinematic Viscosity (135°C), m ² /s(x10 ⁻⁶) Original Binder, Max. RTFO Aged Residue, Min	T201 T201	---- 275	---- 350	2000 275	2000 275	2000 275
Absolute Viscosity Ratio (60°C), Max RTFO Visc./Orig. Visc.	-----	4.0	4.0	4.0	4.0	4.0
Flash Point, Cleveland Open Cup, °C, (Note 4) Original Binder, Min	T48	232	232	232	232	232
Mass Loss After RTFO Test, % (Note 5)	T240	Report (Note 6)	Report	0.60	0.60	0.60
Solubility in Trichloroethylene, % Original Binder, Min	T44	99.0	99.0	Report	Report	Report
Ductility (25°C, 5 cm/min), cm RTFO Aged Residue, Min	T51	75	50	60	60	75
On Residue from Pav @: or Residue from Tilt Oven @ 113°C for: (hours)	PP1 (Note 7)	90°C 18	100°C 36	100°C 36	100°C 36	110°C 72
SSD -115(SSV)-50.6	(Note 9)	-----	-----	-----	-----	25°C
Stiffness, 300 MPa, Max. @: and M-value, 0.30, Min.	TP1	-6°C	-6°C	-24°C	-30°C	-6°C

1. "RTFO Aged Residue" means the asphaltic residue obtained using the Rolling Thin Film Oven Test (RTFO Test), AASHTO Test Method T240 or ASTM Designation: D 2827.
2. The Absolute Viscosity (60°C) of PBA 6a, 6b, and 7 will be determined at 1 sec-1 using ASTM Designation: D 4957 with Asphalt Institute Vacuum Capillary Viscometers.
3. Where actual limits (e.g. 2500-5000) are indicated, the actual test results shall be part of the certified copy of test results, or shall be furnished with the Certificate of Compliance.
4. Actual results of the test shall be part of the certified copy of test results and when PBA Grade 6a, 6b or 7 is used an additional statement verifying an acceptable flash point shall be included with the Certificate of Compliance.
5. Actual results of the test shall be part of the certified copy of test results and when PBA Grade 6a, 6b or 7 is used an additional statement verifying an acceptable mass loss shall be included with the Certificate of Compliance.
6. Where "Report" is indicated, there is no requirement, however the actual results of the test shall be part of the certified copy of test results, or shall be furnished with the Certificate of Compliance.
7. "Tilt Oven Residue" means the asphalt obtained using California Test 374, Method B, "Method for Determining Asphalt Durability Using the California Tilt-Oven Durability Test".
8. SSD = Shear susceptibility of Delta, SSV = Shear susceptibility of Viscosity.
9. California Test 381.

SECTION 8-2. CONCRETE

8-2.01 PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

Unless the use of a mineral admixture is prohibited, whenever the word "cement" is used in the Standard Specifications or the special provisions, it shall be understood to mean "cementitious material" when both of the following conditions are met:

- A. The cement content of portland cement concrete is specified, and
- B. Section 90, "Portland Cement Concrete," of the Standard Specifications is referenced.

Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494 may be used in portland cement concrete for precast steam cured concrete members.

Section 90-1.01, "Description," of the Standard Specifications is amended to read:

90-1.01 DESCRIPTION

- Portland cement concrete shall be composed of cementitious material, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified in these specifications.
- Unless otherwise specified, cementitious material to be used in portland cement concrete shall conform to the provisions for cement and mineral admixtures in Section 90-2, "Materials," and shall be either: 1) "Type IP (MS) Modified" cement or 2) a combination of "Type II Modified" portland cement and mineral admixture.
- Concrete for each portion of the work shall comply with the provisions for the Class, cementitious material content in kilograms per cubic meter, 28-day compressive strength, minor concrete or commercial quality concrete, as shown on the plans or specified in these specifications or the special provisions.
 - Class 1 concrete shall contain not less than 400 kg of cementitious material per cubic meter.
 - Class 2 concrete shall contain not less than 350 kg of cementitious material per cubic meter.
 - Class 3 concrete shall contain not less than 300 kg of cementitious material per cubic meter.
 - Class 4 concrete shall contain not less than 250 kg of cementitious material per cubic meter.
 - Minor concrete shall contain not less than 325 kg of cementitious material per cubic meter unless otherwise specified in these specifications or the special provisions.
- Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic meter of concrete in structures or portions of structures shall conform to the following:

Use	Cementitious Material Content (kg/m ³)
Concrete which is designated by compressive strength: Deck slabs and slab spans of bridges Roof sections of exposed top box culverts Other portions of structures	400 min., 475 max. 400 min., 475 max. 350 min., 475 max.
Concrete not designated by compressive strength: Deck slabs and slab spans of bridges Roof sections of exposed top box culverts Prestressed members Seal courses Other portions of structures	400 min. 400 min. 400 min. 400 min. 350 min.
Concrete for precast members	350 min., 550 max.

- Whenever the 28-day compressive strength shown on the plans is greater than 25 MPa, the concrete shall be considered to be designated by compressive strength. If the plans show a 28-day compressive strength which is 31 MPa or greater, an additional 7 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans which are 25 MPa or less are shown for design information only and are not to be considered a requirement for acceptance of the concrete.
- Concrete designated by compressive strength shall be proportioned such that the concrete will conform to the strength shown on the plans or specified in the special provisions.
- The Contractor shall determine the mix proportions for all concrete except pavement concrete. The Engineer will determine the mix proportions for pavement concrete.

- Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.
- Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, mineral admixture shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.
 - If any concrete used in the work has a cementitious material content, consisting of cement, mineral admixture, or cement plus mineral admixture, which is less than the minimum required for the work, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$0.55 for each kilogram of cement, mineral admixture, or cement plus mineral admixture which is less than the minimum required for the work. The Department may deduct the amount from moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions for cementitious material content will be made based on the results of California Test 518.
 - The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.
 - Concrete for which the mix proportions are determined either by the Contractor or the Engineer shall conform to the requirements of this Section 90.

The first paragraph in Section 90-2.01, "Portland Cement," of the Standard Specifications is amended to read:

90-2.01 PORTLAND CEMENT

- Unless otherwise specified, portland cement shall be either "Type IP (MS) Modified" cement or "Type II Modified" portland cement.
 - "Type IP (MS) Modified" cement shall conform to the specifications for Type IP (MS) cement in ASTM Designation: C 595, and shall be comprised of an intimate mixture of Type II cement and not more than 25 percent of a mineral admixture. The type and minimum amount of mineral admixture used in the manufacture of "Type IP (MS) Modified" cement shall be in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."
 - "Type II Modified" portland cement shall conform to the requirements for Type II portland cement in ASTM Designation: C 150.
 - In addition, "Type IP (MS) Modified" cement and "Type II Modified" portland cement shall conform to the following requirements:
 - A. The cement shall not contain more than 0.60 percent by mass of alkalis, calculated as the percentage of Na₂O plus 0.658 times the percentage of K₂O, when determined by either direct intensity flame photometry or by the atomic absorption method. The instrument and procedure used shall be qualified as to precision and accuracy in conformance with the requirements in ASTM Designation: C 114.
 - B. The autoclave expansion shall not exceed 0.50 percent.
 - C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010 percent and shall not contract in air more than 0.048 percent except that when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members or steam cured concrete products, the mortar shall not contract in air more than 0.053 percent.

The second paragraph in Section 90-2.01, "Portland Cement," of the Standard Specifications is amended to read:

- Type III and Type V portland cements shall conform to the requirements in ASTM Designation: C 150, and the additional requirements listed above for Type II Modified portland cement, except that when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075 percent.

The third paragraph in Section 90-2.01, "Portland Cement," of the Standard Specifications is deleted.

The twelfth paragraph in Section 90-2.02, "Aggregates," of the Standard Specifications is deleted.

The first paragraph in Section 90-2.03, "Water," of the Standard Specifications is amended to read:

90-2.03 WATER

- In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1,000 parts per million of chlorides as Cl, nor more than 1,300 parts per million of sulfates as SO₄. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, nor more than 1,300 parts per million of sulfates as SO₄. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting

time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

The following section is added to Section 90-2, "Materials," of the Standard Specifications:

90-2.04 ADMIXTURE MATERIALS

- Admixture materials shall conform to the requirements in the following ASTM Designations:
 - A. Chemical Admixtures—ASTM Designation: C 494.
 - B. Air-entraining Admixtures—ASTM Designation: C 260.
 - C. Calcium Chloride—ASTM Designation: D 98.
 - D. Mineral Admixtures—Coal fly ash, raw or calcined natural pozzolan as specified in ASTM Designation: C618. Silica fume conforming to the requirements in ASTM Designation: C1240, with reduction of mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.
- Mineral admixtures shall be used in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

The first paragraph in Section 90-3.03, "Fine Aggregate Grading," is amended to read:

Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
9.5-mm	100	100
4.75-mm	95-100	93-100
2.36-mm	65-95	61-99
1.18-mm	X ± 10	X ± 13
600-µm	X ± 9	X ± 12
300-µm	X ± 6	X ± 9
150-µm	2-12	1-15
75-µm	0-8	0-10

Section 90-4.02, "Materials," of the Standard Specifications is amended to read:

90-4.02 MATERIALS

- Admixture materials shall conform to the provisions in Section 90-2.04, "Admixture Materials."

Section 90-4.05, "Optional Use of Chemical Admixtures," of the Standard Specifications is amended to read:

90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

- The Contractor will be permitted to use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate concrete construction application subject to the following conditions:
 - A. When a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by mass except that the resultant cementitious material content shall be not less than 300 kilograms per cubic meter.
 - B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

Section 90-4.07, "Optional Use of Air-entraining Admixtures," of the Standard Specifications is amended to read:

90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES

- When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air

content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate as provided in Section 40-1.015, "Cement Content."

Section 90-4.08, "Required Use of Mineral Admixtures," of the Standard Specifications is amended to read:

90-4.08 REQUIRED USE OF MINERAL ADMIXTURES

- Unless otherwise specified, mineral admixture shall be combined with cement to make cementitious material for use in portland cement concrete.
- The calcium oxide content of mineral admixtures shall not exceed 10 percent and the available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C618.
- The amounts of cement and mineral admixture used in cementitious material for portland cement concrete shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and shall conform to the following:
 - A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
 - B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:
 1. When the calcium oxide content of a mineral admixture, as determined in conformance with the requirements in ASTM Designation: C618 and the provisions in Section 90-2.04, "Admixture Materials," is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
 2. When the calcium oxide content of a mineral admixture, as determined in conformance with the requirements in ASTM Designation: C618 and the provisions in Section 90-2.04, "Admixture Materials," is greater than 2 percent, the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix.
 3. When a mineral admixture is used, which conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix.
 - C. If more than the required amount of cementitious material is used, the additional cementitious material in the mix may be either cement, a mineral admixture conforming to the provisions in Section 90-2.04, "Admixture Materials," or a combination of both; however, the maximum total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

Section 90-4.09, "Optional Use of Mineral Admixtures," of the Standard Specifications is deleted.

Section 90-4.11, "Storage, Proportioning, and Dispensing of Mineral Admixtures," of the Standard Specifications is amended to read:

90-4.11 STORAGE, PROPORTIONING, AND DISPENSING OF MINERAL ADMIXTURES

- Mineral admixtures shall be protected from exposure to moisture until used. Sacked material shall be piled to permit access for tally, inspection, and identification for each shipment.
- Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures in order to prevent any but the specified mineral admixtures from entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper.
- Mineral admixtures shall be incorporated into concrete using equipment conforming to the requirements for cement weigh hoppers, and charging and discharging mechanisms in ASTM Designation: C 94, in Section 90-5.03, "Proportioning," and in this Section 90-4.11.
- When interlocks are required for cement and mineral admixture charging mechanisms by Section 90-5.03A, "Proportioning for Pavement," and cement and mineral admixtures are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the mass of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."

- Mineral admixture used in concrete for exposed surfaces of like elements of a structure shall be from the same source and of the same percentage.

Section 90-5.02, "Proportioning Devices," of the Standard Specifications is amended to read:

90-5.02 PROPORTIONING DEVICES

- Weighing, measuring or metering devices used for proportioning materials shall conform to the provisions in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems used shall comply with the provisions for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." These automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and mineral admixture for one batch of concrete is a single operation of a switch or starter.

- Proportioning devices shall be tested at the expense of the Contractor as frequently as the Engineer may deem necessary to insure their accuracy.

- Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the mass of each batch of material shall not vary from the mass designated by the Engineer by more than the tolerances specified herein.

- Equipment for cumulative weighing of aggregate shall have a zero tolerance of ± 0.5 percent of the designated total batch mass of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be ± 0.5 percent of the individual batch mass designated for each size of aggregate. Equipment for cumulative weighing of cement and mineral admixtures shall have a zero tolerance of ± 0.5 percent of the designated total batch mass of the cement and mineral admixture. Equipment for weighing cement or mineral admixture separately shall have a zero tolerance of ± 0.5 percent of their designated individual batch masses. Equipment for measuring water shall have a zero tolerance of ± 0.5 percent of its designated mass or volume.

- The mass indicated for a batch of material shall not vary from the preselected scale setting by more than the following:

- A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch mass of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch masses.
- B. Cement shall be within 1.0 percent of its designated batch mass. When weighed individually, mineral admixture shall be within 1.0 percent of its designated batch mass. When mineral admixture and cement are permitted to be weighed cumulatively, cement shall be weighed first to within 1.0 percent of its designated batch mass, and the total for cement and mineral admixture shall be within 1.0 percent of the sum of their designated batch masses.
- C. Water shall be within 1.5 percent of its designated mass or volume.

- Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, mineral admixture, or cement plus mineral admixture and aggregates shall not exceed that of commercially available scales having single graduations indicating a mass not exceeding the maximum permissible mass variation above, except that no scale shall be required having a capacity of less than 500 kg, with 0.5 kg graduations.

Section 90-5.03, "Proportioning," excluding Section 90-5.03A, "Proportioning for Pavement," of the Standard Specifications is amended to read:

90-5.03 PROPORTIONING

- Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cement, mineral admixture, and water as provided in these specifications. Aggregates shall be proportioned by mass.

- At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

- Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.

- Bulk "Type IP (MS) Modified" cement that conforms to the provisions in Section 90-2.01, "Portland Cement," shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.

- Bulk cement to be blended with mineral admixture for use in portland cement concrete for pavement and structures may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper with mineral admixture

and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and mineral admixture are weighed cumulatively, the cement shall be weighed first.

- When cement and mineral admixtures are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the mineral admixture shall be individual and distinct from other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material weighing device. The cement and the mineral admixture shall be discharged into the mixer simultaneously with the aggregate.

- The scale and weigh hopper for bulk weighing cement, mineral admixture, and cement plus mineral admixture shall be separate and distinct from the aggregate weighing equipment.

- When the source of an aggregate is changed for concrete structures, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using such aggregates. When the source of an aggregate is changed for other concrete, the Engineer shall be allowed sufficient time to adjust the mix and such aggregates shall not be used until necessary adjustments are made.

- For batches with a volume of one cubic meter or more, the batching equipment shall conform to one of the following combinations:

- A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
- B. Single box and scale indicator for all aggregates.
- C. Single box or separate boxes and automatic weighing mechanism for all aggregates.

- In order to check the accuracy of batch masses, the gross mass and tare mass of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed at the Contractor's expense on scales designated by the Engineer.

Section 90-5.03A, "Proportioning for Pavement," of the Standard Specifications is amended to read:

90-5.03A PROPORTIONING FOR PAVEMENT

- Aggregates and bulk cement, mineral admixture, and cement plus mineral admixture for use in pavement shall be proportioned by mass by means of automatic proportioning devices of approved type conforming to the provisions in this Section 90-5.03A.

- The Contractor shall install and maintain in operating condition an electrically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by mass of the fine aggregate.

- The batching of cement, mineral admixture, or cement plus mineral admixture and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and mineral admixture hoppers or the cement plus mineral admixture hopper are charged with masses which are within the tolerances specified in Section 90-5.02, "Proportioning Devices."

- The discharge gate on the cement and mineral admixture hoppers or the cement plus mineral admixture hopper shall be designed to permit regulating the flow of cement, mineral admixture or cement plus mineral admixture into the aggregate as directed by the Engineer.

- When separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.

- Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.

- When the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.

- The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

The third paragraph in Section 90-6.01, "General," of the Standard Specifications is amended to read:

- Concrete shall be homogeneous and thoroughly mixed. There shall be no lumps or evidence of undispersed cement, mineral admixture, or cement plus mineral admixture.

The third and fourth paragraphs in Section 90-6.02, "Machine Mixing," of the Standard Specifications are amended to read:

- The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one-fourth of the specified mixing time.
- Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, or in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions which reduce or vary the required quantity of cementitious material in the concrete mixture.

The sixth paragraph in Section 90-6.02, "Machine Mixing," of the Standard Specifications is amended to read:

- The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.

The seventh through tenth paragraphs in Section 90-6.03, "Transporting Mixed Concrete," of the Standard Specifications are amended to read:

- When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C, or above, a time less than 1.5 hours may be required.
- When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C, or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.
- Each load of concrete delivered at the job site shall be accompanied by a weight certificate showing the mix identification number, non-repeating load number, date and time at which the materials were batched, the total amount of water added to the load and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weight certificate shall also show the actual scale masses (kilograms) for the ingredients batched. Theoretical or target batch masses shall not be used as a substitute for actual scale masses.
- Weight certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on 90 mm diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be LFCR (one line, separate record) with allowances for sufficient fields to satisfy the amount of data required by these specifications.
- The Contractor may furnish a weight certificate that is accompanied by a separate certificate which lists the actual batch masses or measurements for a load of concrete provided that both certificates are 1) imprinted with the same non-repeating load number that is unique to the contract and 2) delivered to the job site with the load.
- Weight certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications.

Section 90-6.05, "Hand-Mixing," of the Standard Specifications is amended to read:

90-6.05 HAND-MIXING

- Hand-mixed concrete shall be made in batches not more than one-fourth cubic meter and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than 0.3 meters in total depth. On this mixture shall be spread the dry cement and mineral admixture and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

The table in the first paragraph in Section 90-6.06, "Amount of Water and Penetration," of the Standard Specifications is replaced with the following table:

Type of Work	Nominal Penetration (mm)	Maximum Penetration (mm)
Concrete pavement	0-25	40
Non-reinforced concrete facilities	0-35	50
Reinforced concrete structures:		
Sections over 300 mm thick	0-35	65
Sections 300 mm thick or less	0-50	75
Concrete placed under water	75-100	115
Cast-in-place concrete piles	65-90	100

The first paragraph following the table of penetration ranges in Section 90-6.06, "Amount of Water and Penetration," of the Standard Specifications is amended to read:

- The amount of free water used in concrete shall not exceed 183 kg/m³, plus 20 kg for each required 100 kg of cementitious material in excess of 325 kg/m³.

The fourth paragraph in Section 90-6.06, "Amount of Water and Penetration," of the Standard Specifications is amended to read:

- Where there are adverse or difficult conditions which affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic meter of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 kg of water per added 100 kg of cementitious material per cubic meter. The cost of additional cementitious material and water added under these conditions shall be at the Contractor's expense and no additional compensation will be allowed therefor.

Section 90-9.01, "General," of the Standard Specifications is amended to read:

90-9.01 GENERAL

- Concrete compressive strength requirements consist of a minimum strength which must be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or are shown on the plans.
 - The compressive strength of concrete will be determined from test cylinders which have been fabricated from concrete sampled in conformance with California Test 539. Test cylinders will be molded and initial field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with California Test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.
 - When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.
 - When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall, at the Contractor's expense, make corrective changes, subject to approval by the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State \$14 for each in-place cubic meter of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State \$20 for each in place cubic meter of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test which indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."

- If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

- No single compressive strength test shall represent more than 250 cubic meters.
- When a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders which have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. When the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.

- If concrete is specified by compressive strength, then materials, mix proportions, mixing equipment, and procedures proposed for use shall be prequalified prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

- Certified test data, in order to be acceptable, must indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

- Trial batch test reports, in order to be acceptable, must indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 4 MPa greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches which were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

- Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

- The certified test data and trial batch test reports shall include the following information:

- A. Date of mixing.
- B. Mixing equipment and procedures used.
- C. The size of batch in cubic meters and the mass, type and source of ingredients used.
- D. Penetration of the concrete.
- E. The air content of the concrete if an air-entraining admixture is used.
- F. The age at time of testing and strength of concrete cylinders tested.

- Certified test data and trial batch test reports shall be signed by an official of the firm which performed the tests.

- When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.

- After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes which, in the judgment of the Engineer, could result in a lowering of the strength of the concrete below that specified.

- The Contractor's attention is directed to the time required to test trial batches. The Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.

- When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

Section 90-10.02A, "Portland Cement," of the Standard Specifications is renamed "Cementitious Material" and is amended to read:

90-10.02A CEMENTITIOUS MATERIAL

- Cementitious material shall conform to the provisions in Section 90-1.01, "Description." Compressive strength requirements consist of a minimum strength which must be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or are shown on the plans.

The fifth paragraph in Section 90-10.02B, "Aggregate," of the Standard Specifications is deleted.
Section 90-10.03, "Production," of the Standard Specifications is amended to read:

90-10.03 PRODUCTION

- Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice, which will result in concrete that is thoroughly and uniformly mixed, which is suitable for the use intended, and which conforms to provisions specified herein. Recognized standards of good practice are outlined in various industry publications such as those issued by American Concrete Institute, AASHTO, or California Department of Transportation.

- The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."

- The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.

- Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 32°C will be considered as conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.

- The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.

- The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.

- Each load of ready-mixed concrete shall be accompanied by a weight certificate which shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weight certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.

- A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

The third and fourth paragraphs in Section 90-11.02, "Payment," of the Standard Specifications are amended to read:

- Should the Engineer order the Contractor to incorporate admixtures into the concrete when their use is not required by these specifications or the special provisions, furnishing the admixtures and adding them to the concrete will be paid for as extra work as provided in Section 4-1.03D.

- Should the Contractor use admixtures in conformance with the provisions in Section 90-4.05, "Optional Use of Chemical Admixtures," or Section 90-4.07, "Optional Use of Air-entraining Admixtures," or should the Contractor request and obtain permission to use other admixtures for the Contractor's benefit, the Contractor shall furnish those admixtures and incorporate them in the concrete at the Contractor's expense and no additional compensation will be allowed therefor.

8-2.02 FREEZING CONDITION REQUIREMENTS

Portland cement concrete and precast portland cement concrete products shall contain not less than 350 kilograms of cement per cubic meter unless a higher cement content is required elsewhere in these special provisions.

An air-entraining admixture conforming to the requirements in Section 90-4, "Admixtures," of the Standard Specifications shall be added to the concrete at the rate required to result in an air content of 6 ± 1.5 percent in the freshly mixed concrete, unless a different air content is specified elsewhere in these special provisions.

SECTION 8-3. WELDING

8-3.01 WELDING ELECTRODES

Flux core welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform any type of welding for this project.

SECTION 9. (BLANK)

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

Attention is directed to "Maintaining Traffic" and "Temporary Pavement Delineation" of these special provisions and to the stage construction sheets of the plans.

Asphalt concrete pavement shall not be placed between October 1 and May 1, unless otherwise directed by the Engineer in writing.

Attention is directed to construction of the detention pond and oil/water separator. Construction of this system shall proceed prior to or in conjunction with any earthwork activities.

Attention is directed to "Progress Schedule (Critical Path)" of these special provisions regarding the submittal of a general time-scaled logic diagram within 10 days after approval of the contract. The diagram shall be submitted prior to performing any work that may be affected by any proposed deviations to the construction staging of the project.

Before obliterating any pavement delineation that is to be replaced on the same alignment and location, as determined by the Engineer, the pavement delineation shall be referenced by the Contractor, with a sufficient number of control points to reestablish the alignment and location of the new pavement delineation. The references shall include the limits or changes in striping pattern, including one- and 2-way barrier lines, limit lines, crosswalks and other pavement markings. Full compensation for referencing pavement delineation shall be considered as included in the contract prices paid for new pavement delineation and no additional compensation will be allowed therefor.

10-1.02 WATER POLLUTION CONTROL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

Water pollution control work shall conform to the requirements in the Construction Contractor's Guide and Specifications of the Caltrans Storm Water Quality Handbooks, dated April 1997, and addenda thereto issued up to and including the date of advertisement of the project, hereafter referred to as the "Handbook." Copies of the Handbook may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.

Copies of the Handbook are also available for review at the Northern Region Construction Office at 379-A Colusa Highway, Yuba City, California 95991.

The Contractor shall know and fully comply with the applicable provisions of the Handbook and Federal, State, and local regulations that govern the Contractor's operations and storm water discharges from both the project site and areas of disturbance outside the project limits during construction.

Unless arrangements for disturbance of areas outside the project limits are made by the Department and made part of the contract, it is expressly agreed that the Department assumes no responsibility whatsoever to the Contractor or property owner with respect to any arrangements made between the Contractor and property owner to allow disturbance of areas outside the project limits.

The Contractor shall be responsible for the costs and for liabilities imposed by law as a result of the Contractor's failure to comply with the requirements set forth in this section "Water Pollution Control" including, but not limited to, compliance with the applicable provisions of the Handbook and Federal, State, and local regulations. For the purposes of this paragraph, costs and liabilities include, but are not limited to, fines, penalties, and damages whether assessed against the State or the Contractor, including those levied under the Federal Clean Water Act and the State Porter Cologne Water Quality Act.

In addition to the remedies authorized by law, an amount of the money due the Contractor under the contract, as determined by the Department, may be retained by the State of California until disposition has been made of the costs and liabilities.

The retention of money due the Contractor shall be subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has retained funds and it is subsequently determined that the State is not subject to the costs and liabilities in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained at the legal rate of interest for the period of the retention.

Conformance with the provisions in this section "Water Pollution Control" shall not relieve the Contractor from the Contractor's responsibilities as provided in Section 7, "Legal Relations and Responsibilities," of the Standard Specifications.

WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES

As part of the water pollution control work, a Water Pollution Control Program, hereafter referred to as the "WPCP," is required for this contract. The WPCP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Handbook, and these special provisions.

No work having potential to cause water pollution, as determined by the Engineer, shall be performed until the WPCP has been approved by the Engineer.

Within 30 days after the approval of the contract, the Contractor shall submit 3 copies of the WPCP to the Engineer. The Engineer will have 7 days to review the WPCP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the WPCP within 7 days of receipt of the Engineer's comments. The Engineer will have 7 days to review the revisions. Upon the Engineer's approval of the WPCP, 3 additional copies of the WPCP incorporating the required changes shall be submitted to the Engineer. Minor changes or clarifications to the initial submittal may be made and attached as amendments to the WPCP. In order to allow construction activities to proceed, the Engineer may conditionally approve the WPCP while minor revisions or amendments are being completed.

The WPCP shall identify pollution sources that may adversely affect the quality of storm water discharges associated with the project and shall identify water pollution control measures, hereafter referred to as control measures, to be constructed, implemented, and maintained in order to reduce to the extent feasible pollutants in storm water discharges from the construction site during construction under this contract.

The WPCP shall incorporate control measures in the following categories:

- A. Soil stabilization practices;
- B. Sediment control practices;
- C. Sediment tracking control practices;
- D. Wind erosion control practices; and
- E. Nonstorm water management and waste management and disposal control practices.

Specific objectives and minimum requirements for each category of control measures are contained in the Handbook.

The Contractor shall consider the objectives and minimum requirements presented in the Handbook for each of the above categories. When minimum requirements are listed for any category, the Contractor shall incorporate into the WPCP and implement on the project, one or more of the listed minimum controls required in order to meet the pollution control objectives for the category. In addition, the Contractor shall consider other control measures presented in the Handbook and shall incorporate into the WPCP and implement on the project the control measures necessary to meet the objectives of the WPCP. The Contractor shall document the selection process in conformance with the procedure specified in the Handbook.

The following contract items of work, where shown on the project plans, shall be incorporated into the WPCP as critical temporary control measures: Straw Bale Barrier. The Contractor shall consider other control measures to supplement these critical temporary control measures when necessary to meet the pollution control objectives of the WPCP.

The following contract items of work, as shown on the project plans, shall be incorporated in the WPCP as permanent post-construction control measures: Oil/Water Separator and Detention Pond. These control measures shall be utilized as construction period control measures. Attention is directed to "Order of Work" of these special provisions. The Contractor shall consider other control measures to supplement these permanent, post-construction control measures when necessary to meet the pollution control objectives of the WPCP. The Contractor shall maintain and protect the permanent control measures throughout the duration of the project and shall restore these controls to the lines and grades shown on the plans prior to acceptance of the project.

The WPCP shall include, but not be limited to, the following items as described in the Handbook:

- A. Project description and Contractor's certification;

- B. Project information;
- C. Pollution sources, control measures, and water pollution control drawings; and
- D. Amendments, if any.

The Contractor shall amend the WPCP, graphically and in narrative form, whenever there is a change in construction activities or operations which may affect the discharge of significant quantities of pollutants to surface waters, ground waters, municipal storm drain systems or when deemed necessary by the Engineer. The WPCP shall be amended if the WPCP has not achieved the objective of reducing pollutants in storm water discharges. Amendments shall show additional control measures or revised operations, including those in areas not shown in the initially approved WPCP, which are required on the project to control water pollution effectively. Amendments to the WPCP shall be submitted for review and approval by the Engineer in the same manner specified for the initially approved WPCP. Amendments shall be dated and attached to the on-site WPCP document.

The Contractor shall keep a copy of the WPCP, together with updates, revisions and amendments at the project site.

WPCP IMPLEMENTATION

Upon approval of the WPCP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, and maintaining the control measures included in the WPCP and any amendments thereto and for removing and disposing of temporary control measures. Unless otherwise directed by the Engineer or specified in these special provisions, the Contractor's responsibility for WPCP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of control measures are specified in the Handbook and these special provisions.

Soil stabilization practices and sediment control measures, including minimum requirements, shall be provided throughout the winter season, defined as between October 15 and April 15.

Implementation of soil stabilization practices and sediment control measures for soil-disturbed areas on the project site shall be completed, except as provided for below, not later than 20 days prior to the beginning of the winter season or upon start of applicable construction activities for projects which begin either during or within 20 days of the winter season.

Throughout the winter season, the active, soil-disturbed area of the project site shall be not more than 1.9 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active, soil-disturbed area limit. The Contractor shall demonstrate the ability and preparedness to fully deploy soil stabilization practices and sediment control measures to protect soil-disturbed areas on the project site before the onset of precipitation. A quantity of soil stabilization and sediment control materials shall be maintained on site equal to 125 percent of that sufficient to protect unprotected, soil-disturbed areas on the project site. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to fully deploy control measures required to protect unprotected, soil-disturbed areas on the project site prior to the onset of precipitation. A current inventory of control measure materials and the detailed mobilization plan shall be included as part of the WPCP.

Throughout the winter season, soil-disturbed areas on the project site shall be considered to be nonactive whenever soil disturbing activities are expected to be discontinued for a period of 20 or more days and the areas are fully protected. Areas that will become nonactive either during the winter season or within 20 days thereof shall be fully protected with soil stabilization practices and sediment control measures within 10 days of the discontinuance of soil disturbing activities or prior to the onset of precipitation, whichever is first to occur.

Throughout the winter season, active soil-disturbed areas of the project site shall be fully protected at the end of each day with soil stabilization practices and sediment control measures unless fair weather is predicted through the following work day. The weather forecast shall be monitored by the Contractor on a daily basis. The National Weather Service forecast shall be used. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted prior to the end of the following work day, construction scheduling shall be modified, as required, and functioning control measures shall be deployed prior to the onset of the precipitation.

The Contractor shall implement, year-round and throughout the duration of the project, control measures included in the WPCP for sediment tracking, wind erosion, nonstorm water management, and waste management and disposal.

The Engineer may order the suspension of construction operations which create water pollution if the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

MAINTENANCE

To ensure the proper implementation and functioning of control measures, the Contractor shall regularly inspect and maintain the construction site for the control measures identified in the WPCP. The Contractor shall identify corrective actions and time needed to address any deficient measures or reinstate any measures that have been discontinued.

The construction site inspection checklist provided in the Handbook shall be used to ensure that the necessary measures are being properly implemented, and to ensure that the control measures are functioning adequately. One copy of each site inspection record shall be submitted to the Engineer.

During the winter season, inspections of the construction site shall be conducted by the Contractor to identify deficient measures, as follows:

- A. Prior to a forecast storm;
- B. After all precipitation which causes runoff capable of carrying sediment from the construction site;
- C. At 24-hour intervals during extended precipitation events; and
- D. Routinely, at a minimum of once every 2 weeks.

If the Contractor or the Engineer identifies a deficiency in the deployment or functioning of an identified control measure, the deficiency shall be corrected immediately. The deficiency may be corrected at a later date and time if requested by the Contractor and approved by the Engineer in writing, but not later than the onset of subsequent precipitation events. The correction of deficiencies shall be at no additional cost to the State.

PAYMENT

Full compensation for conforming to the provisions in this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

Those control measures which are shown on the plans and for which there is a contract item of work will be measured and paid for as that contract item of work.

The Engineer will retain an amount equal to 25 percent of the estimated value of the contract work performed during estimate periods in which the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

Retentions for failure to conform to the provisions in this section "Water Pollution Control" shall be in addition to the other retentions provided for in the contract. The amounts retained for failure of the Contractor to conform to the provisions in this section will be released for payment on the next monthly estimate for partial payment following the date that a WPCP has been implemented and maintained and water pollution is adequately controlled, as determined by the Engineer.

10-1.03 TEMPORARY EROSION CONTROL

Temporary erosion control shall conform to the provisions for erosion control in Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions.

Attention is directed to "Water Pollution Control" of these special provisions.

Temporary erosion control work shall consist of applying erosion control materials to embankment slopes, excavation slopes and other areas designated on the plans. Temporary erosion control work shall be completed in the designated areas within 10 days after an area becomes inactive during this period as defined in "Water Pollution Control" of these special provisions.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and the following:

Straw

Straw shall be derived from wheat or barley. Wheat and barley straw shall not be derived from dry farmed cereal crops.

APPLICATION

Temporary erosion control material shall be applied in 1 application as follows:

- A. Straw shall be applied at the rate of 4.5 tonnes per hectare based on slope measurements. Incorporation of straw will not be required.

MEASUREMENT AND PAYMENT

Temporary erosion control work will be measured by the square meter or hectare, whichever is designated in the contract item. The quantity of temporary erosion control to be paid for by the square meter or hectare will be calculated on the basis of actual or computed slope measurements.

Items of temporary erosion control work will be either paid for at the contract price per square meter or hectare for temporary erosion control, whichever is involved in the temporary erosion control work and designated in the contract items.

Temporary erosion control placed at locations other than as shown on the project plans or directed by the Engineer, in conformance with the Contractor's Water Pollution Control Program, will not be measured and will be paid for as specified in "Water Pollution Control" of these special provisions.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary erosion control required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to temporary erosion control.

10-1.04 PRESERVATION OF PROPERTY

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing plants, that are not to be removed and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be 615 mm box and the minimum size of shrub replacement shall be No. 15 container. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs and other plants shall be completed not less than 20 working days prior to acceptance of the contract. Replacement plants shall be watered as necessary to maintain the plants in a healthy condition.

10-1.05 TEMPORARY STRAW BALE BARRIER

Temporary straw bale barrier shall conform to the details shown on the plans and these special provisions.

Temporary straw bale barrier work shall consist of furnishing, installing, constructing, anchoring, staking, maintaining, and removing bales at the locations shown on the plans.

Preparation shall conform to the provisions in Section 20-3.02, "Preparation," of the Standard Specifications.

Attention is directed to "Water Pollution Control" of these special provisions.

MATERIALS

Straw for straw bales shall conform to the provisions in Section 20-2.06, "Straw," of the Standard Specifications.

Each straw bale shall be a minimum of 360 mm wide, 450 mm in height, 900 mm in length and shall have a minimum mass of 23 kg. The straw bale shall be composed entirely of vegetative matter, except for binding material.

Stakes shall be 50 mm x 50 mm wood posts. Each stake shall have a minimum length of one meter.

Bales shall be bound by either wire, nylon or polypropylene string. Jute and cotton binding shall not be used. Wire shall be a minimum of 1.57 mm (16-gage) baling wire. Nylon or polypropylene string shall be approximately 2 mm in diameter with 360 N of breaking strength.

INSTALLATION

Temporary straw bale barriers shall be installed as shown on the plans and in conformance with Detail Sheet 1 in Appendix C, CD37(2) in the Construction Contractors Guide and Specifications of the Caltrans Storm Water Quality Handbooks.

Bales shall be placed so that the binding wire or string is not in contact with the ground. Bales shall be securely anchored in place by 2 stakes driven through the bales. The first stake in each bale shall be driven toward the previously laid bale to force the bales together.

Temporary straw bale barriers shall be maintained to provide for adequate sediment holding capacity. Sediment deposits shall be removed when the sediment deposit reaches one-third of the straw bale barrier height. Removed sediment shall be deposited within the project in such a way that the sediment is not subject to erosion by wind or water, or as directed by the Engineer. Installed bales shall be removed and replaced as required to adapt to changing conditions.

When no longer required for the intended purpose, as determined by the Engineer, temporary straw bale barrier shall be removed from the site of the work. As an option, the straw bales may be spread on slopes or other areas designated by the Engineer.

Holes, depressions or any other ground disturbance caused by the removal of the temporary straw bale barrier shall be backfilled and repaired in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MEASUREMENT AND PAYMENT

Temporary straw bale barrier will be measured by the unit as determined from actual count in place.

The contract unit price paid for temporary straw bale shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary straw bale barriers, complete in place, including maintenance and removal of materials, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Temporary straw bale barriers placed at locations other than as shown on the project plans or directed by the Engineer, in conformance with the Contractor's Water Pollution Control Program will not be measured and will be paid for as specified in "Water Pollution Control" of these special provisions.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary straw bale required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to temporary straw bale.

10-1.06 PROGRESS SCHEDULE (CRITICAL PATH)

Progress schedules will be required for this contract and shall conform to the requirements of these special provisions. Progress schedules shall utilize the Critical Path Method (CPM). Attention is directed to "Cooperation" and "Obstructions" of these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7, "Legal Relations and Responsibility," of the Standard Specifications.

DEFINITIONS

The following definitions shall apply to these special provisions:

- A. Activity.—A task or item of work that shall be performed in order to complete a project.
- B. Baseline Schedule.—The initial CPM progress schedule as accepted by the Engineer representing the Contractor's original work plan.
- C. Concurrent Delay.—Two or more delays on the critical path that occur at the same time.
- D. Contract Completion Date.—The date the Contractor is contractually obligated to complete the project, including any authorized adjustments, as specified in Section 8-1.06, "Time of Completion," of the Standard Specifications.
- E. Contractor Delay.—A delay that extends the time required to complete a controlling operation caused by and within the control of the Contractor, subcontractors at any tier or suppliers.
- F. Controlling Operation.—A feature of work or activity on the critical path.
- G. Critical Path.—In a project network, the sequence of activities yielding the longest path in a CPM analysis necessary to complete the project.
- H. Critical Path Method (CPM).—A mathematical calculation using the sequence of activities and their interrelationships, interdependencies, resources, and durations to determine the critical path that shows the expected time to complete a project.
- I. Data Date.—The day after the date through which progress updates have been calculated; everything occurring earlier than the data date is "As-Built"; and everything on or after the data date is "Planned."
- J. Early Completion Time.—The difference in time between the contract completion date and the current State-accepted scheduled completion date.
- K. Float.—The amount of time between the early start date and the late start date or the early finish date and the late finish date of any activity or group of activities in the network.
- L. Free Float.—The amount of time an activity can be delayed before delaying a subsequent activity.
- M. Fragnet.—A section or fragment of the network diagram comprised of a group of activities.
- N. Milestone.—A marker in a network which is typically used to mark a point in time or denote the beginning or end of a sequence of activities. A milestone has zero duration and zero resources, but will otherwise function in the network as if the milestone were an activity.
- O. Narrative Report.—A report that identifies potential problem areas, current and anticipated delaying factors and their impact, actions taken or proposed, proposed changes in schedule logic, extension or contraction of activities, proposed addition or deletion of activities, explanation for changes in the critical path, explanation for changes in scheduled completion date, out of sequence work, and other topics related to job progress or scheduling.
- P. Near Critical Path.—A path having 10 working days or less of total float.
- Q. Punch List.—A list of details needing attention to complete task or work for both contract item and extra work.
- R. Schedule Revision.—A change in the future portion of the schedule that modifies logic; alters construction sequences such as performing sequential activities concurrently or concurrent activities sequentially; adds or deletes activities or significantly alters activity durations, as determined or accepted by the Engineer.
- S. Scheduled Completion Date.—The Contractor's scheduled completion date as shown on the accepted baseline schedule as modified by subsequent accepted schedule updates and revisions.
- T. Time Impact Analysis.—An analysis demonstrating the estimated time impact of a contract change order, delay or other event on the scheduled completion date.

- U. Total Float.—The amount of time that an activity may be delayed without delaying the scheduled completion date.
- V. Update.—The routine modification of the CPM progress schedule through a regular monthly review to incorporate actual past progress to date by activity, projected completion dates and approved time adjustments.

MATERIALS (COMPUTER SYSTEM)

The Contractor shall provide a computer system for the State's exclusive possession and use for CPM progress schedules. The minimum computer system to be furnished shall be complete with keyboard, mouse, monitor, printer and plotter. The system shall conform to the following requirements:

- A. Latest industry-available Intel Pentium processor, Motorola RISC processor or equivalent.
- B. Latest computer operating system software compatible with the selected processor, either Windows or MACINTOSH.
- C. Minimum of 64 megabytes of random access memory (RAM).
- D. Internal drives, including: one 4-gigabyte minimum hard disk drive, one 1.44-megabyte 90 mm (3.5-inch) floppy disk drive and one 32x speed CD-ROM drive.
- E. Internal fax/modem, latest speed and software version of U.S. Robotics, 3COM or equivalent.
- F. A 430 mm (17-inch) minimum, color monitor capable of at least 1,024 x 768 pixels.
- G. A color-ink-jet-type, B-size plotter compatible with the selected system capable of printing fully legible, time-scaled charts, network diagrams and reports.
- H. A manual parallel cable switching device, with connecting cables, allowing the user to alternate printing between the plotters.
- I. CPM software shall be compatible with the hardware provided, shall be the latest version of Primavera Project Planner for Windows, SureTrak for Windows, or equal, and shall be able to create files that can easily be imported into the latest version of Primavera.
- J. General software shall be the latest version of McAfee VirusScan virus protection or equal and shall be compatible with the hardware provided.
- K. Upgrades to the CPM and general software shall be provided, as the upgrades become available.

The computer hardware and software furnished by the Contractor shall be compatible with that used for the production of the CPM progress schedule required by these special provisions, including original instruction manuals and other documentation normally provided with the CPM and general software. Before delivery and setup of the computer system, the Contractor shall submit, for approval of the Engineer, a detailed list of the computer hardware and software the Contractor proposes to furnish, including an itemized schedule of costs for the system.

The Contractor shall furnish, install, set up, maintain, and repair the computer system ready-for-use, and provide plotter supplies as necessary during the course of the project at a location determined by the Engineer. The first submittal of the baseline schedule will not be considered complete until the hardware and software are installed and ready for use with the submitted baseline schedule. The Contractor shall instruct and assist the Engineer in the use of the hardware and software. When requested by the Engineer, the Contractor shall provide one 8-hour session of outside commercial training in the use of the CPM software for a maximum of 2 project staff at a location acceptable to the Engineer. Hardware repairs shall be made within 48 hours of notification by the Engineer, or replacement equipment shall be furnished and installed by the Contractor until repairs have been completed.

Computer hardware and software furnished shall remain the property of the Contractor and shall be removed by the Contractor upon acceptance of the contract if no claims involving contract progress are pending. If contract claims involving contract progress are pending, computer hardware or software shall not be removed until the final estimate has been submitted to the Contractor.

GENERAL

Early completion time shall be considered a resource for the exclusive use of the Contractor. The Contractor may increase early completion time by increasing production or reallocating resources to be more efficient, or by proposing, and the State accepting, contract change orders that are the result of significant Contractor development and investment or from an appropriate share of an accepted cost reduction proposal in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

The State may reduce contract working days if the action is the result of a contract change order other than those that result from significant Contractor development and investment. The Contractor shall conduct a time impact analysis to determine the effect of the change in the same manner described in "Schedule Time Adjustment" specified herein, and shall include the impacts acceptable to the Engineer in the next update or revision.

The Contractor shall be responsible for assuring that the work sequences are logical and the network shows a coordinated plan for complete performance of the work. Failure of the Contractor to include in the schedule any element of work

required for the performance of the contract shall not relieve the Contractor from completing the work within the time limit specified in the contract. If the Contractor or the Engineer discovers an undefined element of work, activity or logic, it shall be corrected by the Contractor in a schedule revision, as specified in these special provisions. If a planned activity requires greater-than-normal daily resources to accomplish, schedule revision submittals shall include a narrative describing the activity, and the amount and use of the extraordinary resources.

The Baseline Schedule or Schedule Update submitted for acceptance shall not show variances from the requirements of these special provisions unless approved by the Engineer. The Contractor shall make specific mention of the variations in the letter of transmittal and shall make the associated adjustments to the project schedule. The Contractor will not be relieved of the responsibility for executing the work in strict conformance with the provisions in the requirements of these special provisions. In the event of a conflict between the requirements of these special provisions and the information provided or shown on an accepted schedule, the requirements of these special provisions shall take precedence.

Each schedule submitted to the Engineer shall comply with the limits imposed by these special provisions, with the specified intermediate milestones and completion dates, and with the constraints, restraints or sequences included in these special provisions, except that after the Engineer accepts the baseline schedule, the Contractor may show a late scheduled completion date on subsequent updates or revisions. The degree of detail shall include factors to the satisfaction of the Engineer, including, but not limited to:

- A. Physical breakdown of the project;
- B. Contract milestones and completion dates, substantial completion dates, constraints, restraints, sequences of work shown in these special provisions, the planned substantial completion date, and the final completion date;
- C. Type of work to be performed, the sequences and the activities to be performed by subcontractors;
- D. Procurement, submittal, submittal review, manufacture, test, delivery, and installation of major materials and equipment that require approval;
- E. Preparation, submittal and approval of shop or working drawings and material samples showing time, as specified in these special provisions for the Engineer's review;
- F. Identification of interfaces and dependencies with preceding, concurrent and follow-on contractors, railroads, and utilities as indicated in these special provisions;
- G. Identification of each utility relocation or interface as a separate activity;
- H. Batch plant erection and plant certification;
- I. Erection and removal of falsework or shoring;
- J. Submission and approval of reports or results for major tests, such as that for pile loading or traffic controllers;
- K. Indicate long-term ramp and connector closing and opening events, traffic switches, and opening and closing of pavements to traffic as separate one day activities;
- L. Punch-list and final clean-up;
- M. State-owned float as the last activity in the schedule, at the end of which is the Scheduled Completion Date;
- N. Activity coding conventions shall include the following:

	Code	Value	Description
(1) Responsibility	RESP	CT	Caltrans
		UTIL	Utility Company
		RAIL	Railroad
		xxxx	Contractor
		xxxx	Subcontractor
		xxxx	others, as needed
(2) Stage	STGE	1	Stage 1
		2	Stage 2
		other designations	other descriptions, as needed
(3) Phase	PHAS	1	Phase 1
		2	Phase 2
		other phases	other phases, as needed
(4) Utilities	UTIL	PGE	Pacific Gas & Electric
		BELL	Pacific Bell
		GTE	GTE
		SCE	Southern California Edison
		other utilities	other utilities, as needed

The Contractor may include additional coding conventions, such as Ramps (RAMP), Facilities (FAC), and Events (EVNT).

The work shall be executed in the sequence indicated in the accepted baseline schedule and subsequent accepted updates and revisions. Once the Engineer accepts a CPM schedule, the Contractor shall neither artificially improve the progress nor artificially change the quantity of float in any part of the schedule by artificially adding or deleting activities, revising schedule logic restraints, or changing planned activity durations. Schedule changes of planned work shall be documented in a properly submitted revision. The Contractor may improve the progress by performing sequential activities concurrently or by performing activities more quickly than planned. In the case of multiple critical paths, float generated by early completion of one or a sequence of activities will be considered in determining if that sequence of activities remains on the critical path.

The schedule shall be modified to reflect actual events and conditions, including non-work days, as these events and conditions occur for historical purposes and for use in time impact analysis. Submittals and Engineer review time shall be shown in the progress schedule, including CPM schedule updates and revisions. The duration of the Engineer review activity shall be 15 days unless specified otherwise in these special provisions.

The Contractor shall be allowed to show an early or late scheduled completion date on schedule updates and revisions. The Engineer will use the most current, accepted schedule update and revision, and Contractor-provided cause, time-impact and schedule-delay analysis that is acceptable to the Engineer to determine apparent impacts.

The Engineer shall have 20 days to review and accept or reject the baseline schedule. The Engineer shall have 15 days to review and accept or reject any updated or revised schedule. Rejected schedules shall be resubmitted to the Engineer within 5 days, at which time a new review period of 5 days will begin. After the baseline schedule is accepted, schedules that are not accepted or rejected within the required review period will be deemed to have been accepted by the Engineer. Acceptance of a schedule does not relieve the Contractor of the responsibility of submitting complete and accurate information.

PRE-CONSTRUCTION SCHEDULING CONFERENCE

The Contractor shall schedule, and the Engineer will conduct, a Pre-construction Scheduling Conference with the Contractor's Project Manager and Construction Scheduler within 10 days after approval of the contract. At this meeting, the Engineer will review the requirements of this section of the special provisions with the Contractor. The Contractor shall submit a general time-scaled logic diagram displaying the major activities and sequence of planned operations and shall be prepared to discuss the proposed work plan and schedule methodology that complies with the requirements of these special provisions. If the Contractor proposes deviations to the construction staging of the project, the Contractor shall submit a general time-scaled logic diagram displaying the deviations and resulting time impacts and shall be prepared to discuss the proposal. At this meeting, the Contractor shall additionally submit the alpha-numeric coding structure and the activity identification system for labeling the work activities. To easily identify relationships, each activity description shall indicate its associated scope or location of work by including such terms as quantity of material, type of work, Bridge Number, Station to Station location, side of highway (such as left, right, northbound, southbound), lane number, shoulder, ramp name, ramp line descriptor or mainline. The Engineer will review and comment on the logic diagram, the coding structure and activity identification system within 15 days after submission by the Contractor. The Contractor shall make modifications to

the time-scaled logic diagram, the coding structure, and activity identification system that the Engineer requests and shall employ that coding structure and identification system. The Contractor shall include the Engineer-requested modifications in the baseline schedule.

NETWORK DIAGRAM AND PROJECT SCHEDULE REPORTS

Schedules submitted to the Engineer, including the baseline schedule, shall include originally-plotted time-scaled network diagram(s). Network diagrams shall be based on early start and early finish dates of activities shown. The network diagrams submitted to the Engineer shall also be accompanied by the CPM software-generated tabular reports for each activity included in the project schedule. Three different report sorts shall be provided: Early Start, Total Float, and Activity Number which shall show the predecessors and successors for each activity. Tabular reports, 215 mm x 280 mm size (8 1/2" x 11"), shall be submitted to the Engineer and shall include at a minimum, the following:

- A. Data date;
- B. Predecessor and successor activity numbers and descriptions;
- C. Activity number and description;
- D. Activity code(s);
- E. Scheduled, or actual and remaining durations for each activity;
- F. Earliest start date (by calendar date);
- G. Earliest finish date (by calendar date);
- H. Actual start date (by calendar date);
- I. Actual finish date (by calendar date);
- J. Latest start date (by calendar date);
- K. Latest finish date (by calendar date);
- L. Free Float, in work days;
- M. Total Float, in work days;
- N. Percentage of activity complete and remaining duration for incomplete activities;
- O. Lag(s); and
- P. Imposed constraints.

The networks shall be drafted time-scaled to show a continuous flow of information from left to right. The primary path(s) of criticality shall be clearly and graphically identified on the network(s). The network diagram shall be prepared on E-size sheets, 860 mm x 1120 mm (34" x 44"), and shall have a title block in the lower right-hand corner and a timeline on each page. Exceptions to the size of the network sheets and the use of computer graphics to generate the networks shall be subject to the Engineer's approval.

The narrative report shall be organized as follows:

- A. Contractor's Transmittal Letter;
- B. Work completed during the period;
- C. Identification of unusual resources: manpower, material, or equipment restrictions or use, including multiple shifts, 6-day work weeks, specified overtime, or work at times other than regular days or hours;
- D. Description of the current critical path;
- E. Changes to the critical path since the last schedule submittal;
- F. Description of problem areas;
- G. Current and anticipated delays:
 - 1. Cause of delay,
 - 2. Impact of delay on other activities, milestones and completion dates,
 - 3. Corrective action and schedule adjustments to correct the delay;
- H. Pending items and status thereof:
 - 1. Permits,
 - 2. Change Orders,
 - 3. Time Adjustments,
 - 4. Non-Compliance Notices;
- I. Contract completion date(s) status:
 - 1. Ahead of schedule and number of days,

2. Behind schedule and number of days,
3. If date changes, explain the cause;

J. Attached Updated Network Diagram and Reports.

Schedule network diagrams, tabular reports and narrative reports shall be submitted to the Engineer for acceptance in the following quantities:

- A. Two sets of originally-plotted, time-scaled network diagram(s);
- B. Two copies of each of the three sorts of the CPM software-generated tabular reports 215 mm x 280 mm size (8 1/2" x 11");
- C. One 1.44-megabyte 89 mm (3.5 inch) floppy diskette containing the schedule data;
- D. Two copies of the narrative report.

BASELINE SCHEDULE REQUIREMENTS

Within 30 days after approval of the contract, the Contractor shall submit a baseline schedule to the Engineer. The baseline project schedule shall have a data date of the first working day of the contract and shall not include any completed work to-date. The baseline schedule shall be practicable; include the entire scope of work; meet interim target dates, milestones, stage construction requirements, and internal time constraints; show logical sequence of activities; and shall not extend beyond the number of working days originally provided in these special provisions. An early completion schedule will be acceptable provided that the schedule meets the requirements of these special provisions and the Standard Specifications.

The baseline CPM progress schedule submitted by the Contractor shall have a sufficient number of activities to assure adequate planning of the project, to permit monitoring and evaluation of progress, and the analysis of time impacts. The baseline schedule shall depict how the Contractor plans to complete the whole work involved, and shall show the activities that define the critical path. Multiple critical paths and near-critical paths shall be kept to a minimum, as determined by the Engineer. A total of not more than 50 percent of the baseline schedule activities shall be critical or near-critical, unless otherwise approved by the Engineer.

Activities shall have a duration of not less than one working day nor more than 20 working days, unless otherwise approved by the Engineer. The activities in the baseline schedule, with the exception of the first and last activities, shall have a minimum of one predecessor and a minimum of one successor. The baseline schedule shall not attribute negative float or negative lag to an activity.

MONTHLY SCHEDULE UPDATES

On or before the first calendar day of each month, the Contractor shall meet with the Engineer to review contract progress. At the monthly progress meeting the Contractor shall submit to the Engineer an update of the network diagram and project schedule reports as defined above. Update schedules shall have a data date of the twenty-first calendar day of the month, or other date as established by the Engineer, and shall include the information available up to that date. Durations for work that has been completed will be shown on the schedule as the work actually occurred, including Engineer submittal review and Contractor resubmittal times.

SCHEDULE REVISIONS

When the Contractor proposes a revision to an accepted schedule, the Contractor shall state in writing the reasons for the change, as well as the specifics, such as, but not limited to, revisions to activities, logic, durations, and other matters pertinent to the proposed revisions. If the Engineer considers a schedule revision to be of a major nature, the Engineer may require the Contractor to revise and submit for acceptance the affected portion(s) of the project schedule and an analysis to show the effect on the entire project. In addition to the revision submittal, the Contractor shall submit a schedule update with the same data date as the revision which is to reflect the project condition just prior to implementing the revision. The Contractor shall discuss contemplated revisions with the Engineer prior to the submittal.

Within 15 days, the Contractor shall submit a revised CPM network for approval when requested by the Engineer, or when any of the following occurs:

- A. There is a significant change in the Contractor's operations that affects the critical or near critical path(s).
- B. The scheduled completion date of the current submitted updated CPM schedule indicates that the contract progress is 20 days or more behind the current accepted schedule or revision.
- C. The Contractor or the Engineer considers that an approved or anticipated change will impact the critical or near critical path or contract progress.

SCHEDULE TIME ADJUSTMENT

When the Contractor requests a time adjustment due to contract change orders or delays, or if the Contractor or the Engineer considers that an approved or anticipated change will impact the critical path or contract progress, the Contractor shall submit a written time impact analysis to the Engineer illustrating the impacts of each change or delay on the current scheduled completion date or milestone completion date. The analysis shall use the currently accepted schedule that has a data date closest to and prior to the event. If the Engineer determines that the currently accepted schedule does not appropriately represent the conditions prior to the event, the schedule shall be updated to the day before the event being analyzed. An additional analysis shall be performed after the completion of the event. If the event is on the critical path at the time of its completion, then the difference between the scheduled completion dates of these 2 analyses shall be equal to the adjustment in time. The time impact analysis shall include one or more fragment(s) demonstrating how the Contractor proposes to incorporate the event(s) into the schedule, including logic and duration of the proposed activities. Until such time that the Contractor provides the analysis, the Engineer may, at his option, construct and utilize the project as-built schedule or other recognized method to determine adjustments in contract time.

Time impact analyses shall be submitted in duplicate within 15 days of a delay and shall be used in determining contract change order days. Approval or rejection of each time impact analysis by the Engineer will be made within 15 days after receipt of the time impact analysis. In the event the Contractor does not agree with the decision of the Engineer regarding the impact of a change or delay, notice shall be given in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications. The third paragraph of Section 4-1.03A of the Standard Specifications shall not apply.

FINAL SCHEDULE UPDATE

Within 30 days after acceptance of the contract by the Director, the Contractor shall submit a final update of the schedule (as-built schedule) with actual start and actual finish dates for the activities. The Contractor shall submit a written certificate with this submittal signed by the Contractor's Project Manager and an officer of the company stating "To the best of my knowledge, the enclosed final update of the project schedule reflects the actual start and completion dates of the actual activities for the project contained herein." An officer of the company may delegate in writing the authority to sign the certificate to a responsible manager. Submittal of the final schedule update and the certification shall be a condition precedent to the release of any retained funds under the contract.

PAYMENT

Progress schedule (critical path) will be paid for at a lump sum price. The contract lump sum price paid for progress schedule (critical path) shall include full compensation for furnishing all labor, material (including computer hardware and software), tools, equipment, and incidentals; and for doing all the work involved in preparing, furnishing, updating, and revising progress schedules; maintaining and repairing the computer hardware; and instructing and assisting the Engineer in the use of the computer hardware and software, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer. Payments for the progress schedule (critical path) contract item will be made as follows:

- A. A total of 50 percent of the progress schedule (critical path) contract item amount will be made upon achieving all of the following: 5 percent of all work completed, accepted baseline, all accepted required schedule updates and revisions, and required CPM training.
- B. A total of 60 percent of the progress schedule (critical path) contract item amount will be made upon achieving all of the following: 25 percent of all work completed, accepted baseline, and all accepted required schedule updates and revisions.
- C. A total of 75 percent of the progress schedule (critical path) contract item amount will be made when 50 percent of all work completed, accepted baseline, and all accepted required schedule updates and revisions.
- D. A total of 100 percent of the progress schedule (critical path) contract item amount will be made when 100 percent of all work completed, accepted baseline, all accepted required schedule updates and revisions, and a completed and certified Final Schedule Update.

The adjustment provisions in Section 4-1.03, "Changes," of the Standard Specifications shall not apply to the item of progress schedule (critical path). Adjustments in compensation for progress schedule (critical path) will not be made for any increased or decreased work ordered by the Engineer in furnishing progress schedules.

RETENTION

The Department will retain an amount equal to 25 percent of the estimated value of the work performed during each estimate period in which the Contractor fails to submit pre-construction scheduling documents, an acceptable baseline, acceptable updated schedule, or acceptable revised progress schedule (critical path) conforming to the requirements of these special provisions as determined by the Engineer. Retentions for failure to submit acceptable CPM progress schedules shall

be in addition to other retentions provided for in the contract. Retentions for failure to submit progress schedules (critical path) will be released for payment on the next monthly estimate for partial payment following the date that pre-construction scheduling documents and acceptable progress schedules (critical path) are submitted to the Engineer, and no interest will be due the Contractor.

10-1.07 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 150 mm in diameter or pipelines operating at pressures greater than 415 kPa (gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

If these facilities are not located on the plans in both alignment and elevation, no work shall be performed in the vicinity of the facilities, except as provided herein for conduit to be placed under pavement, until the owner, or the owner's representative, has located the facility by potholing, probing or other means that will locate and identify the facility. If, in the opinion of the Engineer, the Contractor's operations are delayed or interfered with by reason of the utility facilities not being located by the owner or the owner's representative, the State will compensate the Contractor for the delays to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications, and not otherwise, except as provided in Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

It is anticipated that the following utility facilities will be relocated by others prior to the dates shown:

Utility	Location	Date
Power	Overhead line on the east side of the yard	7/1/00

The following utility facilities will be relocated by others during the progress of the contract. The Contractor shall notify the Engineer, in writing, prior to doing work in the vicinity of the facility. The utility facility will be relocated within the listed working days, as defined in Section 8-1.06, "Time of Completion," of the Standard Specifications, after the notification is received by the Engineer:

Utility	Location	Working Days
Liquid Propane Gas	Various	4
Water	Various	5
Electrical	Various	10
Sewer	South-East corner of the Yard	3

10-1.08 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" of these special provisions.

GENERAL

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

MATERIALS

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or Traffix Sand Barrels manufactured after March 31, 1997, or equal:

- A. Energite III Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076, Telephone 1-312-467-6750, FAX 1-800-770-6755.
 1. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
- B. Fitch Inertial Modules, manufactured by Roadway Safety Service, Inc., 1050 North Rand Road, Wauconda, IL 60084, Telephone 1-800-426-0839, FAX 1-847-487-9820.
 - 1.. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
- C. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pinteroesco, San Clemente, CA 92672, Telephone 1-949-361-5663, FAX 1-949-361-9205.
 1. Russ Enterprises, Inc., 1533 Berger Drive, San Jose, CA 95112, Telephone 1-408-287-4303, FAX 1-408-287-1929.
 2. Statewide Safety, P.O. Box 1440, Pismo Beach, CA 93448, Telephone 1-800-559-7080, FAX 1-805-929-5786.

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

INSTALLATION

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

MEASUREMENT AND PAYMENT

Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions will not be measured nor paid for.

10-1.09 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

ABANDON SEWER LINE

Existing utility sewer lines, where shown on the plans to be abandoned, shall be abandoned in place or, at the option of the Contractor, the sewer lines shall be removed and disposed of. Resulting openings into existing structures that are to remain in place shall be plugged with commercial quality concrete containing not less than 300 kg of cement per cubic meter.

Abandoning sewer lines in place shall conform to the following:

- A. Sewer lines that intersect the side slopes shall be removed to a depth of not less than one meter measured normal to the plane of the finished side slope, before being abandoned.
- B. The ends of sewer lines shall be securely closed by a 150 mm thick tight fitting plug or wall of commercial quality concrete.

Sewer lines shall not be abandoned until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended sewer line abandonment.

Full compensation for concrete plugs, pipe removal, structure excavation, and backfill (including sand, controlled low strength material or slurry cement backfill) shall be considered as included in the contract unit price paid for abandon sewer line and no additional compensation will be allowed therefor.

REMOVE FENCE

Existing fence, at those locations shown on the plans to be removed, shall be removed and disposed of.

REMOVE ASPHALT CONCRETE SURFACING

Existing bituminous surfacing shown on the plans to be removed, shall be removed. Resulting holes and depressions shall be backfilled with earthy material selected from excavation to the lines and grade established by the Engineer.

The material removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 15-2.03, "Disposal," of the Standard Specifications, or at the option of the Contractor, if the surfacing is removed by means of a grinder, which produces material suitable for spreading and compacting, the material may be used as sub-base in the new structural section.

Removing asphalt concrete surfacing will be measured and paid for by the square meter.

REMOVE CONCRETE

Concrete, where shown on the plans to be removed, shall be removed.

The pay quantities of concrete to be removed will be measured by the cubic meter, measured before and during removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

10-1.10 CLEARING AND GRUBBING

Clearing and grubbing shall conform to the provisions in Section 16, "Clearing and Grubbing," of the Standard Specifications and these special provisions.

Trees and buildings shown on the plans to be removed, shall be removed.

Vegetation shall be cleared and grubbed only within the excavation and embankment slope lines.

Existing vegetation outside the areas to be cleared and grubbed shall be protected from injury or damage resulting from the Contractor's operations.

Nothing herein shall be construed as relieving the Contractor of the Contractor's responsibility for final cleanup of the maintenance station as provided in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

10-1.11 DEMOLITION

SCOPE

This work shall consist of demolition and removal of all improvements remaining either wholly or partially within the project limits, including, but not limited to, sheds, buildings, foundations, slabs above ground and other features shown to be removed.

SALVAGE

The State reserves the right to salvage any furnishings or equipment from the improvements prior to the date set for opening of bids.

DESCRIPTION

The general description of these improvements are as follows:

- 1) Old Truck Shed = 350 square meters
Slab on grade, wood frame and roof structure, with metal roof and siding.
- 2) Blacksmith Shop = 120 square meters
Slab on grade, wood frame and roof structure, with metal roof and siding.
- 3) Warehouse = 132 square meters
Slab on grade, wood frame and roof structure, with metal roof and siding. Concrete and loading dock.

PREPARATION

Prior to beginning demolition work, the Contractor shall make all arrangements with the serving utilities for disconnecting, removing, capping and plugging all utility services.

DISPOSAL

The Contractor shall not dispose of the improvements or material therefrom by sale, gift, or in any manner whatsoever to the general public at the site, provided however, that these provisions shall not be construed as limiting or prohibiting the sale or disposal of such improvements or materials at the site to duly licensed contractors or materials men, and provided that the materials are removed from the improvement by the State's Contractor. Removal of the buildings as a unit, or in sections capable of reassembly as a structure, is expressly prohibited.

MEASUREMENT

Demolition work will be paid for at a lump sum price.

PAYMENT

The contract lump sum price paid for demolition work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in demolition, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.12 EARTHWORK

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

When a layer of specified material is not to be placed on the basement material, the finished grading plane shall not vary more than 30 mm above or below the grade established by the Engineer. The requirements for obtaining a relative compaction of 95 percent, as provided in the first 2 paragraphs in Section 19-5.03, "Relative Compaction (95 Percent)," of the Standard Specifications, shall not apply when a layer of specified material is not to be placed on the basement material.

When portland cement concrete pavement is to be placed on the grading plane, the grading plane shall not extend above the grade established by the Engineer.

When portland cement concrete base is to be placed on the grading plane, the grading plane shall not extend above the grade established by the Engineer.

At the footings where material is removed and replaced, as described herein, a relative compaction of not less than 95 percent shall be obtained for a minimum depth of 150 mm below the bottom of excavation.

Surplus excavated material shall become the property of the Contractor and shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Where a portion of the existing surfacing is to be removed, the outline of the area to be removed shall be cut on a neat line with a power-driven saw to a minimum depth of 50 mm before removing the surfacing. Full compensation for cutting the existing surfacing shall be considered as included in the contract price paid per cubic meter for roadway excavation and no additional compensation will be allowed therefor.

10-1.13 CONTROLLED LOW STRENGTH MATERIAL

Controlled low strength material shall consist of a workable mixture of aggregate, cementitious materials, and water and shall conform to the provisions for slurry cement backfill in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications and these special provisions.

At the option of the Contractor, controlled low strength material may be used as structure backfill for pipe culverts, except that controlled low strength material shall not be used as structure backfill for aluminum and aluminum-coated culverts nor for culverts having a diameter or span greater than 6.1 m.

When controlled low strength material is used for structure backfill, the width of the excavation shown on the plans may be reduced so that the clear distance between the outside of the pipe and the side of the excavation, on each side of the pipe, is a minimum of 300 mm. This minimum may be reduced to 150 mm when the height of cover is less than or equal to 6.1 m or the pipe diameter or span is less than 1050 mm.

Controlled low strength material in new construction shall not be permanently placed higher than the basement soil. For trenches in existing pavements, permanent placement shall be no higher than the bottom of the existing pavement permeable drainage layer. If a drainage layer does not exist, permanent placement in existing pavements shall be no higher than 25 mm below the bottom of the existing asphalt concrete surfacing or no higher than the top of base below the existing portland cement concrete pavement. The minimum height that controlled low strength material shall be placed, relative to the culvert invert, is 0.5 diameter or 0.5 height for rigid culverts and 0.7 diameter or 0.7 height for flexible culverts.

When controlled low strength material is proposed for use, the Contractor shall submit a mix design and test data to the Engineer for approval prior to excavating the trench for which controlled low strength material is proposed for use. The test data and mix design shall provide for the following:

- A. A 28-day compressive strength between 345 kPa and 690 kPa for pipe culverts having a height of cover of 6.1 m or less and a minimum 28-day compressive strength of 690 kPa for pipe culverts having a height of cover greater than 6.1 m. Compressive strength shall be determined in conformance with the requirements in ASTM Designation: D 4832.
- B. When controlled low strength material is used as structure backfill for pipe culverts, the sections of pipe culvert in contact with the controlled low strength material shall conform to the requirements of Chapter 850 of the Highway Design Manual using the minimum resistivity, pH, chloride content, and sulfate content of the hardened controlled low strength material. Minimum resistivity and pH shall be determined in conformance with the requirements of California Test 643. The chloride content shall be determined in conformance with the requirements of California Test 422 and the sulfate content shall be determined in conformance with the requirements of California Test 417.
- C. Cement shall be any type of portland cement conforming to the requirements in ASTM Designation: C 150; or any type of blended hydraulic cement conforming to the requirements in ASTM Designation: C 595M or the physical requirements in ASTM Designation: C 1157M. Testing of cement will not be required.
- D. Admixtures may be used in conformance with the provisions in Section 90-4, "Admixtures," of the Standard Specifications. Chemical admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined in conformance with the requirements of California Test 415, shall not be used. If an air-entraining admixture is used, the maximum air content shall be limited to 20 percent. Mineral admixtures shall be used at the Contractor's option.

Materials for controlled low strength material shall be thoroughly machine-mixed in a pugmill, rotary drum or other approved mixer. Mixing shall continue until the cementitious material and water are thoroughly dispersed throughout the material. Controlled low strength material shall be placed in the work within 3 hours after introduction of the cement to the aggregates.

When controlled low strength material is to be placed within the traveled way or otherwise to be covered by paving or embankment materials, the material shall achieve a maximum indentation diameter of 76 mm prior to covering and opening to public traffic. Penetration resistance shall be measured in conformance with the requirements in ASTM Designation: C 6024.

Controlled low strength material used as structure backfill for pipe culverts will be considered structure backfill for compensation purposes.

10-1.14 AGGREGATE SUBBASE

Aggregate subbase shall be Class 1 and shall conform to the provisions in Section 25, "Aggregate Subbases," of the Standard Specifications and these special provisions.

The restriction that the amount of reclaimed material included in Class 1, Class 2 and Class 3 aggregate subbase not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 1, Class 2 and Class 3 aggregate subbase may include reclaimed glass. Aggregate subbase incorporating reclaimed glass shall not be placed at locations where material will not be placed over the aggregate subbase.

10-1.15 AGGREGATE BASE

Aggregate base shall be Class 2 and shall conform to the provisions in Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

The restriction that the amount of reclaimed material included in Class 2 aggregate base not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 2 aggregate base may include reclaimed glass. Aggregate base incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate base.

10-1.16 FOG SEAL COAT

Fog seal coat shall conform to the provisions in Section 37-1, "Seal Coats," of the Standard Specifications and these special provisions.

Attention is directed to "Order of Work" in these special provisions regarding application of asphalt emulsion.

Asphaltic emulsion shall be CSS1h grade.

10-1.17 ASPHALT CONCRETE

Asphalt concrete shall be Type A and shall conform to the provisions in Section 39, "Asphalt Concrete," of the Standard Specifications and these special provisions.

The grade of asphalt binder to be mixed with aggregate for Type A asphalt concrete shall be PBA Grade 6b and shall conform to the provisions in "Asphalt" of these special provisions.

California Test 367 is modified by amending Section C, "Optimum Bitumen Content," as follows:

C. OPTIMUM BITUMEN CONTENT

1. Plot asphalt content versus void content for each specimen on Form TL-306 (Figure 3), and connect adjacent points with straight lines.
2. Modify Form TL-306 (Figure 3) to show stability on the vertical axis beginning with a stability value of 20 on the bottom horizontal line and ending with a value of 60 on the top horizontal line.
3. Plot stability versus asphalt content for each specimen on Form TL-306 (Figure 3) as modified in step 2 above and connect adjacent points with straight lines.
4. Select the theoretical asphalt content which is at the point passing through the minimum specification for stability from modified Figure 3.
5. Optimum asphalt content is determined as follows:

If voids are less than 4.0% at the asphalt content selected in Step 4, then select the asphalt content at 4.0% voids from Figure 3. Selected optimum asphalt content should be as close to 4.0% voids as possible.

6. To establish a recommended range, use the Optimum Bitumen Content (OBC) as the high value and 0.3% less as the low value where the OBC is 7.9% or less. When the OBC is between 8.0% and 8.6%, use it as the high value of the range and use 7.6% as the low value. When the OBC is greater than 8.6%, use it as the high value and 1.0% less as the low value.

If the recommended bitumen ratio range, as determined by California Test 367, is increased or decreased by the Engineer beyond the recommended range by more than 0.1 percent by weight of the dry aggregate, the compensation payable to the Contractor for asphalt concrete will be increased or decreased on the basis of the total increase or decrease in tonnes of asphalt binder times the cost of asphalt binder per tonne, f.o.b. the asphalt binder plant (including sales tax) plus the freight cost per tonne, at the carrier's established rates, for the delivery of the asphalt binder from the asphalt binder plant to the asphalt concrete plant being used for the project. In determining the cost of the asphalt binder, any cash or trade discount offered or available will be credited to the State notwithstanding the fact that such discount may not have been taken by the purchaser. The highest value of the specified range will be considered to be the specified asphalt content for determining the

total increase in asphalt binder and the lowest value of the specified range will be considered to be the specified asphalt content for determining the total decrease in asphalt binder.

The aggregate for Type A asphalt concrete shall conform to the 19-mm maximum, medium grading specified in Section 39-2.02, "Aggregate," of the Standard Specifications.

At least four weeks prior to their intended use, the Contractor shall furnish samples of aggregates, in the quantity requested by the Engineer, from the source or sources he proposes to use for the project.

Aggregate from each source shall conform to the following quality requirements:

Test	California Test	Asphalt Concrete Type A
Los Angeles Rattler	211	
Loss at 500 Rev. (Max)		25%

Fine aggregate shall be obtained from a source or sources that meet the requirements for California Test Method 211 specified for coarse aggregate and shall also conform to the following quality requirement:

Test	California Test	Requirement
Durability Index (Df)	229	50 Min

In addition to the aggregate provisions listed in Section 39, "Asphalt Concrete," of the Standard Specifications, the combined aggregates shall conform to the following quality requirement when mixed with performance based asphalt (PBA) binder grade 1 in the amount of asphalt determined to be optimum by California Test 367, as modified in these special provisions:

Test	California Test	Requirement
Surface Abrasion	360, Method A	Loss not to exceed 15 g
	AASHTO Designation	
Tensile Strength Ration	T-283	0.80 Min.

At the Contractor's option, a liquid anti-strip additive, approved by the Engineer, may be used in the amount of 0.5 percent by weight of the binder to conform to the tensile strength ratio requirement. If the Contractor elects to use an anti-strip additive, the State will waive the tensile strength ratio test (AASHTO Designation T-283). Full compensation for furnishing and mixing an anti-strip additive with the aggregate and paving asphalt shall be considered as included in the contract price paid per tonne for asphalt concrete (Type A) and no separate payment will be made therefor.

Asphaltic emulsion for paint binder (tack coat) shall be, at the Contractors option, either Grade PMCRS2 cationic polymer modified asphaltic emulsion or paving asphalt grade AR-4000.

Anti-strip additives shall not be used in asphalt concrete produced with lime treated aggregates.

In addition to the temperature requirements specified in Section 39-6.01, "General Requirements, " of the Standard Specifications, asphalt concrete shall be placed only when the surface temperature of the area to be paved is above 7° C.

In addition to the provisions in Section 39-5.01, "Spreading Equipment," of the Standard Specifications, asphalt paving equipment shall be equipped with automatic screed controls and a sensing device or devices.

When placing asphalt concrete, the end of the screed nearest the centerline shall be controlled by a sensor activated by a ski device not less than 9 m long. The end of the screed farthest from centerline shall be controlled manually.

When paving contiguously with previously placed mats, the end of the screed adjacent to the previously placed mat shall be controlled by a sensor that responds to the grade of the previously placed mat and will reproduce the grade in the new mat within a 3-mm tolerance. The end of the screed farthest from the previously placed mat shall be controlled in the same way it was controlled when placing the initial mat.

Should the methods and equipment furnished by the Contractor fail to produce a layer of asphalt concrete conforming to the provisions, including straightedge tolerance, of Section 39-6.03, "Compacting," of the Standard Specifications, the paving operations shall be discontinued and the Contractor shall modify the equipment or methods, or furnish substitute equipment.

Should the automatic screed controls fail to operate properly during a day's work, the Contractor may manually control the spreading equipment for the remainder of that day. However, the equipment shall be corrected or replaced with alternative automatically controlled equipment conforming to the provisions in this section before starting another day's work.

The area to which paint binder has been applied shall be closed to public traffic. Care shall be taken to avoid tracking binder material onto existing pavement surfaces beyond the limits of construction.

10-1.18 CONCRETE STRUCTURES

Portland cement concrete structures shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Portland cement concrete shall conform to the provisions in "Freezing Condition Requirements" of these special provisions.

Concrete Oil/Water Separator will be measured and paid for as minor concrete (minor structure).

10-1.19 CORRUGATED METAL PIPE

Corrugated steel pipe culverts shall conform to the provisions in Section 66, "Corrugated Metal Pipe," of the Standard Specifications and these special provisions.

Corrugated steel pipe shall be fabricated from zinc-coated steel sheet.

10-1.20 MISCELLANEOUS CONCRETE CONSTRUCTION

Curbs and gutters shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications.

SECTION 11. (BLANK)

SECTION 12. BUILDING WORK

SECTION 12-1. GENERAL REQUIREMENTS

12-1.01 SCOPE

Building work described herein and as shown on the plans shall conform to the requirements of these special provisions and Sections 1 through 9 of the Standard Specifications. Sections 10 through 95 of the Standard Specifications shall not apply to the work in this Section 12 except when specific reference is made thereto.

The building work to be done consists, in general, of constructing a resident's mechanics facility; enclosed storage building; salt storage building; covered storage canopy; covered materials bins; trailer sanitary station; disabled accessible parking; mechanical and electrical and such other items or details, not mentioned above, that are required by the plans, Standard Specifications, or these special provisions shall be performed, placed, constructed or installed.

12-1.02 ABBREVIATIONS

Section 1-1.02, "Abbreviations," of the Standard Specifications is amended by adding the following:

AAMA	American Architectural Manufacturers' Association
ACI	American Concrete Institute
AGA	American Gas Association
AITC	American Institute of Timber Construction
AMCA	Air Movement and Control Association
APA	American Plywood Association
ARI	American Refrigeration Institute
ASHRAE	American Society of Heating, Refrigeration and Air Conditioning Engineers
CS	Commercial Standards (US Department of Commerce)
ESO	Electrical Safety Orders
FGMA	Flat Glass Marketing Association
FM	Factory Mutual
FS	Federal Specification
ICBO	International Conference of Building Officials
NAAMM	National Association of Architectural Metal Manufacturers

NBFU	National Board Fire Underwriters
NEC	National Electrical Code
NFPA	National Fire Protection Association
PEI	Porcelain Enamel Institute
PS	Product Standard (US Department of Commerce)
RIS	Redwood Inspection Service
SCPI	Structural Clay Products Institute
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
SSPC	Steel Structures Paint Council
TCA	Tile Council of America
TPI	Truss Plate Institute
UBC	Uniform Building Code
UL	Underwriters Laboratories, Inc.
WCLIB	West Coast Lumber Inspection Bureau (stamped WCLB)
WCLB	Grade stamp for WCLIB
WIC	Woodwork Institute of California
WWPA	Western Wood Products' Association

When reference is made to the Uniform Building Code (UBC) on the plans or in the special provisions, it shall be the 1994 Uniform Building Code as amended by the 1995 Title 24 California Building Standards Code.

12-1.03 GUARANTEE

The Contractor hereby unconditionally guarantees that the building work will be done in accordance with the requirements of the contract, and further guarantees the building work of the contract to be and remain free of defects in workmanship and materials for a period of one year from the date of acceptance of the contract, unless a longer guarantee period is required elsewhere in these special provisions. The Contractor hereby agrees to repair or replace any and all building work, together with any other adjacent work which may be displaced in so doing, that may prove to be not in accordance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

The performance bond for the contract, or a portion thereof, in the sum equal to one-half the contract price of the building work, shall remain in full force and effect during the guarantee period.

The Contractor further agrees, that within 10 calendar days after being notified in writing by the Department of any building work not in accordance with the requirements of the contract or any defects in the building work, he shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event he fails to comply, he does hereby authorize the Department to proceed to have such work done at the Contractor's expense and he shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

12-1.04 AREAS FOR CONTRACTOR'S USE

No area is available within the contract limits for the exclusive use of the Contractor. The Contractor shall arrange with the Engineer for areas to store equipment and materials within the work area.

12-1.05 COOPERATION

Attention is directed to Sections 7-1.14, "Cooperation," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

Work by State forces will be in progress within the contract limits during the working period for this contract.

The Contractor shall comply with all security policies of the State concerning the Quincy Maintenance Station.

The Contractor shall plan his work to minimize interference with State forces and the public. Interruptions to any services for the purpose of making or breaking a connection shall be made only after consultation with and for such time periods as directed by the Engineer.

12-1.06 SUBMITTALS

Working drawings, material lists, descriptive data, samples and other submittals specified in these special provisions shall be submitted for approval in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and these special provisions.

Unless otherwise permitted in writing by the Engineer, all submittals required by these special provisions shall be submitted within 35 days after the contract has been approved.

Attention is directed to the provisions in Section 5-1.01, "Authority of Engineer," of the Standard Specifications. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Attention is directed to Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications. The second indented paragraph of the first paragraph of said Section 6-1.05 is amended to read:

Whenever the specifications permit the substitution of a similar or equivalent material or article, no test or action relating to the approval of such substituted material will be made until the request for substitution is made in writing by the Contractor accompanied by complete data as to the equality of the material or article proposed. Such request shall be made within 35 days after the date the contract has been approved and in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.

Work requiring the submittal of working drawings, material lists, descriptive data, samples, or other submittals shall not begin prior to approval of said submittal by the Engineer. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Office of Structure Design, Documents Unit, Fourth Floor, Mail Station 9, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252, or the submittals shall be mailed to the Office of Structure Design, Documents Unit, Mail Station 9, P. O. Box 942874, Sacramento, California 94274-0001.

Each submission of drawings, material lists and descriptive data shall consist of at least 5 copies. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal.

Each separate item submitted shall bear a descriptive title, the name of the project, district, county, and contract number. Plans and detailed drawings shall be not larger than 559 mm x 914 mm.

The material list shall be complete as to name of manufacturer, catalog number, size, capacity, finish, all pertinent ratings, and identification symbols used on the plans and in the special provisions for each unit.

Parts lists and service instructions packaged with or accompanying the equipment installed in the work shall be delivered to the Engineer at the jobsite. Required operating and maintenance instructions shall be submitted in triplicate.

Manufacturer's warranties for products installed in the work shall be delivered to the Engineer at the jobsite.

Unapproved samples and samples not incorporated in the work shall be removed from State property, when directed by the Engineer.

12-1.07 PROGRESS SCHEDULE

A progress schedule shall be submitted in duplicate for the building work in accordance with the requirements in Section 8-1.04, "Progress Schedule," of the Standard Specifications.

12-1.08 SCHEDULE OF VALUES

The Contractor shall prepare and submit to the Engineer 2 copies of a Schedule of Values covering each lump sum item for building work. The Schedule of Values, showing the value of each kind of work, shall be acceptable to the Engineer before any partial payment estimate is prepared.

The sum of the items listed in the Schedule of Values shall equal the contract lump sum price for building work. Overhead, profit, bond premium, temporary construction facilities, and plant shall not be listed.

12-1.09 INSPECTION

All items covered or all stages of work that are not to remain observable must be inspected and approved before progress of work conceals portions to be inspected. The Contractor shall notify the Engineer not less than 72 hours in advance of when such inspection is needed.

12-1.10 UTILITY CONNECTION

The Contractor shall make all arrangements, and obtain all permits and licenses required for the extension of and connection to each utility service applicable to this project, shall furnish all labor and materials necessary for such extensions which are not performed or provided by the utility, and shall furnish and install any intermediate equipment required by the serving utilities.

Upon written request by the Contractor, the State will pay all utility permits, licenses, connection charges, and excess length charges directly to the utility. Such request shall be submitted not less than 15 days before service connections are required.

The costs incurred by the Contractor for the extensions of utilities beyond the limits shown on the plans, and in furnishing and installing any intermediate equipment required by the serving utilities, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Full compensation for any costs incurred by the Contractor to obtain the permits and licenses shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.11 TEMPORARY UTILITIES

The Contractor may obtain electrical power and water from existing State electrical power and water outlets within the contract limits free of charge for contract operations where such utilities exist, provided that such utility services are in service and are not required by the State for other purposes and subject to the provisions in the section "Cooperation" of these special provisions.

The Contractor shall make his own arrangements to obtain any additional electrical power and water or other utilities required for his operations and shall make and maintain the necessary service connections at his own expense.

When existing utility systems are being modified, periods of shutdown will be determined by the Engineer.

The Contractor shall provide adequate temporary lighting to perform the work and allow the Engineer to inspect the project as each portion is completed.

The Contractor shall provide and pay for telephone service he may require. State telephone facilities shall not be used.

12-1.12 SANITARY FACILITIES

When operational, State sanitary facilities will be available for use by the Contractor's employees, during normal State working hours. Tools shall not be cleaned nor shall cleaning liquids be disposed of in State sanitary facilities or sewers.

12-1.13 MEASUREMENT AND PAYMENT

The contract lump sum price paid for building work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the building work, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for any incidental materials and labor, not shown on the plans or specified, which are necessary to complete the buildings and appurtenances shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.14 FIELD ENGINEERING

This section specifies administrative and procedural requirements for field engineering services to be performed by the Contractor.

In general, these will consist of the primary vertical and horizontal control points.

Lines and grades.--Attention is directed to Section 5-1.07, "Lines and Grades," of the Standard Specifications.

Such stakes or marks will be set by the Engineer as he determines to be necessary to establish the lines and grades required for the completion of the work shown on the plans and as specified in these special provisions. In general, these will consist of the primary vertical and horizontal control points.

Stakes and marks set by the Engineer shall be carefully preserved by the Contractor. In case such stakes and marks are destroyed or damaged they will be replaced at the Engineer's earliest convenience. The Contractor will be charged for the cost of necessary replacement or restoration of such stakes and marks which in the judgment of the Engineer were carelessly or willfully destroyed or damaged by the Contractor's operations. This charge will be deducted from any moneys due or to become due the Contractor.

All other stakes or marks required to establish the lines and grades required for the completion of the work shall be the responsibility of the Contractor.

Existing utilities and equipment.--The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, the Contractor shall investigate and verify the existence and location of underground utilities and other construction.

Prior to construction, the Contractor shall verify the location and invert elevation at points of connection of sanitary and septic sewers, storm sewer, and water or fire service piping.

Surveys for layout and performance.--The Contractor shall perform all surveys for layout and performance, reduce field notes, and make all necessary calculations and drawings necessary to carry out the work.

The Contractor shall locate and layout site improvements, and other work requiring field engineering services, including pavements, stakes for grading, fill and topsoil placement, utility slopes and invert elevations by instrumentation and similar appropriate means.

Batter boards shall be located and laid out for structures, building foundations, column grids and locations, floor levels and, control lines and levels required for mechanical and electrical work.

Survey accuracy and tolerances.--The tolerances generally applicable in setting survey stakes for foundations, slabs, and underground work shall not exceed the following:

Survey Stakes or Markers	Tolerance
Rough grading or excavation	30 mm
Trimming or preparation of subgrade for roadways	15 mm
Roadway surfacing, steel or concrete pipe	6 mm
Structures or building construction	3 mm

Such tolerance shall not supersede stricter tolerances required by the plans or special provisions, and shall not otherwise relieve the Contractor of responsibility for measurements in compliance therein.

12-1.15 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following requirements:

Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.

Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish all information necessary as required to the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision shall be final.

When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, a list of substitutions to be made shall be submitted for approval.

The following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325M	
METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR REINFORCEMENT	
METRIC BAR DESIGNATION NUMBER AS SHOWN ON THE PLANS	IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

SUBSTITUTION TABLE FOR WELDED PLAIN WIRE REINFORCEMENT, ASTM DESIGNATION: A 185	
	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

CONVERSION TABLE FOR SIZES OF: (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449	
DIAMETER	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL			
UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED (GALVANIZED) SHEETS	
METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT US STANDARD GAGE inch	METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT GALVANIZED SHEET GAGE inch
7.94	0.3125		
6.07	0.2391		
5.69	0.2242		
5.31	0.2092		
4.94	0.1943		
4.55	0.1793		
4.18	0.1644	4.270	0.1681
3.80	0.1495	3.891	0.1532
3.42	0.1345	3.510	0.1382
3.04	0.1196	3.132	0.1233
2.66	0.1046	2.753	0.1084
2.28	0.0897	2.372	0.0934
1.90	0.0747	1.994	0.0785
1.71	0.0673	1.803	0.0710
1.52	0.0598	1.613	0.0635
1.37	0.0538	1.461	0.0575
1.21	0.0478	1.311	0.0516
1.06	0.0418	1.158	0.0456
0.91	0.0359	1.006 or 1.016	0.0396
0.84	0.0329	0.930	0.0366
0.76	0.0299	0.853	0.0336
0.68	0.0269	0.777	0.0306
0.61	0.0239	0.701	0.0276
0.53	0.0209	0.627	0.0247
0.45	0.0179	0.551	0.0217
0.42	0.0164	0.513	0.0202
0.38	0.0149	0.475	0.0187

CONVERSION TABLE FOR WIRE		
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT USA STEEL WIRE THICKNESS	GAGE NO.
mm	inch	
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

CONVERSION TABLE FOR COMMON NAILS				
NAIL SIZE	METRIC		ENGLISH	
	Length	Diameter	Length	Diameter
8d	63.5	3.33	2 1/2	0.131
10d	76.2	3.76	3	0.148
16d	88.9	4.11	3 1/2	0.162

CONVERSION TABLE FOR LUMBER	
METRIC NOMINAL SURFACE DRY SIZE	EQUIVALENT NOMINAL SURFACE DRY U S SIZE
mm	inch
51	2
102	4
152	6
203	8
254	10
305	12

CONVERSION TABLE FOR PLYWOOD	
METRIC	ENGLISH
mm	inch
6.4	1/4
7.9	5/16
9.5	3/8
11.1	7/16
11.9	15/32
12.7	1/2
15.1	19/32
15.9	5/8
18.3	23/32
19.1	3/4
22.2	7/8
25.4	1
28.6	1 1/8

CONVERSION TABLE FOR INSULATION R-VALUE	
METRIC	ENGLISH
(m ² K/W)	(HR FT ² F/BTU)
0.5	3
0.7	4
1.4	8
1.9	11
2.3	13
2.5	14
3.3	19
5.3	30

CONVERSION TABLE FOR VAPOR TRANSMISSION RATING	
METRIC	ENGLISH
(Perm-m)	(perm-inch)
0.29	0.02

CONVERSION TABLE FOR LOW PRESSURE	
METRIC	ENGLISH
(Pa)	(Inches of Water Column)
30	0.125
60	0.25
90	0.375
120	0.50
150	0.60
155	0.625
175	0.70
185	0.75
200	0.80
250	1.00
310	1.25

CONVERSION TABLE FOR PRESSURE	
METRIC (kPa)	ENGLISH (psi)
10	1.5
210	30
280	40
350	50
690	100
860	125
1040	150
1100	160
1210	175
1380	200
1730	250
2070	300
2170	315
2410	350
2590	375
2760	400
4830	700
5170	750
5520	800
13800	2000
17200	2500
20700	3000
27600	4000
34500	5000
137900	20000

CONVERSION TABLE FOR MIL THICKNESS	
METRIC (mm)	ENGLISH (inch/1000)
0.10	4
0.10	5
0.50	20
0.75	30
1.00	40

CONVERSION TABLE FOR HVAC DUCTING.	
METRIC (mm)	ENGLISH (inch)
100	4
125	5
150	6
175	7
200	8
225	9
250	10
300	12
360	14
410	16
460	18
510	20
560	22
610	24
660	26
710	28
760	30

CONVERSION TABLE FOR MECHANICAL PIPING		
METRIC (GSP, PVC, BSP, DUCTILE IRON)	METRIC (mm)	ENGLISH (inch)
NPS 1/2	15	1/2
NPS 3/4	20	3/4
NPS 1	25	1
NPS 1 1/4	32	1 1/4
NPS 1 1/2	40	1 1/2
NPS 2	50	2
NPS 2 1/2	65	2 1/2
NPS 3	75	3
NPS 4	100	4
NPS 6	150	6

CONVERSION TABLE FOR LUBRICATION PIPING TUBING WALL THICKNESS	
METRIC (mm)	ENGLISH (inch)
2.1	0.083
0.9	0.035

CONVERSION TABLE FOR HOSE/TUBING SIZES O. D.	
METRIC (mm)	ENGLISH (inch)
6	1/4
10	3/8
13	1/2
16	5/8
19	3/4
22	7/8
25	1

CONVERSION TABLE FOR DRUM SIZES			
METRIC		ENGLISH	
L	kg	gallons	pounds
205	180	55	400
60	55	16	120
19	16	5	35

CONVERSION TABLE FOR POWER	
METRIC (kW)	ENGLISH (HP)
0.037	1/20
0.075	1/10
0.18	1/4
0.25	1/3
0.37	1/2
0.55	3/4
0.75	1
1.1	1 1/2
1.5	2
2.2	3
3.7	5
5.5	7 1/2
7.5	10
11	15
15	20
18.5	25
22	30
30	40
37	50
45	60
55	75
75	100
90	120
110	150

CONVERSION TABLE FOR IMPELLER BALANCE		
SYNCHRONOUS RPM	METRIC (g mm/kg)	ENGLISH (ounce- inch/pound)
720	94	0.059
900	73	0.046
1200	54	0.034
1800	41	0.026
3600	17	0.011

CONVERSION TABLE FOR ELECTRICAL CONDUIT	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
16	1/2
21	3/4
27	1
35	1 1/4
41	1 1/2
53	2
103	4

SECTION 12-2. SITEWORK

12-2.01 REMOVING PORTIONS OF EXISTING FACILITIES

PART 1.- GENERAL

Scope.--This work shall consist of removing portions of the existing facilities, including removal of existing work to gain access to or for new work, in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS (Not applicable)

PART 3.- EXECUTION

PREPARATION.--

General.--The limits of removal shall be located and identified. Items to be removed and the interface of items to be removed and items to remain intact shall be identified and marked.

Prior to removing concrete, a saw cut approximately 25 mm deep shall be made along the limits of removal on all faces that will be visible in the completed work.

REMOVAL.--

General.--Removal shall be to the limits shown on the plans. Removal shall be done carefully to minimize damage to the portions to remain. Remaining portions that are damaged by the Contractor's operation shall be restored to original condition at the Contractor's expense.

Existing apparatuses, devices, or accessories which would be functionally impaired by new construction or remodeling shall be moved, brought out to new surfaces, or provided with new access covers, as necessary to restore apparatuses, devices, or accessories to their original usefulness.

Piping and conduits to be abandoned shall be capped or plugged.

Surfaces that are exposed to view at the limits of removal work shall be patched, bumps shall be removed and depressions filled, and the surface shall be finished to match the existing surrounding surfaces. Depressions in concrete less than 25 mm deep shall be deepened to 25 mm minimum depth before filling with cement mortar.

Anchor bolts and reinforcement shall be removed at least 25 mm below the surrounding surfaces, and the resulting hole shall be patched with cement mortar.

Existing reinforcement that is to be incorporated into the new work shall be protected from damage and thoroughly cleaned before being embedded in new concrete.

DISPOSAL.--

General.--Materials that are to be removed, shall become the property of the Contractor and shall be disposed of outside the highway right of way in accordance with the requirements in Section 7-1.13, "Disposal of Material Outside of the Highway Right of Way," of the Standard Specifications.

12-2.02 RELOCATING MATERIALS AND EQUIPMENT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of relocating existing materials and equipment in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS (Not applicable)

PART 3.- EXECUTION

RELOCATION.--

General.--Materials or equipment to be relocated shall be removed carefully to avoid damage to the materials or equipment or to the materials or equipment which are to remain. Assemblies to be relocated which require dismantling for removal shall be match marked before dismantling.

The Contractor shall notify the Engineer prior to the relocation work in order that the materials or equipment may be inspected for existing damage.

Materials or equipment to be relocated shall have all adhering concrete, mastics, earth or other deleterious materials removed and shall have all exterior surfaces cleaned.

Materials or equipment which are damaged by the Contractor's operations shall be replaced or restored to match the condition of the materials or equipment prior to the beginning of the Contractor's operations. Replacement or restoration of damaged materials or equipment shall be at the Contractor's expense.

Connections, anchorages and fasteners for relocated materials and equipment shall match existing and shall be furnished and installed by the Contractor. Assemblies which have been dismantled shall be reassembled to match the existing installation. Relocated materials and equipment shall be installed as required for new work.

Modifications to wiring and plumbing to accommodate relocated items shall be as shown on the plans. Ends of piping and conduits to be abandoned shall be capped.

Surfaces that are exposed to view upon removal or relocation of materials or equipment shall be patched. Bumps shall be removed and depressions filled, and the surface finished to match the existing surfaces. Depressions in concrete less than 25 mm deep shall be deepened to 25 mm minimum depth before filling with cement mortar.

DISPOSAL.--

General.--Materials from existing facilities to be reused in the work, in the opinion of the Engineer, is unsuitable for use shall become the property of the Contractor and disposed of as provided in Section 7-1.13, "Disposal of Material Outside of the Highway Right of Way" of the Standard Specifications. The unsuitable material shall be replaced as ordered by the Engineer and will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

12-2.03 EARTHWORK FOR BUILDING WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing earthwork for building work in accordance with the details shown on the plans and these special provisions.

Earthwork for building work shall consist of excavation for footings, foundations, slabs, and clarifiers; filling under slabs; backfilling; trenching and backfilling for pipes and conduits; backfilling holes resulting from removal of existing facilities; and any other earthwork, not mentioned, but necessary to complete the building work.

Attention is directed to the requirements of "Field Engineering" in Section 12-1, "General Requirements," of these special provisions.

QUALITY ASSURANCE.--

Samples.--Samples of sand, pea gravel, or crushed stone, weighing not less than 11 kg, shall be submitted to the Engineer at the jobsite for approval.

SITE CONDITIONS.--

Existing underground piping and conduit.--The location of existing underground piping and conduit is based on the best records available. Before beginning work, the Contractor shall accurately locate the piping and conduit involved in the work. If the location of the existing piping or conduit deviates from the location shown on the plans by more than 1.5 meters, or, if no elevations are indicated and the piping or conduit is more than 0.9 meter below grade, the cost of the additional excavation, backfill, piping or conduit, and removal and replacement of concrete, if any, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing surfaced or planted areas.--Existing surfaced or planted areas that are removed, broken or damaged by the Contractor's operations shall be restored to their original condition except as otherwise shown on the plans or specified herein. Restoration materials shall be equal to or better than the original materials.

PART 2.- PRODUCTS

BACKFILL MATERIALS.--

Structure backfill.--

Structure and trench backfill shall be free of organic and other deleterious material and shall be suitable for the required compaction. Gravel without sand matrix shall not be used except as free draining granular material beneath slabs and footings.

Select backfill.--

Select backfill shall conform to the requirements specified under "Aggregate Base," elsewhere in this Section 12-2.

Sand.--

Sand shall be clean, washed sand, free from clay or organic material graded such that 100 percent passes the 6 mm sieve, 90 percent to 100 percent passes the 4.75 mm sieve and not more than 5 percent passes the 75 µm sieve size.

PART 3.- EXECUTION

PREPARATION.--

Sawcutting.--Prior to excavation or trenching, existing surfacing shall be removed to saw cut lines, or to existing wood dividers or expansion joints, if any. The saw cut shall be to a neat line and have a depth not less than 25 mm. Surfacing shall be replaced to match the thickness, grades and finish of the adjacent surrounding surfaces.

EXCAVATION.--

Footing excavation.--The footing depths shown on the plans shall be changed to suit field conditions when directed by the Engineer. Solid rock at or near required depths shall not be disturbed. Unsuitable material shall be excavated down to firm bearing as directed by the Engineer. Work and materials required because of excavation in excess of the depths shown on the plans, when such excavation has been ordered by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Overdepth excavation for footings shall be backfilled with concrete or such other material recommended by the Contractor and approved by the Engineer. Relative compaction shall be not less than 95 percent.

At locations and to the limits shown on the plans, material below the bottom of the foundation or footing shall be removed and replaced with select backfill in accordance with the placing and compacting requirements for backfill.

Excavation for pipes and conduits.--Pipes or conduits in the same trench shall have a minimum clear distance between pipes or conduits of 150 mm. Pipes or conduits shall have not less than 0.75 meter of cover from top of pipes or conduits to finished grade unless otherwise shown on the plans or specified.

Trenching shall be of sufficient depth to permit placing a minimum depth of 100 mm of compacted sand under all pipes and conduits.

Dewatering.--Excavations shall be kept clear of standing water. Water shall be removed by pumping if necessary. Water removed from excavation shall be carried away from the building site and disposed of in a manner that will not harm State or adjacent property.

BACKFILLING.--

General.--Backfill shall be placed and compacted in horizontal layers, not more than 150 mm thick prior to compaction, and to the lines and grades shown on the plans or to original ground.

Structure backfill.--After structures are in place and forms are removed, wood and other debris shall be removed from excavations before placing backfill.

Unless approved in writing by the Engineer, compaction of structure or select backfill by jetting or ponding shall not be permitted.

Select backfill.--At the locations and to the limits shown on the plans, materials below the bottom of footings or foundations shall be removed and replaced with select backfill material in accordance with the placing and compacting requirements of structure backfill. The relative compaction shall be not less than 95 percent.

At the footings or foundations where material is removed and replaced, as described herein, a relative compaction of not less than 95 percent shall be obtained.

Backfilling pipes and conduits.--Backfill placed under pipe and conduits shall be compacted sand, 100 mm minimum depth. Backfill material placed to a level 150 mm above tops of pipes and conduits shall be sand or fine earth and particles shall not exceed 13 mm in greatest dimension. For wrapped, coated, or plastic pipe or conduits, sand shall be used for backfill. Backfill material placed higher than 150 mm above tops of pipes or conduits shall consist of material free of stones or lumps exceeding 100 mm in greatest dimension except:

- (a) The top 300 mm of backfill under roads, walks or paving shall consist of aggregate base material.
- (b) The top 150 mm of backfill in planted areas shall consist of topsoil.

Unless otherwise shown on the plans, pipe under roads, with less than 0.75 m of cover over the top of pipe, shall be backfilled with concrete to a level 100 mm above the top of pipe. Concrete for backfill shall be commercial quality concrete containing not less than 350 kg/m³ of cement.

COMPACTION.--

General.--Relative compaction shall be determined in accordance with California Test 216 or 231. Unless otherwise noted below, all backfill shall be compacted to a relative compaction of 90 percent.

Compact original ground.--Original ground within 400 mm of the top of concrete slabs and asphalt concrete surfacing shall be compacted to a relative compaction of not less than 95 percent.

Structure backfill.--Structure backfill and select backfill shall be compacted to a relative compaction of not less than 95 percent.

Trench backfill.--Trench backfill placed beneath slabs or paved areas shall be compacted to a relative compaction of not less than 95 percent.

DISPOSAL.--

Surplus material.--Surplus material from the excavation shall be removed and disposed of outside the right-of-way in accordance with Section 7-1.13 of the Standard Specifications.

FIELD QUALITY CONTROL.--

Inspection.--When the excavation is substantially completed to grade, the Contractor shall notify the Engineer. No concrete shall be placed until the foundation has been approved by the Engineer.

Testing.--The State will conduct compaction tests during the backfilling and compacting operations.

12-2.04 AGGREGATE BASE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, spreading and compacting aggregate base in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Aggregate base.--

Aggregate base shall be commercial quality aggregates consisting of broken stone; crushed gravel; natural, clean, rough-surfaced gravel and sand; or a combination thereof.

Aggregate base shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
25 mm	100
19 mm	90 - 100
4.75 mm	35 - 60
6 µm	10 - 30
75 µm	2 - 9

Aggregate base shall also conform to the following quality requirements:

Tests	California Test No.	Test Requirements
Durability Index	229	35 Min.
Resistance (R-Value)	301	78 Min.
Sand Equivalent	217	22 Min.

PART 3.- EXECUTION

SPREADING AND COMPACTING.--

Spreading.--Aggregate base shall be placed and compacted to the lines and grades shown on the plans.

Spreading and compacting shall be performed by methods that will produce a uniform base, free from pockets of coarse or fine material.

Compaction.--Relative compaction of each layer of compacted base material shall be not less than 95 percent, as determined by California Test 216 or 231.

12-2.05 FREE DRAINING GRANULAR MATERIAL

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and placing free draining granular material beneath slabs in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Free draining granular material.--

Free draining granular material shall be clean, hard, durable, free-draining rock. The material gradation shall be such that all passes the 25 mm screen, and not more than 5 percent passes the 4.75 mm sieve as determined by California Test 202. Granular material shall be free from organic material, clay balls or other deleterious substances.

PART 3.- EXECUTION

SPREADING AND CONSOLIDATING.--

General.--Free draining granular material shall be placed, spread and consolidated by tamping or vibrating.

12-2.06 GEOTEXTILE FABRIC

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and installing geotextile fabric in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Geotextile Fabric.--

Geotextile fabric shall be a subgrade enhancement fabric The geotextile fabric shall be Amoco woven geotextile grade number 2016 or equal.

PART 3.--EXECUTION

Installation.--Geotextile fabric shall be installed as recommended by the manufacturer.

12-2.07 PAINTED PAVEMENT MARKINGS

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and applying paint for pavement markings in accordance with the details shown on the plans and these special provisions.

Pavement markings include, but are not limited to, word and symbol markings, and parking stall markings.

Alternatives.--At the option of the Contractor, striping tape may be placed instead of the painted pavement markings specified herein.

PART 2.- PRODUCTS

Paint.--

Paint shall be top commercial quality for pavement marking, formulated for the use intended, and manufactured by a nationally recognized manufacturer of paint and other coating products.

The kind of paint to be used (solvent or water borne) shall be determined by the Contractor, based on local air pollution control regulations and weather conditions.

Striping tape.--

Striping tape shall be permanent type striping tape. Striping tape shall be Brite-Line, Series 1000; Swarco Industries, Director; 3M Stamark Brand, Pliant Polymer Grade Series 5730; 3M Stamark Brand, Bisymmetric 1.75 Grade Series 5730; or equal.

PART 3.- EXECUTION

ALIGNMENT AND LAYOUT.--All necessary alignment and layout work shall be performed by the Contractor, in a manner that will not damage the pavement.

Unless otherwise shown on the plans, the width of parking stall markings shall be 105 mm.

EQUIPMENT AND OPERATION.--Mechanical means shall be used to paint pavement markings.

All equipment used in the application of paint shall produce pavement markings of uniform quality.

All spray equipment shall be the proper type and of adequate capacity for the work involved.

Air atomized spray equipment shall be equipped with oil and water extractors and pressure regulators, and shall have adequate air volume and compressor recovery capacity. Spray gun tip needle assemblies and orifices shall be the proper size.

Rapid dry paint shall be applied only with airless type equipment.

Stencils and hand spray equipment shall be used to paint word and symbol markings. Stencils shall be furnished by the Contractor. The stencil layout shall conform to the dimensions shown on the plans.

SURFACE PREPARATION.--Surfaces which are to receive paint shall be cleaned of all dirt and loose material.

APPLICATION.--Paint shall be applied only on dry surfaces, and only during periods of favorable weather, in accordance with the manufacturer's recommendations.

On new surfacing, paint shall be applied in 2 coats. The first coat shall be dry before application of the second coat is applied.

On existing surfacing, paint shall be applied in one coat.

Completed pavement markings shall have clean and well-defined edges, and shall conform to the dimensions shown on the plans or as specified in these special provisions.

Drips, oversprays, improper markings, and paint material tracked by traffic shall be immediately removed from the pavement by methods approved by the Engineer. All such removal shall be at the Contractor's expense.

If used, striping tape shall be applied in accordance with the manufacturer's specifications.

APPLICATION RATES.--Each application of paint shall be applied at the rates recommended by the paint manufacturer for the type of surface involved.

PROTECTION.--Newly placed pavement markings shall be protected from damage by traffic or other causes until the paint is thoroughly dry.

DISABLED ACCESSIBLE PARKING STALL SYMBOL.--Each parking space reserved for persons with physical disabilities shall have a minimum 0.9 m x 0.9 m surface identification with the international symbol of accessibility. The symbol and border shall be white and the background shall be blue conforming to Federal Standard 595a, Color No. 15090.

12-2.08 SANITARY SEWAGE DISPOSAL SYSTEM

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, installing and constructing a sanitary sewage system in accordance with the details shown on the plans and these special provisions.

Sanitary sewage system shall include sanitary sewer lines, cleanouts and other fittings and appurtenances, not mentioned, which are required for the complete installation and proper operation of the system.

Related work.--Earthwork for installation of pipes, cleanouts and other appurtenances shall be as specified under "Earthwork for Building Work," in this Section 12-2 of these special provisions.

Concrete and reinforcement shall conform to the requirements specified under "Cast-in-place Concrete" in Section 12-3, "Concrete and Reinforcement," of these special provisions.

Sewer pipes in buildings and to a point 1.5 meters beyond the building shall be as specified in Section 12-15, "Mechanical," of these special provisions.

Order of work.--Work which will curtail the use of the existing sewage system shall not be done until the facilities utilizing the system are closed and are no longer required.

SUBMITTALS.--

Product data.--Materials list for materials to be used shall be submitted for approval and shall include the name of the manufacturer and the source, model number, description, and standard of manufacture.

Manufacturer's descriptive data and catalog cuts shall be submitted for the following:

- Sewer pipe and fittings
- Coatings
- Meter box
- Cleanout access cap

QUALITY ASSURANCE.--

Codes and standards.--All sanitary sewage work shall conform to the applicable portions of the 1994 Uniform Plumbing Code, as amended by the 1995 Title 24 California Building Standards Code, pertaining to the selection and installation of sanitary sewage system materials and products.

Certificates of Compliance.--Certificates of compliance shall be furnished for manhole covers and frames in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2.- PRODUCTS

IDENTIFICATION.--

Underground tracer tape.--

Underground tracer tape shall be permanent, bright colored, continuous printed plastic tape with integral metallic strip or wire, intended for direct burial service; not less than 50 mm wide; lettering shall read "CAUTION SEWER BURIED BELOW".

PIPES AND PIPE FITTINGS.--

General.--Provide pipes of one of the following materials, of weight and class indicated. Provide pipe fittings and accessories of same material and weight and class as pipes, with joining method as indicated.

Sewer and drain pipe.--

Sewer and drain pipe shall be polyvinyl chloride (PVC) plastic sewer pipe and fittings, Standard Dimension Ratio (SDR) 35, conforming to ASTM Designation: D 3034; or PVC drain waste and vent pipe (PVC-DWV) and fittings conforming to ASTM Designation: D 2665.

Sewer pipe adapters.--

Sewer pipe adapters for PVC, cast iron soil pipe or clay piping shall be PVC-DWV adapters, conforming to ASTM Designation: D 2665; or PVC sewer pipe adapters, conforming to ASTM Designation: D 3034. Rubber boot and clamps shall not be used. Variation from the adapters specified herein shall be submitted to the Engineer for approval.

METER BOXES.--

Meter box and cover (for cleanouts).--

Meter box and cover shall be precast concrete with cast iron cover. Cover shall be factory marked "SEWER," "SS," or "SANITARY SEWER." Meter box and cover shall be Bes, No. C9W with C15 cover; Christy, No. B9 with B9C cover; Cook Concrete Products, No. 14 with 14-T cover; or equal.

CLEANOUTS.--

Cleanouts.--

Cleanouts shall be PVC sewer pipe and fittings, conforming to ASTM Designation: D 3034 SDR 35; or PVC-DWV pipe and fittings conforming to ASTM Designation: D 2665. Cleanout piping shall terminate with a flexible PVC connector with stainless steel band coupler with hex tightening screw. Rubber coupling will not be allowed. Connectors shall be INdiana Seal; Fernco; or equal.

COATINGS.--

Bituminous coating.--

Bituminous coating shall conform to ASTM Designation: D 41.

MISCELLANEOUS MATERIALS.--

Cement mortar.--

Cement mortar shall be one part cement to 2 to 3 parts clean plaster or concrete sand mixed with just enough water for suitable consistency.

Epoxy mortar.--

Epoxy mortar shall be a commercial quality, trowelable, 3-component epoxy mortar consisting of 2 pourable epoxy components and a chemically resistant aggregate filler of silica quartz sand with a maximum water absorption of 0.1 percent. Epoxy shall have a pull-off strength of not less than 6.9 MPa and a 90 percent cure in 24 hours. Epoxy mortar shall be the type that requires no primer as a bonding agent.

PART 3.- EXECUTION

INSTALLATION OF IDENTIFICATION.--

General.--Continuous underground tracer tape shall be installed directly above buried line and 150 mm to 200 mm below finished grade during backfilling operations.

INSTALLATION OF SEWER PIPES AND FITTINGS.--

General.--Sewer pipe shall be installed upgrade unless otherwise permitted by the Engineer.

All joints shall be cleaned and sealed with the type of materials required by the local agencies which have jurisdiction over the work. In the absence of such requirements, the pipe shall be jointed with the materials recommended by the pipe manufacturer. The joint sealing operation shall make the joints watertight and shall prevent leakage and infiltration under all conditions of expansion, contraction, and settlement. All joints shall be carefully cleaned before assembly. Completed joints shall be finished smooth on the inside.

Sewers near water lines.--Sewers near water lines shall be installed below water lines in the same trench, in parallel trenches less than 3 meters apart, or at any crossing.

When water lines cross above a sewer line, a vertical separation of not less than 300 mm shall be maintained between the top of the sewer pipe and the bottom of the water line.

Cleaning pipe.--Interior of pipes shall be cleaned of dirt and other materials as the work progresses.

Joint adapters.--Joints between different types of pipes shall be made with standard manufactured adapters and fittings intended for that purpose.

Closing abandoned utilities.--Open ends of abandoned underground utilities which are indicated to remain in place shall be closed. Sufficiently strong closures shall be placed to withstand hydro-static pressure which may result after the pipes are closed.

Interior inspection.--Interiors of pipes shall be inspected to determine displacement or damage during installation or backfilling.

Damaged or misaligned pipe shall be corrected prior to use.

INSTALLATION OF CLEANOUTS.--

General.--Cleanouts shall be installed 90 degrees to finished grade and shall terminate in a meter box. A concrete pad, 450 mm long and 100 mm thick, shall be provided full width of the trench under a wye branch. A concrete collar shall be formed and cast-in-place around each cleanout valve box.

APPLICATION OF COATINGS.--

General.--The exterior surfaces of precast and cast-in-place concrete sewer structures, except the bottom of tanks, shall be completely coated with 2 applications of bituminous coating, applied at a rate of 2.5 square meters per liter.

Black epoxy resin paint shall be applied to the manhole frames and covers and cast iron traffic lids for cleanouts to grade (except mating surfaces) in 2 coats to achieve a minimum dry film thickness.

The preparation of surfaces to receive coatings shall be in accordance with the coating manufacturer's recommendations.

Concrete surfaces to be coated shall not be coated until 28 days after the last concrete for these structures has been poured.

The edge and bottom of manhole cover seat areas shall be coated with a uniform application of heavy duty, waterproof automotive or industrial grease.

TAP CONNECTION.--

General.--Connections to existing systems shall be as shown on the plans and subject to approval by the local agency.

FIELD QUALITY CONTROL.--

Testing pipes.--All sewer pipes shall be tested for obstructions before covering the pipes by balling and flushing the pipes with an approved commercial sewer cleaning ball. The ball shall be moved slowly through the sewer with a tag line. NPS 4 sewer pipe shall be tested by pulling an appropriate sized inflatable plug through the pipe. Obstructions or irregularities shall be removed or repaired.

Sewer pipes shall be tested for leakage for a minimum period of 4 hours by filling with water to an elevation of 1.2 meters above the average invert of sewer, or to the top of the manholes where less than 1.2 meters deep. The system shall show no visible leaks, and the leakage rate shall not exceed the rate allowed by the local agency. In the absence of such requirements, leakage shall not exceed 0.5 liters per 24 hours, per millimeter diameter, per 30 meters of pipe. Sewers may be tested in sections with the test water progressively passed down the sewers if feasible. Water shall be released at a rate which will not create water hammer or surge in the plugged section of sewer.

In lieu of hydrostatic test with water, the air test method, as outlined in the Uniform Plumbing Code (UPC), "Low Pressure Air Test for Building Sewers," may be used.

12-2.09 TRAILER SANITARY STATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a trailer sanitary station in accordance with the details shown on the plans and these special provisions.

Concrete and reinforcement shall conform to the requirements for minor work specified under "Cast-In-Place Concrete" in Section 12-3, "Concrete and Reinforcement," of these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and catalog cuts for the water tower and accessories shall be submitted for approval.

PART 2.- PRODUCTS

Water tower.--

Water tower shall be standard commercially manufactured product designed for normal use at RV dump stations. Tower shall have 4.5 meter reach at full extension, 250 mm cast steel base; 13 mm diameter anchor bolts; 13 mm supply bushing at base of vertical, center pivoting stand pipe, heavy return spring at pivot, pressure vacuum breaker at top of tower and flexible 10 mm rubber hose with self-closing, rough brass radiator bib.

Sewer and vent pipe below finished grade.--

Sewer and vent pipe below finished grade shall be polyvinyl chloride (PVC) plastic sewer pipe and fittings, Standard Dimension Ratio (SDR) 35, conforming to ASTM Designation: D 3034 or PVC drain waste and vent pipe (PVC-DWV) and fittings conforming to ASTM Designation: D 2665.

Vent pipe above finished grade.--

Vent pipe above finished grade and embedded in concrete foundation shall be Schedule 40 galvanized steel pipe with galvanized malleable iron fittings.

Signs.--

Signs shall be galvanized sheet steel not less than 1.6 mm thick (16-gage) with baked enamel finish and galvanized steel mounting plate and fastening hardware. Sign colors and messages shall be as shown on the plans.

PART 3.- EXECUTION

INSTALLATION.--

Sewer and vent piping.--The sewer and vent piping shall be installed in accordance with the applicable requirements specified under "Sanitary Sewage Disposal System," in this Section 12-2 of these special provisions.

Warning signs.--Warning signs and instructional signs for use of the trailer sanitary station shall be installed in accordance with the details shown on the plans.

12-2.10 GUARD POSTS

PART 1.- GENERAL

Scope.--This work shall consist of constructing guard posts in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Steel posts.--

Steel posts for guard posts shall be standard weight, galvanized steel pipe conforming to the details shown on the plans.

Concrete.--

Concrete for guard posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 300 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Installation.--The length and diameter of the guard posts shall conform to the details shown on the plans.

Guard posts shall be placed in holes excavated to the depth and cross section shown on the plans, and shall be installed plumb.

Guard posts shall be backfilled with concrete as shown on the plans.

Painting.--Guard posts shall be prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

12-2.11 PARKING BUMPERS

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and installing precast concrete parking bumpers in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Parking bumpers.--

Parking bumpers shall be commercially available precast parking bumpers.

Parking bumpers shall be 1220 mm long, nominal 200 mm wide and 150 mm high with both top longitudinal corners continuously chamfered and anchor holes 230 mm from each end.

PART 3.- EXECUTION

Layout.--Arrangement of parking bumpers shall be coordinated with the layout of parking stalls and traffic aisles, providing the proper angle to engage wheels and proper location to prevent overtravel of vehicles.

Parking bumpers shall be anchored with two 19 mm diameter reinforcing bars 380 mm in length. The reinforcing bars shall be installed such that the top of the bars is flush with the top of the parking bumper.

12-2.12 DISABLED PARKING AND AUTHORIZATION SIGNS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing disabled parking and authorization signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and sign fastening details shall be submitted for approval.

PART 2.- PRODUCTS

Disabled parking stall identification sign.--

Disabled parking stall identification sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595a, Color No. 15090. Symbol, lettering and border shall be white and shall conform to Federal Standard 595a, Color No. 17886.

Van accessible sign.--

Van accessible sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595a, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595a, Color No. 17886.

Disabled authorization sign.--

Disabled authorization sign shall be a metal sign with baked enamel finish. Sign background shall be blue and shall conform to Federal Standard 595a, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595a, Color No. 17886. Lettering shall be not less than 25 mm in height and shall read as shown on the plans.

Support post.--

Support post shall be commercial quality, standard weight, galvanized steel pipe. Pipe diameter shall be 35 mm.

Fastening hardware.--

Fastening hardware shall be galvanized or cadmium plated.

Concrete.--

Concrete for support posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 300 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Installation.--Support posts shall be placed in holes excavated to the depth and cross-section shown on the plans. Posts shall be set vertical and shall be firmly embedded in concrete backfill. The top of the concrete backfill around the post shall be crowned to drain water.

Support posts shall be fitted with a rainproof top.

Sign shall be fastened rigidly and securely to the support post.

The Engineer will provide the Contractor with the necessary information for the disabled authorization sign.

SECTION 12-3. CONCRETE AND REINFORCEMENT

12-3.01 CAST-IN-PLACE CONCRETE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of constructing cast-in-place concrete facilities in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for admixtures, expansion joint material, vapor barrier, and sealer shall be submitted for approval.

Descriptive data shall be delivered to the Engineer at the jobsite.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for cement, reinforcement, admixtures, freeze-thaw aggregates and epoxy products in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

A Certificate of Compliance shall be furnished for each shipment of epoxy-coated reinforcing bars certifying that the coated bars conform to the requirements of ASTM Designation: D 3963. Said Certificate of Compliance shall include all certifications specified in ASTM Designation: D 3963 and a statement that the coating material has been prequalified by acceptance testing performed by the National Bureau of Standards or by the Valley Forge Laboratories, Inc., Devon, Pennsylvania.

Samples.--Prior to coating, the Contractor shall furnish to the Engineer a representative 0.11 kg sample from each batch of epoxy coating material used. The sample shall be packaged in an airtight container identified with the manufacturer's name and batch number.

After coating, two 800 mm long samples of epoxy-coated reinforcing steel from each size and from each load shipped to the jobsite shall be submitted to the Engineer. The samples shall be representative of the material furnished. The samples, as well as any additional random samples taken by the Engineer, may be tested for specification compliance. Such additional sampling, and all tests performed by the Engineer, may be performed at any location deemed appropriate by the Engineer. Failure of any sample to meet the requirements of the specification will be cause for rejection of all reinforcing bars represented by the sample.

PART 2.- PRODUCTS

CONCRETE MIXES.--

Concrete (structural work).--

Commercial quality concrete shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 350 kg/m³ of cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

The air content of the freshly mixed concrete shall be 6 ± 1 1/2 percent, as determined by California Test 504.

Concrete (minor work).--

Commercial quality concrete for concrete apron shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 300 kg/m³ of cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

The air content of the freshly mixed concrete shall be 6 ± 1 1/2 percent, as determined by California Test 504.

CONCRETE MATERIALS.--

Cement.--

Cement shall conform to ASTM Designation: C 150, Types II, or III portland cement; or Type IP (MS) Modified cement. Type IP (MS) Modified shall conform to ASTM Designation: C 595 and shall be comprised of an intimate mixture of Type II Modified cement and not more than 20 percent of a pozzolanic material.

Aggregates.--

Aggregates shall be free from deleterious coatings, clay balls and other extraneous materials.

Aggregates proposed for use in portland cement concrete shall conform to the requirements for freezing and thawing as determined by California Test 528.

A list of sources of aggregates which have previously passed the freeze-thaw test is available in the District Office in Redding.

Admixtures.--

Admixtures used in portland cement concrete shall be included on the Department's current list of approved admixtures, and shall conform to ASTM Designation: C 494, Types A, B, D, F or G for chemical admixtures; ASTM Designation: C 260 for air-entraining admixtures; and ASTM Designation: C 618 for mineral admixtures, except loss on ignition shall not exceed 4 percent. Properties of admixtures shall be uniform in each lot.

FORM MATERIALS.--

Forms for exposed finish concrete.--

Forms for exposed surfaces shall be plywood, metal or other panel type materials. Plywood shall be not less than 16 mm thick and without scars, dents, and delaminations. Forms shall be furnished in largest practical pieces to minimize number of joints.

Plywood shall conform to the requirements of U. S. Product Standard PS-1 for Exterior B-B (Concrete Form) Class I.

Forms for edges of slabs shall be nominal 50 mm solid stock lumber, plywood, or metal forms.

Forms for unexposed finish concrete.--

Forms for unexposed finish concrete surfaces shall be plywood, lumber, metal or other acceptable material.

Form ties.--

Form ties shall be factory fabricated, removable or snapoff metal ties for use as necessary to prevent spreading of forms during concrete placement.

Form oil.--

Form oil shall be commercial quality form oil which will permit the ready release of the forms and will not discolor the concrete.

REINFORCING MATERIALS.--

Bar reinforcement.--

Bar reinforcement shall conform to ASTM Designation: A 615/A 615M, Grade 420, or ASTM Designation: A 706/A 706M.

Epoxy coated reinforcement.--

The reinforcing steel to be coated shall conform to ASTM Designation: A 615/A 615M, Grade 420, or A 706/A 706M. Epoxy-coated reinforcement shall conform to ASTM Designation: D 3963, except that the thickness of the coating shall be 0.2 mm plus or minus 0.05 mm. The coating shall have a light pastel color.

Welded wire fabric.--

Welded wire fabric shall conform to ASTM Designation: A 185.

Bar supports.--

Bar supports for reinforcement shall be precast mortar blocks or ferrous metal chairs, spacers, metal hangers, supporting wires, and other approved devices of sufficient strength to resist crushing under applied loads.

RELATED MATERIALS.--**Anchor bolts, nuts, and washers.--**

Nonheaded anchor bolts shall conform to ASTM Designation: A 36/A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 325.

Nuts shall conform to ASTM Designation: A 563M, Grade A.

Washers for anchor bolts shall be commercial quality.

Exposed anchor bolts, nuts, and washers shall be hot dipped galvanized.

Expansion joint material.--

Expansion joint material shall be commercial quality asphalt impregnated pressed fiber sheets, 13 mm minimum thickness.

Vapor barrier.--

Vapor barrier shall be commercial quality polyethylene sheets not less than 0.15 mm thick.

Bond breaker.--

Bond breaker shall be Type I asphalt saturated organic felt or such other material approved by the Engineer.

Type A control joints.--

Type A control joints shall be commercial quality, preformed, T-shaped plastic strips with detachable top flange.

Keyed construction joint forms.--

Keyed construction joint forms shall be commercial quality, galvanized metal, factory fabricated construction joint forms. Forms shall produce a rabbeted key type joint.

Divider and edger strips.--

Divider and edger strips shall be foundation grade redwood.

Mortar.--

Mortar shall consist of one part cement to 2 parts clean sand and only enough water to permit placing and packing.

Curing compound.--

Curing compound shall be a non-pigmented curing compound with fugitive dye conforming to the requirements of ASTM Designation: C 309, Type 1-D, Class A.

Concrete sealer.--

Concrete sealer shall be commercial quality VOC-compliant, silane type sealer with hydrophobic and oleophobic properties. Concrete sealer shall be Tamms Industries, Hey'Di H.O.S.; Textured Coatings of America, Inc., Rainstopper 1750W-Clear; or equal.

ADMIXTURES.--

General.--Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option to conserve cement or to facilitate any construction operation.

Calcium chloride shall not be used in any concrete containing reinforcement or other embedded items.

Admixtures shall be combined with concrete materials by methods that produce uniform properties throughout the concrete.

If more than one admixture is used, said admixtures shall be compatible with each other so that the desirable effects of all admixtures will be realized.

Mineral admixtures may be used to replace up to 15 percent of Type II portland cement provided the weight of mineral admixture used is not less than the weight of cement replaced. Mineral admixtures shall not be used to replace Type IP (MS) Modified or Type III cements. Chemical admixtures may be used to reduce up to 5 percent of the portland cement except that the cement content shall not be less than 300 kg/m³. When both chemical and mineral admixtures are used with Type II cement, the weight of cement replaced by mineral admixture may be considered as cement in determining the resulting cement content.

Mineral admixtures will be required in the manufacture of concrete containing aggregates that are determined to be "deleterious" or "potentially deleterious" when tested in accordance with ASTM Designation: C 289. The use of mineral admixture in such concrete shall conform to the requirements in this section except that the use of set retarding admixtures will not be permitted.

When the use of a chemical admixture is specified or is ordered by the Engineer, the admixture shall be used at the rate specified or ordered. If no rate is specified or ordered, or if the Contractor uses a chemical admixture for his own convenience, the admixture shall be used at the dosage normally recommended by the admixture manufacturer.

When air-entrainment is specified or is ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce concrete having the specified or ordered air content as determined by California Test 504. If the Contractor uses air-entrainment for his own convenience, the average air content shall not exceed 4 percent and no single test shall exceed 5 1/2 percent.

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers shall have sufficient capacity to measure at one time the total quantity required for each batch. If more than one liquid admixture is used in the concrete, a separate measuring unit shall be provided for each liquid admixture and dispensing shall be such that the admixtures are not mixed at high concentrations. When air-entraining admixtures are used with other liquid admixtures, the air-entraining admixtures shall be the first to be incorporated into the mix. Unless liquid admixtures are added to premeasured water for the batch, they shall be discharged to flow into the stream of water so that the admixtures are well dispersed throughout the batch.

BAR REINFORCING STEEL.--

Bending.--Reinforcing steel bars shall accurately conform to the dimensions shown on the plans.

Bars shall be bent or straightened in a manner that will not crack or break the material. Bars with kinks or improper bends shall not be used.

Hooks, bends and splices shall conform to the provisions of the Building Code Requirements for Reinforced Concrete of the American Concrete Institute.

Epoxy-coated Reinforcing Steel.--In fabricating, handling, shipping, and placing of epoxy-coated reinforcing bars, adequate care shall be taken to avoid damage to the coating. Handling and shipping equipment shall have padded contact areas. All bundling bands shall be padded or suitable banding shall be used to prevent damage to the coating. All bundles of coated bars shall be lifted with a strongback or multiple support system to prevent bar-to-bar abrasion from sags in the bundles. Bars or bundles shall not be dropped or dragged.

All damage to the coating caused by handling and fabrication prior to shipment to the jobsite shall be repaired as required by ASTM Designation: D 3963. Damage to the coating occurring during shipment or installation, or both, need not be repaired where the damaged areas are 6 mm by 6 mm or smaller and the sum of all damaged areas in each 300 mm length of bar does not exceed 2 percent of the bar surface area. All bars with total damage greater than 2 percent of the bar surface area will be rejected and shall be removed. On bars with a total damaged coating area not exceeding 2 percent of the bar surface area, all damaged areas larger than 6 mm square and all damage in sections of bar with more than 2 percent coating damage in a 300 mm length shall be repaired with patching material. The bar surface area covered by patching material shall not exceed 5 percent of the total surface area of the bar.

Patching material shall be compatible with the coating material, not harmfully reactive with the concrete, and shall be feasible for repairs by the coating applicator or bar fabricator or in the field. The patching material shall be prequalified as required for the coating material and shall be either identified on the container as meeting the requirements of Annex A1 of ASTM Designation: D 3963 or shall be accompanied by a Certificate of Compliance certifying that the material meets the requirements of said Annex A1. Patching of damaged areas shall be performed in accordance with the patching material manufacturer's recommendations.

MIXING AND TRANSPORTING CONCRETE.--

General.--When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be complete within 1 1/2 hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of cement to the aggregates.

Truck mixers or agitator shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified. The counters shall be of the continuous-registering type, which accurately register the number of revolutions and shall be mounted on the truck so that the Engineer may safely and conveniently inspect them from alongside the truck. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, a time less than 1 1/2 hours may be required.

When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be complete within one hour after the introduction of cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C, or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete for the work shall be accompanied by a trip ticket, a copy of which shall be delivered to the Engineer at the jobsite. The trip ticket shall show volume of concrete, weight of cement and aggregates, quantity of each admixture, quantity of water including water added at the jobsite, time of day the concrete is batched, and revolution counter readings on transit mix trucks at the times the truck is charged and unloaded.

PART 3.- EXECUTION

PREPARATION.--

Forms.--Forms shall be mortar tight, true to the dimensions, lines, and grades shown on the plans, securely fastened and supported, and of adequate rigidity to prevent distortion during placing of concrete.

Forms for exposed surfaces shall be constructed with triangular fillets not less than 19 mm x 19 mm attached so as to prevent mortar runs and to produce smooth straight chamfers at all sharp edges of the concrete.

Form fasteners shall be removable without chipping, spalling, heating or otherwise damaging the concrete surface. Form ties shall be removed to a depth of at least 25 mm below the surface of the concrete.

The inside surfaces of forms shall be cleaned of all dirt, mortar and foreign material. Forms shall be thoroughly coated with form oil prior to use.

Forms shall not be stripped until at least 40 hours after placing concrete.

Anchorage and embedded items shall be placed and rigidly secured at their planned locations prior to placing concrete.

Redwood dividers shall have 4 mm x 89 mm galvanized nails partially driven into both vertical faces at 450 mm on centers.

Vapor barrier.--Vapor barrier shall be lapped 150 mm and securely taped at splices. Vapor barrier shall be protected with a 75 mm layer of clean uncompacted sand cover.

Unless otherwise shown on the plans, vapor barrier shall be placed under portions of the floor slab scheduled to receive finish flooring.

Placing reinforcing steel.--Reinforcing steel bars shall be accurately placed to the dimensions shown on the plans.

Bar reinforcement conforming to ASTM Designation: A 615/A 615M, Grade 420, or A 706//A 706M shall be lapped at least 45 diameters.

Bars shall be firmly and securely held in position by means of wiring and approved bar supports. The spacing of supports and ties shall prevent displacement of the reinforcing or crushing of supports.

Tie wire shall be clear of concrete form work and concrete surfaces.

All reinforcing steel shall be in place and inspected before concrete placement begins. Placing of bars on fresh layers of concrete will not be permitted.

Within areas where epoxy-coated reinforcement is required, tie wire and bar chairs or other metallic devices used to secure or support the reinforcement shall be plastic or epoxy-coated to prevent corrosion of the devices or damage to the coated reinforcement.

Ground bar.--A continuous reinforcing steel bar shall be installed in the building foundation at the location indicated on the plans for the electrical ground bar. The use of epoxy coated reinforcing bar is not permitted. The end of the ground bar shall extend beyond the concrete surface and shall be protected from damage by construction operations.

PLACING CONCRETE.--

General.--Concrete shall be placed and consolidated by means of internal vibrators to form dense, homogeneous concrete free of voids and rock pockets.

Forms and subgrade shall be thoroughly moistened with water immediately before placing concrete.

Concrete shall be placed as nearly as possible to its final location and the use of vibrators for extensive shifting of the concrete will not be permitted.

Concrete shall be deposited and consolidated in a continuous operation within limits of construction joints, until the placing of the panel or section is completed.

When concrete is to be placed in large areas requiring more than two pours, concrete shall be placed in alternate long strips between construction joints and the final slab infilled.

Vibrators used to consolidate concrete containing epoxy-coated bar reinforcement shall have a resilient covering to prevent damage to such reinforcement.

FINISHING CONCRETE SURFACES.--

Finishing unformed surfaces.--Slabs shall be placed full thickness to finish elevation and leveled to screeds by use of long straightedges. The screeds shall be set to grade at approximately 1.8 meter centers. After leveling, screeds shall be removed and the surface shall be floated with wooden floats.

Type A control joint strips shall be inserted into the floated concrete so that the bottom of the top flange is flush with the finish elevation. Strips shall be standard manufactured lengths and shall be placed on an approximate straight line. The top flange of the strips shall be removed after the concrete has set and cured.

The floated surface shall be trowelled with steel trowels. Troweling shall form a dense, smooth and true finish. Walkways, pedestrian ramps, stairs and outdoor slabs for pedestrian traffic shall be given a non-slip broom finish unless a different finish is called for on the plans or in these special provisions.

The application of cement dust coat will not be permitted.

Finished surfaces of floor slabs shall not deviate more than 3 mm from the lower edge of a 3-meter long straight edge.

Finishing formed surfaces.--Formed concrete surfaces shall be finished by filling holes or depressions in the surface, repairing all rock pockets, and removing fins. All surfaces of formed concrete exposed to view shall have stains and discolorations removed, unsightly bulges removed, and all areas which do not exhibit the required smooth, even surface of uniform texture and appearance shall be sanded with power sanders or other approved abrasive means until smooth, even surfaces of uniform texture and appearance are obtained.

Cement mortar, patching and finishing materials used to finish exposed surfaces of concrete shall closely match the color of surrounding surfaces.

CURING CONCRETE.--

General.--Freshly placed concrete shall be protected from premature drying and excessive cold or hot temperatures.

Initial curing of floor slabs shall start as soon as free water has disappeared from the concrete surface. The concrete shall be kept continuously moist for not less than 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or sand blankets may be used as a curing medium to retain the moisture during the curing period. Curing materials that will stain or discolor concrete shall not be used on surfaces exposed to view.

Prior to placing the curing medium, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.

Concrete surfaces, other than floor slabs, shall be kept moist for a period of at least 5 days by leaving the forms in place or by covering the exposed surfaces using moist rugs, cotton mats or other curing materials approved by the Engineer.

Concrete curbs, sidewalks, collars, and gutter depressions shall be cured with a curing compound.

PROTECTING CONCRETE.--

General.--Concrete shall not be placed on frozen or frost covered surfaces.

Concrete shall be protected from damage due to rain, freezing or inclement weather, and shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall provide a written outline of his proposed methods of protecting concrete.

Vehicles, equipment, or concentrated loads weighing more than 140 kg individually and material stockpiles weighing more than 240 kg/m² will not be permitted on the concrete within 10 calendar days after placing.

SPECIAL TREATMENTS.--

Concrete sealer.--Concrete sealer shall be applied to the concrete surfaces designated on the plans in accordance with the manufacturer's instructions for heavy duty use. The sealer shall be applied to dry concrete surfaces.

SECTION 12-4. (BLANK)

SECTION 12-5. METALS

12-5.01 STRUCTURAL STEEL FOR BUILDINGS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of fabricating, assembling, furnishing and erecting structural steel in accordance with the details shown on the plans and these special provisions.

Structural steel consists of:

W shapes, C shapes, metal roof decking, angles, plates, stiffeners

Source quality control.--Materials and fabrication procedures are subject to inspection and tests in mill, shop and field, conducted by the Engineer or a qualified inspection agency. The Contractor or fabricator shall provide access to the Engineer or testing agency to places where the structural steel work is being fabricated or produced so that the required inspection and testing can be accomplished. Such inspections and tests will not relieve the Contractor of responsibility for providing materials and fabrication procedures in compliance with specified requirements. The testing agency may inspect the structural steel at the plant before shipment; however, the Engineer reserves the right, at any time before final acceptance to reject the material that does not conform to the contract requirements.

REFERENCES.--

General.--Structural steel shall be fabricated, assembled and erected in accordance with American Institute of Steel Construction (AISC), "Specifications for the Design, Fabrication and Erection of Structural Steel for Buildings."

Welding shall be in accordance with American Welding Society (AWS) D1.1, "Structural Welding Code - Steel."

Dimensional details and workmanship for welded joints in tubular and pipe connections shall conform to Part C, Structural Details; Part D, Special Provision for Welding Tubular Joints; and Part E, Workmanship, in Section 10 of AWS D1.1.

SUBMITTALS.--

Product data.--Product data for items to be incorporated into the work, including structural steel, high strength bolts, nuts and washers and alternative connectors, shall be submitted for approval.

Working drawings.--Working drawings and calculations shall be submitted for approval.

Working drawings shall show any changes proposed in the work, details of connections and joints exposed to the weather, details for connections not dimensioned on the plans, the sequence of shop and field assembly and erection, welding sequences and procedures. If required, the location of butt welded splices on a layout drawing of the entire structure, and the location and details of any temporary supports that are to be used.

Calculations and working drawings for falsework to be used for the erection of structural steel shall be submitted for approval. The falsework shall be designed and constructed to provide the necessary rigidity and to support loads which will be applied. Working drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown.

QUALITY ASSURANCE.--

Qualifications for welding.--A certified copy of qualification test record for welders shall be submitted to the Engineer at the jobsite. Descriptive data for equipment for field welding structural steel, including type and electric power requirements, shall be submitted for approval.

Certificates of Compliance.--Certificate of Compliance shall be furnished for structural steel products in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. Certificate of Compliance shall include mill test certificates for each heat number used in the work.

DELIVERY, HANDLING AND STORAGE.--

Structural materials shall be loaded, transported, unloaded and stored so that it is kept clean and undamaged. Material shall be stored above ground on platforms, skids, or other supports. Covers and protection shall be provided to protect the materials from corrosion.

Anchorage and anchor bolts, which are to be embedded in concrete or masonry, shall be delivered in ample time to not delay the work.

PART 2.- PRODUCTS

MATERIALS.--

Steel bars, plates and shapes.--

Steel bars, plates and shapes shall conform to ASTM Designation: A 572/A 572M, Grade 50 [345].

Stud connectors.--

Stud connectors shall conform to ASTM Designation: A 108, Grades 1018 through 1020, cold drawn, either semi- or fully killed.

Metal roof decking.--

Metal roof decking shall be galvanized sheet steel conforming to ASTM Designation: A 361 and the requirements shown on the plans.

Anchor bolts, nuts and washers.--

Nonheaded anchor bolts shall conform to ASTM Designation: A 36/A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 325.

Nuts shall conform to ASTM Designation: A 563M, Grade A.

Washers for anchor bolts shall be commercial quality.

Machine bolts, nuts and washers.--

Machine bolts and nuts shall conform to ASTM Designation: A 307.

Washers for machine bolts shall be commercial quality.

High strength (HS) bolts, nuts and washers.--

High strength (HS) bolts, nuts and washers shall conform to ASTM Designation: A 325M.

Direct tension indicators.--

Direct tension indicators shall conform to ASTM Designation: F 959.

Tension control fasteners.--

Tension control bolts shall have a splined end extending beyond the threaded portion of the bolt and which shears off when the specified bolt tension is attained.

Inorganic zinc primer.--

Inorganic zinc primer shall be a waterborne inorganic zinc primer conforming to the requirements of AASHTO Designation: M 300-92 I, Type II. Inorganic zinc primer shall be listed on the qualified products list which may be obtained from the Transportation Laboratory, (916) 227-7000.

Mortar.--

Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

FABRICATION.--

Shop fabrication and assembly.--Workmanship and finish shall be equal to the best general practice in modern shops.

Cuts shall not deviate more than 2 mm from the intended line. Roughness, notches or gouges shall be removed.

Bearing stiffeners at points of loading shall be square with the web and shall have at least 75 percent of the stiffener in contact with the flanges.

Finished members shall be true to line, shall have square corners and smooth bends and shall be free from twists, kinks, warps, dents and open joints.

Exposed edges and ends of metal shall be dressed smooth, with no sharp edges and with corners slightly rounded.

Stud connectors.--Steel surfaces shall be prepared as recommended by the manufacturer of the stud connectors. Stud connectors shall be welded to the flanges of beams or girders as shown on the plans. Automatic end welding of headed stud connectors shall be in accordance with the manufacturer's instructions.

Connections.--Abutting surfaces at connections shall be clean.

Cutting and welding at the jobsite will not be allowed except as shown on the approved drawings or specifically approved by the Engineer.

Finished holes for bolts shall be cylindrical and perpendicular to the plane of the connection. Subpunched and subdrilled holes shall be 6 mm smaller in diameter than the diameter specified for the finished hole.

Bolted Connections.--Bolts for connecting steel to steel shall be machine bolts conforming to ASTM Designation: A 307 or high-strength bolts conforming to ASTM Designation: A 325M as shown on the plans.

High-strength structural steel bolts, or equivalent fasteners, other bolts attached to structural steel, nuts, and washers shall be galvanized by mechanically deposited coating.

Holes for other work.--Holes for securing other work to structural steel and passage of other work through steel framing members shall be as shown on the approved drawings.

Threaded nuts or specialty items for securing other work to steel members shall be as shown on the approved drawings.

Holes shall be cut, drilled or punched perpendicular to metal surfaces. Holes shall not be flame cut or enlarged by burning. Holes are to be drilled in bearing plates.

SHOP PAINTING.--

General.--Structural steel members, except those to receive sprayed-fireproofing, shall be painted.

Surface preparation.--Surfaces of structural steel to receive inorganic zinc primer shall be blast cleaned in accordance with Steel Structures Painting Council, SSPC-SP 10, "Near-White Blast Cleaning."

Bolted connections.--Contact surfaces of high strength bolted connections and ungalvanized anchor bolt assemblies shall be blast cleaned and coated with waterborne inorganic zinc primer before assembly. The total thickness of primer on each surface shall be between 0.025 mm to 0.076 mm and may be applied in one application.

Painting.--Immediately after surface preparation, surfaces of structural steel shall receive an undercoat of waterborne inorganic zinc primer. Color shall essentially match Federal Standard 595B, No. 36373.

The manufacturer's published mixing and application instructions for inorganic zinc primer shall be followed.

PART 3.- EXECUTION

ERECTION AND ASSEMBLY.--

Field splices.--Field splices shall be made only at the locations shown on approved working drawings.

The parts shall be accurately assembled in their final position as shown on the plans and in true alignment with related and adjoining work before final fastening.

All parts shall be supported adequately and at locations to provide a vibration free, rigid, and secure installation.

Bolted connections.--All high strength bolted connections shall be made with high strength bolts installed with direct tension indicator washers or tension control fasteners.

When used, one mechanically galvanized direct tension washer shall be installed with each high strength bolt. Bolts shall be tightened until a direct tension indicator washer gap is 0.13 mm or less. A zero gap will not be cause for rejection.

During installation of tension control bolts, the torque required to turn the nut on the tension control bolt shall be counterbalanced by the torsion shear resistance of the splined end of the bolt.

The bolt head type and head location shall be consistent within a joint.

Nuts shall be on side of member least exposed to view.

Setting bases and bearing plates.--Concrete and masonry surfaces shall be cleaned and roughened to improve bond. Bottom of base and bearing plates shall be clean.

Base plates and bearing plates for structural members shall be set on wedges or other adjusting devices.

Anchor bolts shall be wrench tightened after supported members have been positioned and plumbed.

Mortar shall be solidly packed between bearing surfaces and base or bearing plates to ensure that no voids remain. Exposed surfaces shall be finished and allowed to cure.

FIELD PAINTING.--

Touch-up painting.--After erection, the Contractor shall clean field welds, bolted connections, and abraded areas of shop paint and apply the same materials as applied for shop painting.

Surfaces that are scheduled to receive finish coats shall be painted with an additional prime coat and finish coats in accordance with the requirements specified for shop primed steel under "Painting" in Section 12-9.

QUALITY CONTROL.--

Testing and inspection.--Ultrasonic examination shall be performed by the Contractor on at least 50 percent of all full penetration butt-welded splices in accordance with the requirements of AWS D1.1 and these special provisions.

Welding procedures and methods shall be subject to inspection for conformance with AWS D1.1.

Butt welds shall be tested in accordance with AWS D1.1, Chapter 6, Part C, Ultrasonic Testing of Groove Welds.

Examination, reporting and disposition of tests shall be in accordance with the provisions of 6.12, AWS D1.1.

In addition to ultrasonic examinations by the Contractor, welds may be subject to inspection or non-destructive testing by the Engineer.

When additional inspection or non-destructive testing is required by the Engineer, the Contractor shall provide sufficient access facilities in the shop and at the jobsite to permit the Engineer or his agent to perform such inspection and testing.

The Contractor shall correct all deficiencies in the structural steel work which inspections and laboratory test reports have indicated to be not in compliance with these special provisions. Additional tests shall be performed by the Contractor at his expense to reconfirm any non-compliance of original work, and to show compliance of the corrected work.

12-5.02 BUILDING MISCELLANEOUS METAL

PART 1.- GENERAL

Scope.--This work shall consist of fabricating, furnishing and installing building miscellaneous metal in accordance with the details shown on the plans and these special provisions.

Building miscellaneous metal shall include all anchors, fastenings, hardware, accessories and other supplementary parts necessary to complete the work.

REFERENCES.--

Codes and standards.--Welding of steel shall be in accordance with American Welding Society (AWS) D 1.1, "Structural Welding Code-Steel" and D 1.3, "Structural Welding Code-Sheet Steel."

SUBMITTALS.--

Product data.--Submit manufacturer's specifications, anchor details and installation instructions for products used in miscellaneous metal fabrications.

Working drawings.--Working drawings of fabricated items shall be submitted for approval.

QUALITY ASSURANCE.--

Shop assembly.--Preassemble items in shop to the greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark all units for reassembly and installation.

Inspection and tests.--Materials and fabrication procedures shall be subject to inspection and tests by the Engineer, in mill, shop and field. Such tests will not relieve the Contractor of responsibility of providing materials and fabrication procedures in compliance with specified requirements.

PART 2.- PRODUCTS

MATERIALS.--

Galvanized sheet steel.--

Galvanized sheet steel shall conform to ASTM Designation: A 446M having a minimum yield strength of 228 MPa. Galvanizing shall be G60.

Bolts, studs, threaded rods, nuts and washers.--

Bolts, studs, threaded rods, and nuts for general application shall conform to ASTM Designation: A 307.

Washers shall be commercial quality.

Fittings.--

Brackets, bolt, threaded studs, nuts, washers, and other fittings for railings and handrailings shall be commercial quality pipe and fittings.

Expansion anchors.--

Expansion anchors shall be ICBO approved for the purpose intended, integral stud type anchor or internally threaded type with independent stud, hex nut and washer.

Mortar.--

Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

FABRICATION.--

Workmanship and finish.--Workmanship and finish shall be equal to the best general practice in modern shops.

Miscellaneous metal shall be clean and free from loose mill scale, flake rust and rust pitting, and shall be well formed and finished to shape and size with sharp lines and angles. Bends from shearing or punching shall be straightened.

The thickness of metal and details of assembly and support shall give ample strength and stiffness.

Built-up parts shall be true to line and without sharp bends, twists and kinks. Exposed ends and edges of metal shall be milled or ground smooth, with corners slightly rounded.

Joints exposed to the weather shall be made up to exclude water.

Galvanizing.--Items indicated on the plans to be galvanized shall be hot-dip galvanized after fabrication. The weight of galvanized coating shall be at least 460 grams per square meter of surface area, except drainage grates shall have at least 610 grams per square meter of surface area.

Painting.--Building miscellaneous metal items not galvanized shall be cleaned and prime painted prior to erection in accordance with the requirements specified for steel and other ferrous metals under "Painting" in Section 12-9, "Finishes," of these special provisions.

Loose bearing and leveling plates.--Loose bearing and leveling plates shall be furnished for steel items bearing on masonry or concrete construction, made flat, free from warps or twists, and of required thickness and bearing area. Plates shall be drilled to receive anchor bolts. Galvanize after fabrication.

PART 3.- EXECUTION

GENERAL.--

Anchorage.--Anchorage devices and fasteners shall be provided for securing miscellaneous metal in-place construction; including threaded fasteners for concrete and masonry inserts, toggle bolts, through bolts, lag bolts, wood screws and other connectors.

Cutting, drilling and fitting shall be performed as required for installation of miscellaneous metal fabrications. Work is to set accurately in location, alignment and elevation, plumb, level, true and free of rack, measured from established lines and levels.

Loose leveling and bearing plates.--Plates shall be set on wedges or other adjustable devices. Anchor bolts shall be wrench tightened after the plates have been positioned and plumbed. Mortar shall be packed solidly between bearing surfaces and plates to ensure that no voids remain.

DAMAGED SURFACES.--

General.--Galvanized surfaces that are abraded or damaged at any time after the application of the zinc coating shall be repaired by thoroughly wire brushing the damaged areas and removing all loose and cracked coating, after which the clean areas shall be painted with 2 applications of unthinned zinc-rich primer (organic vehicle type). Aerosol cans shall not be used.

12-5.03 ALUMINUM GATE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of fabricating, furnishing and installing aluminum gate in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for products and processes used in gate fabrication shall be submitted for approval.

Working drawings.--Working drawings of gate shall be submitted for approval.

Working drawings shall show fabrication and installation for gate including plans, elevations, sections, profiles of rails, fittings, connections and anchors.

PART 2.- PRODUCTS

MATERIALS.--

Gate elements.--

Gate elements shall conform to ASTM Designation: B 429, Type 6061-T6 aluminum alloy pipe.

Brackets, flanges, fittings and anchors.--

Brackets, flanges, fittings and anchors shall be the manufacturer's standard for interconnection of gate members to other work.

Fasteners.--

Fasteners shall be the same basic metal as the fastened metal. Corrosive metals and metals that are incompatible with the metals joined shall not be used.

Exposed fasteners shall be Phillips flat head screws unless otherwise noted on the plans.

FABRICATION.--

General.--Gate shall be fabricated to the dimensions and details shown on the plans.

Items shall be preassembled in the shop to the greatest extent possible to minimize field splicing and assembly. Units shall be disassembled only as necessary for shipping and handling.

Welding shall be by the tungsten inert gas arc welding method or the consumable electrode inert gas method. Welding processes that require the use of flux will not be permitted.

All welds shall conform to the requirements of Section 8.15, "Quality of Welds," of the American Welding Society publication No. AWS D 1.1, "Structural Welding Code."

Exposed welds shall be ground smooth and flush.

FINISHES.--

Anodizing.--After fabrication, exposed surfaces of aluminum shall be given a clear anodic oxide coating conforming to the requirements of ASTM Designation: B 580, Type B, Architectural Class I. Surfaces to be coated shall be free of scratches, porosity, inclusions, roll and die marks, cold-shuts, and cracks that will adversely affect the appearance and performance of the anodic coatings.

PART 3.- EXECUTION

INSTALLATION.--

General.--The gate shall be erected to line and grade without welding in the field. Installation shall be in accordance with the manufacturer's recommendations.

Exposed connections shall be accurately fitted to form tight, hairline joints.

Corrosion protections.--Aluminum surfaces to be in contact with grout or concrete materials shall be given a heavy coat of alkali-resistant bituminous paint or zinc chromate primer.

An isolation coating shall be provided on aluminum surfaces in contact with dissimilar metals.

Gate shall be secured to walls with the manufacturer's standard wall brackets and fittings, unless otherwise shown on the plans.

CLEANING.--

General.--Paint, dirt, stains and grout shall be removed without marring or scratching the aluminum surfaces. Solvents and cleaning compounds shall be chemically compatible with the anodic coating and aluminum.

PROTECTION.--

General.--Finishes of gate shall be protected from damage during constructions by use of temporary protective coverings. Coverings are to be removed upon completion of the work.

Finishes damaged during installation and construction shall be restored so that no evidence remains of construction work.

SECTION 12-6. WOOD AND PLASTICS

12-6.01 ROUGH CARPENTRY

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing materials and performing rough carpentry work including wood framing, furring, sheathing and subflooring, in accordance with the details shown on the plans and these special provisions.

Rough carpentry includes carpentry work not specified as part of other sections and which is generally not exposed.

SUBMITTALS.--

Product Data.--Manufacturer's material data and installation instructions shall be submitted for gypsum sheathing, framing hardware and underlayments.

Wood treatment data.--Chemical treatment manufacturer's instructions shall be submitted for the handling, sorting, installation, and finishing of treated materials.

For each type of preservative treatment used, certification by treating plant shall include type of preservative solution and pressure process used, net amount of preservative retained and conformance with the applicable standards of the American Wood Preservers Association.

For each type of fire-retardant treatment, include certification by treating plant that the treated material complies with the applicable standards and other requirements.

DELIVERY, HANDLING AND STORAGE.--

Delivery and storage.--Materials shall be kept under cover and dry. All materials shall be protected from exposure to weather and contact with damp or wet surfaces with blocking and stickers. All lumber, plywood and other panels shall be stacked in such a manner to provide air circulation within and around the stacks.

PART 2.- PRODUCTS

LUMBER.--

General.--Lumber shall be manufactured to comply with PS 20, "American Softwood Lumber Standard," and with applicable grading rules of inspection.

Softwood lumber shall be quality grade stamped or shall be accompanied by a certificate of inspection. Inspection certificates or grade stamps shall indicate compliance with the grading requirements of WWPA, WCLIB, RIS, or other approved lumber inspection agencies.

All lumber used shall be nominal sized and dressed S4S unless otherwise specified in these special provisions.

Framing lumber shall be solid stock lumber, Douglas Fir-Larch, and the grades indicated under WCLIB or WWPA rules. Moisture content shall not exceed 19 percent and shall be grade stamped "S-Dry."

DIMENSION LUMBER.--

Except as otherwise shown on the plans, lumber shall have the following grades.

Vertical framing lumber.--

Vertical framing lumber, nominal 51 mm x 51 mm through 102 mm x 102 mm, shall be Construction grade or better.

Vertical framing lumber, nominal 51 mm x 152 mm through 102 mm x 152 mm shall be No. 2 or better.

Horizontal framing lumber.--

Horizontal framing lumber, nominal 51 mm x 102 mm and wider, including joists and rafters, shall be No. 2 or better.

Horizontal framing lumber, nominal 102 mm x 102 mm and wider, including joists and rafters, shall be No. 1 or better.

Exposed framing lumber.--

Exposed framing lumber which is not concealed and is to receive a stain or natural finish shall be the same grade and species as indicated for structural framing and hand selected for appearance.

Miscellaneous lumber.--

Miscellaneous lumber for support or attachment of other work including rooftop equipment curbs and support bases, cant strips, bucks, nailers, blocking, furring, grounds, stripping and similar members shall be not less than No. 2 or better.

Lumber in contact with concrete or masonry construction shall be pressure treated Douglas Fir or foundation grade Redwood, No. 2 or better.

TIMBERS.--**Timbers (nominal 127 mm or thicker).--**

Timbers shall be No. 1 or better.

CONSTRUCTION PANELS.--

General.--Construction panels shall comply with Voluntary Product Standard PS1, "U. S. Product Standard for Construction and Industrial Plywood," or American Plywood Association (APA), "Performance Standards and Policies for Structural Use Panels."

Plywood and construction panels shall be Group 1 unless otherwise noted.

Each construction panel shall be factory marked with APA or other trademark evidencing compliance with grade requirements.

Structural plywood wall sheathing.--

Structural plywood wall sheathing for interior walls shall be APA RATED SHEATHING, Exposure 1. Span rating and thickness shall be as shown on the plans. Structural plywood wall sheathing shall be Flame Spread Class III (Index 76-200) per UBC table 8-A.

Structural plywood wall sheathing for exterior walls shall be APA RATED SHEATHING, Exposure 1. Span rating and thickness shall be as shown on the plans.

Structural plywood roof sheathing.--

Structure plywood roof sheathing shall be APA RATED SHEATHING, Exterior. Span rating and thickness shall be as shown on the plans. Structural plywood roof sheathing shall be Flame spread Class III (Index 76-200)per UBC table 8-A.

Structure plywood roof sheathing in exposed overhangs shall be APA RATED SHEATHING, A-C, Exterior. Span rating and thickness shall be the same as the remainder of the sheathing.

Plywood backing panels.--

Plywood backing panels for mounting electrical or telephone equipment shall be 19 mm, fire-retardant treated plywood panels APA A-C PLUGGED INT with exterior glue, touch-sanded.

Plywood decking.--

Plywood decking shall be APA RATED STURD-I-FLOOR, Exposure 1, with tongue-and-groove edges. Span rating and thickness shall be as shown on the plans.

MISCELLANEOUS MATERIALS.--

Rough Carpentry Hardware.--

Steel plates and rolled sections shall be mild, weldable steel, conforming to AISI grades 1016 through 1030 except 1017.

Nails, screws, bolts, nuts, washers shall be commercial quality. Exposed fasteners shall be hot dipped galvanized or stainless steel.

Joist hangers, clips and other standard framing hardware shall be ICBO approved, commercial quality, galvanized sheet steel or hot dipped galvanized, of the size shown on the plans.

Expansion anchors, resin anchors, and powder driven anchors shall be as specified under "Building Miscellaneous Metal," in Section 12-5, "Metals," of these special provisions.

Building paper.--

Building paper shall be kraft type waterproofing building paper, Type I (No. 15) asphalt saturated roofing felt or high density, bonded polyethylene fiber building paper.

Adhesive.--

Adhesive for plywood glue-nailed systems shall conform to APA Specification: AFG-01.

WOOD TREATMENT BY PRESSURE PROCESS.--

Preservative treatment.--

Preservative treatment shall be copper naphthenate, pentachlorophenol or water-borne arsenicals (ACA, CCA or ACZA).

The following items shall be treated:

Wood cants, nailers, curbs, equipment support bases, blocking, stripping and similar members in connection with roofing, flashing, vapor barriers and waterproofing.

Wood sills, sleepers, blocking, furring and other similar members in contact with concrete or masonry.

All holes, daps and cut ends of treated lumber shall be thoroughly swabbed with 2 applications of copper naphthenate.

PART 3.- EXECUTION

INSTALLATION.--

Wood framing.--Wood framing shall be in accordance with Chapter 23 of the Uniform Building Code as amended the 1995 Title 24 California Building Standard Code.

Framing members shall be of sizes and spacing shown on the plans. Unless otherwise shown on the plans, structural members shall not be spliced between supports.

Wood framing shall be accurately cut and assembled to provide closely fitted members. Framing shall be erected true to the lines and grades shown on the plans and shall be rigidly secured in place as shown and as required by recognized standards. Bracing shall be placed wherever necessary to support all loads on the structure during erection.

The size and spacing of fasteners and the edge distance for nails shall be as shown on the plans.

Nailing schedule shall be as shown on the plans and shall comply with the Uniform Building Code.

Wall coverings exposed to the weather shall have a backing of building paper applied weatherboard fashion to the framing or sheathing. Backing shall be lapped 50 mm at horizontal joints, 152 mm at vertical joints and 305 mm at building corners.

Stair framing.--Stair framing members shall be of the size and spacing shown on the plans.

Stringers shall be notched to receive treads, risers and supports. Effective depth remaining shall be not less than 89 mm.

Construction panels.--Construction panels shall be attached to the framing as shown on the plans and these special provisions.

Subflooring shall be glued and nailed to the framing system.

Wall and roof sheathing shall be nailed to the framing system and shall be continuous over 2 or more supports. Roof and floor panels shall be installed with the long dimension across the supports, with end joints staggered 1.25 mm. Wall sheathing shall have all edges blocked. Spacing between panels shall be 3 mm.

Underlayment shall be nailed or stapled to the framing system. Panels shall be installed with the long dimension across the supports and shall be continuous over 2 or more supports. Panel ends shall be staggered. Spacing between panels shall be 3 mm.

12-6.02 PRE-ENGINEERED WOOD TRUSSES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of designing, fabricating, furnishing and erecting pre-engineered, factory fabricated wood trusses in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's data for lumber, metal plates, hardware and fabrication process shall be submitted for approval.

Working drawings.--Complete working drawings, erection drawings, if required, and design calculations for the pre-engineered wood trusses and permanent bracing shall be submitted for approval. Submittals shall be approved prior to the start of fabrication.

Working drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown. Engineer's original signature shall be submitted, copies will not be accepted.

Working drawings shall show the lumber size, species and grades for all truss and temporary and permanent bracing members. Joint and connection details shall be shown.

Working drawings shall include a location plan which shows the location and identification of each truss.

Calculations for the design of the trusses and bracing shall include a list of applied loads and load combinations, including fire sprinkler system if required, with the resulting member forces and member stresses.

If the design calculations contain or consist of computerized or tabulated calculations, the values pertaining to the design shall be identified, described or indexed in such a manner that a design review can be performed.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for trusses in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Codes and standards.--Wood trusses and permanent bracing shall be designed for the loads shown on the plans. The design shall be in accordance with the requirements of the Uniform Building Code (UBC), the "National Design Specification for Wood Construction" by the National Forest Products Association (NFPA), the "Timber Construction Standards" by the American Institute of Timber Construction (AITC) and the "Design Specifications for Light Metal Connected Wood Trusses" by the Truss Plate Institute (TPI).

Wood trusses with light metal plate connectors shall be fabricated in accordance with the requirements of the UBC Section 2343.

DELIVERY, STORAGE AND HANDLING.--

Trusses shall be transported and handled in such a manner as to prevent damage due to warping, distortion and moisture.

Trusses shall be stored off the ground in such a manner to avoid damage from bending, overturning or other cause for which the truss is not designed to resist or endure.

PART 2.- PRODUCTS

Pre-engineered truss.--

Pre-engineered truss shall be factory fabricated pre-engineered truss sized to fit the location shown on the plans. Lumber sizes, species and grades shall be as shown on the approved working drawings. Lumber shall bear grade marks of a recognized grading association and the moisture content of the lumber shall be within the amount specified in the referenced specifications.

Connector plates.--

Connector plates shall be galvanized sheet steel conforming to ASTM Designation: A 446, Grade A. Zinc coating by hot dip galvanizing shall conform to ASTM Designation: A 525, G90. Minimum coated metal thickness shall be not less than 0.91 mm.

Steel plates and rolled sections.--

Steel plates and rolled sections shall be mild, weldable steel, AISI grades 1016 through 1030 except 1017.

Bolts, nuts and washers.--

Bolts, nuts and washers shall conform to ASTM Designation: A 307.

FABRICATION.--

General.--Truss and bracing members shall be accurately cut to length and shape to provide tightly fitted joints.

Connectors, framing anchors and other hardware accessories shall be coordinated for placement in the proper locations and positions.

Camber, if required by the design, shall be built into the trusses.

Each truss shall be stamped or marked with a location identification mark or symbol and with the name and address of the manufacturer.

Connector plates.--Connector plates shall be coated with epoxy paint after installation. Surfaces to be coated shall be prepared and painted as recommended by the paint manufacturer.

PART 3.- EXECUTION

INSTALLATION AND ERECTION.--

General.--Trusses shall be erected plumb and true and shall be secured rigidly in place in accordance with the truss manufacturer's recommendations.

Fasteners and connectors shall be placed as shown on the plans and as recommended by the truss manufacturer.

Longitudinal and transverse bracing shall be installed during erection to hold the trusses plumb and true and in a safe position until sufficient permanent construction is in place to provide full stability.

All permanent bracing shall be secured in place before any sustained permanent loads are applied to the roof truss system.

Materials loaded on the truss system shall be located in such a manner that the design load of the trusses is not exceeded in the area of placement of the loads.

12-6.03 LAMINATED VENEER LUMBER

PART 1.- GENERAL

SUMMARY.--

Scope.--This work consists of furnishing and erecting laminated veneer lumber members, in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's data, current ICBO Evaluation Report, and specifications for laminated veneer lumber, including adhesives, shall be submitted for approval.

QUALITY ASSURANCE.--

Codes and standards.--The laminated veneer lumber manufacturer shall be have a current approved ICBO Evaluation Report for the product.

Factory marks.--Laminated veneer lumber members shall be identified with stamps noting the name of the manufacturer, product name, grade, ICBO evaluation report number, and the quality control agency.

Certificates of Compliance.--Certificates of Compliance shall be furnished for laminated veneer lumber in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, STORAGE, HANDLING.--

General.--Laminated veneer lumber members shall be stored in such a manner to prevent warping and damage due to moisture.

Laminated veneer lumber members shall be stored off the ground.

PART 2.- PRODUCTS

Laminated veneer lumber.--

Laminated veneer lumber members shall be constructed by gluing wood veneers together with an exterior type adhesive. The veneer grain shall be parallel to the member length.

Laminated veneer lumber members shall have a minimum allowable bending stress (F_b) of 19.99 Mpa, allowable shear stress (F_v) of 1.99 Mpa, and a minimum modulus of elasticity (E) of 13 790 Mpa. Laminated venneer lumber shall be Paralam; or equal.

FABRICATION.--

General.--Laminated veneer lumber members shall fabricated in accordance with the ICBO Evaluation Report.

PART 3.- EXECUTION

INSTALLATION.--

General.--Miscellaneous steel connectors, anchors and accessories shall be installed as shown on the plans. Members shall be erected so that a close fit and neat appearance of joints and structure as a whole will not be impaired.

12-6.04 FINISH CARPENTRY

PART 1.- GENERAL

SUMMARY.--

Scope.--This work consists of furnishing and installing materials and performing finish carpentry, including exterior and interior trim, plywood soffits and panels and plywood and softwood paneling, as shown on the plans and these special provisions.

Finish carpentry includes carpentry work not specified as part of other sections and which is generally exposed to view.

SUBMITTALS.--

Product data.--Manufacturer's specifications and installation instructions for each item of factory-fabricated siding and paneling.

Samples.--One sample shall be submitted to the Engineer at the jobsite for each species and cut or pattern of finish carpentry as shown below:

Interior standing and running trim - 610 mm long by full board or molding width, finished on one side and one edge.

Plywood paneling - 610 mm long x full panel width, finished on one side.

QUALITY ASSURANCE.--

Factory marks.--Each piece of lumber and plywood shall be marked with type, grade, mill and grading agency identification. Marks shall be omitted from surfaces to receive transparent finish. A mill certificate stating that material has been inspected and graded in accordance with requirements shall be furnished if marks cannot be placed on concealed surfaces.

PRODUCT DELIVERY, STORAGE AND HANDLING.--

Delivery.--Carpentry materials shall be delivered after painting, wet work and similar operations have been completed.

Protection.--Finish carpentry materials shall be protected during transit, delivery, storage and handling to prevent damage, soiling and deterioration.

PART 2.- PRODUCTS

WOOD PRODUCT QUALITY STANDARDS.--

Softwood lumber.--Softwood lumber shall conform to the requirements of PS 20, "American Softwood Lumber Standard," with applicable grading rules of inspection.

Plywood.--Plywood shall conform to the requirements of Voluntary Products Standard PS-1, "U. S. Product Standard for Construction and Industrial Plywood."

Hardwood lumber.--Hardwood lumber shall conform to the requirements of the National Hardwood Lumber Association (NHLA) rules.

Woodworking.--Woodworking shall conform to the requirements of Woodwork Institute of California (WIC), "Manual of Millwork."

MATERIALS.--

General.--Lumber sizes indicated shall be nominal sizes except as indicated by detailed dimensions. Lumber which is to be dressed or worked and dressed shall be manufactured to the actual sizes as required by PS 20.

Lumber that is to receive a transparent finish (stained or clear) shall be made of solid lumber stock.

Lumber that is to be painted may be solid or glued-up lumber at the contractor's option.

Glued-up lumber for exterior finish work shall comply with PS 56 for "wet use" and be so certified by the inspection agency.

Plywood paneling and wainscotting.--

Plywood paneling and wainscotting shall be APA Interior Grade A-C, Group 1, Exposure 1 plywood. Thickness shall be as shown on the plans.

Interior standing and running trim.--

Standing and running trim to be painted shall be paint-grade pine, solid stock or finger jointed.

Standing and running trim to have transparent finish shall be solid hardwood, species to be shown on the plans.

Stair treads.--

Interior stair treads shall be S3S, C and better grade Douglas fir stepping.

Stair risers.--

Interior stair risers shall be S4S, No. 1 grade Douglas fir.

Railings.--

Interior railings shall be S4S, No. 1 grade Douglas fir.

Miscellaneous Materials.--

Nails, screws and other anchoring devices of the type, size, material and finish required shall be provided for secure attachment, concealed where possible.

Fasteners and anchorages for exterior use shall be hot dip galvanized.

Screens for soffit vents shall be 4 x 4 or 8 x 8 mesh, galvanized screen. Open area shall be not less than 50 percent.

Preservative treatment.--

Preservative treatment shall be copper naphthenate, pentachlorophenol or water-borne arsenicals (ACA, CCA or ACZA).

Wood members, except those of redwood, in contact with mortar setting beds, concrete block walls, slab on grade and other concrete work, and wood used for roofing cant and curbs shall be pressure treated with leach resistant preservative. Each piece of pressure treated lumber shall bear the AWPA label.

All holes, daps, or cuts made after treating shall be thoroughly swabbed with copper naphthenate.

PART 3.- EXECUTION**INSTALLATION.--**

General.--All work shall be installed plumb, level and true with no distortions.

Standing and running trim.--Standing and running trim shall be installed with minimum number of joints possible, using full length pieces to the greatest extent possible.

Exterior joints shall be made water-resistant by careful fitting.

Anchor finish carpentry.--Finish carpentry shall be anchored to framing or blocking built in or attached directly to the substrate.

Interior carpentry shall be attached to grounds, stripping and blocking with countersunk, concealed fasteners and blind nailing where required for complete installation. Fine finish nails shall be used for exposed nailing, countersunk and filled flush with finished surface and matching final finish where transparent finish is indicated.

Finish exterior siding shall be fastened with corrosion resistant nails. The size and spacing of the siding fasteners shall be as shown on the plans. Nails shall be driven flush with the surrounding surfaces, not countersunk. Nails shall be located in the grooves of grooved siding whenever possible.

ADJUSTMENT, CLEANING, FINISHING AND PROTECTION.--

General.--Damaged and defective finish carpentry work shall be repaired or replaced.

All exposed or semi-exposed surfaces shall be cleaned.

Finish carpentry shall be finished in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

SECTION 12-7. THERMAL AND MOISTURE PROTECTION**12-7.01 WATER REPELLENT SEALANT****PART 1.- GENERAL****SUMMARY.--**

Scope.--The work shall consist of cleaning and placing a silane sealant on exterior concrete surfaces and on those interior concrete surfaces that will not be covered by insulation, framing, paneling or other construction.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and application instructions shall be submitted for approval.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished with each shipment of water repellent sealant in accordance with Section 6-1.07, "Certificates of Compliance," of the Standard Specifications, and a Materials Safety Data Sheet.

PART 2.- PRODUCTS

Manufacturers.--Water repellent sealer shall be Hydrozo Inc., Enviroseal 40; Tamms Industries, Baracade Silane 40; Sonneborne, Penetrating Sealer 40; or equal.

Water repellent sealant.--

Water repellent sealant shall be a 40 percent minimum, organosilane solution, diluted in a suitable solvent, and shall consist of alkyltrimethoxy silanes with alkyl groups of i-butyl, i-octyl, n-octyl, singularly or in combination.

The water repellent sealant shall be tinted with a fugitive dye which will cause the concrete sealant to be distinguishable on the concrete surface for at least four hours after application, but shall disappear within seven days after application.

PART 3.- EXECUTION

PREPARATION.--

Protection.--Surfaces of other materials surrounding or near the surfaces to receive the water repellent sealant shall be protected from overspray or spillage from the waterproofing operation. Water repellent sealant applied to surfaces not intended to be waterproofed shall be removed and the surfaces restored to their original condition.

Surface preparation.--All surfaces to receive water repellent sealant shall be cleaned with light abrasive blasting. Blasting shall remove all dirt, debris and other deleterious materials, including removal of existing cement matrix. After cleaning, the concrete surfaces shall be air blown to dry and remove loose surface material prior to sealing.

APPLICATION.--

General.--The water repellent solution shall be applied in accordance with manufacturer's application instructions.

Water repellent sealant shall be applied only during periods of weather as recommended by the manufacturer, when the atmospheric temperature is between 4°C and 38°C and for exterior application when wind speed is less than 8 kilometers per hour.

Subject to written approval by the Engineer, the Contractor may provide suitable enclosures to permit concrete sealing during inclement weather.

FIELD QUALITY CONTROL.--

Tests.--Approximately 24 hours after placement of the water repellent sealant, the Contractor shall uniformly dampen the treated concrete surface using a fine water spray. Spray shall completely wet the surface without causing runoff.

After 5 days following sealant application, if required by the Engineer, the Contractor shall spray designated sealed concrete surfaces with a fresh water spray to verify sealant coverage. The water spray shall not penetrate the concrete surfaces, and surfaces determined to lack sufficient sealant coverage shall be resealed.

12-7.02 INSULATION (GENERAL)

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing insulation in accordance with the details shown on the plans and these special provisions.

Insulation materials shall be as specified in these special provisions, and shall be compatible with existing or new materials incorporated in the building.

SUBMITTALS.--

Product data.--A list of materials, manufacturer's descriptive data, location schedule, and time schedule shall be submitted for approval.

The list of materials to be used shall include the trade name, manufacturer's name, smoke developed and flame spread classification, resistance rating and thickness for the insulation materials and accessories.

Schedules.--A location schedule and time schedule shall be submitted for approval.

The location schedule shall show where each material is to be installed.

The Contractor shall provide the Engineer at the jobsite with an accurate time schedule of the areas of the building to be insulated each day. The time schedule shall be submitted 3 working days in advance of the work.

Samples.--Samples of insulation material shall be submitted to the Engineer at the jobsite.

QUALITY ASSURANCE.--

Codes and standards.--All insulating materials shall be certified to comply with the California Quality Standards for Insulating Materials and shall be listed in the Department of Consumer Affairs publication "Consumer Guide and Directory of Certified Insulation Material."

DELIVERY, STORAGE AND HANDLING.--

General.--Insulating materials shall be delivered to the jobsite and stored in a safe dry location with labels intact and legible.

Insulating materials shall be protected from physical damage and from becoming wet or soiled.

In the event of damage, materials shall be repaired or replaced as necessary to comply with these specifications.

PART 2.- PRODUCTS (Not applicable.)

PART 3.- EXECUTION (Not applicable.)

12-7.02A BATT INSULATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing batt insulation in accordance with the details shown on the plans and these special provisions.

Batt insulation shall include faced and unfaced batts in walls and ceilings.

QUALITY ASSURANCE.--

Laminator's qualifications.--Laminator for bonding polyethylene vapor-retarder to insulating batts shall be approved by the insulation manufacturer.

The name of the laminator shall be submitted with the Product Data.

Codes and standards.--All batt insulation, including facings such as vapor barriers, shall have a flame-spread rating not to exceed 25 and a smoke density not to exceed 450 when tested in accordance with UBC Standard No. 8-1.

The flame-spread and smoke density limitations do not apply to facings on batt insulation installed between ceiling joists, or in roof-ceiling or wall cavities, provided the facing is installed in substantial contact with the surface of the ceiling or wall finish.

PART 2.- PRODUCTS

INSULATING MATERIALS.--

General.--Fiberglass batts shall be thermal insulation produced by combining glass fibers with thermosetting resins to comply with ASTM Designation: C 665.

Wall insulation.--

Wall insulation shall be R-3.3 K• m²/W fiberglass batts with paper-laminate vapor-retarder membrane on one face. Insulation shall conform to ASTM Designation: C 665, Type II, Class C.

Ceiling insulation.--

Ceiling insulation shall be R-5.3 K• m²/W fiberglass batts with paper-laminate vapor-retarder membrane on one face. Insulation shall conform to ASTM Designation: C 665, Type II, Class C.

Exposed insulation.--

Exposed insulation shall be fiberglass batts with foil-paper vapor-retarder membrane on one face. Insulation shall conform to ASTM Designation: C 665, Type III, Class A. Exposed insulation for ceilings shall be R-5.3 K• m²/W and R-3.3 K• m²/W for walls.

VAPOR-RETARDERS.--

Paper-laminate vapor-retarder.--

Paper-laminate vapor-retarder shall be kraft paper sheets laminated together with asphalt or other vapor retarding compounds, scrim reinforced at edges of sheets.

Foil-paper vapor-retarder.--

Foil-paper vapor-retarder shall be 0.0076 mm reflective aluminum foil laminated with scrim reinforcing to plastic-coated kraft paper.

Polyethylene vapor-retarder.--

Polyethylene vapor-retarder shall be factory-applied, 0.076 mm, white polyethylene film, a blend of fiberglass and polyester yarn reinforcement, and metallized polyester film laminated with a flame resistant adhesive, and a Class I flame-spread classification.

AUXILIARY INSULATION MATERIALS.--

Insulation tape.--

Insulation tape shall be as recommended by the insulation manufacturer.

Insulation adhesive.--

Insulation adhesive shall be the type recommended by the insulation manufacturer and complying with the requirements for fire resistance.

FABRICATION--

General.--Polyethylene shall be factory laminated to fiberglass batts or blankets by an applicator approved by the manufacturer of the batts or blankets.

PART 3.- EXECUTION

INSTALLATION.--

General.--The vapor retarder on faced batts shall be toward the interior and shall be fastened to provide a sealed retarder. Punctures and holes in the retarder shall be repaired.

Unless otherwise shown on the plans or specified elsewhere in these special provisions, insulation shall be kept 75 mm to 100 mm clear of lighting fixtures and heat producing electrical appliances and equipment.

Installing batt type insulation.--Insulation batts shall be installed to completely fill the space between framing members. Apply a single layer of insulation of required thickness, unless otherwise shown on the plans or required to make up total thickness. Installation shall conform to the manufacturer's recommendations and these special provisions.

12-7.02B INSULATION FOR PRE-ENGINEERED STEEL BUILDING

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a batt insulation for pre-engineered steel building in accordance with the details shown on the plans and these special provisions.

Insulation for pre-engineered steel building shall be batt for ceilings and walls. Insulating materials and details of fastening and support systems shall be compatible with the pre-engineered building being furnished and shall be of a type approved by the building manufacturer.

Vapor retarder requirements may be waived for certain alternative systems that have a suitable finish on the exposed surfaces.

QUALITY ASSURANCE.--

Laminator's qualifications.--Laminator for bonding polyethylene vapor-retarder to insulating batts shall be approved by the insulation manufacturer.

The name of the laminator shall be submitted to the Engineer with the Product Data.

Codes and standards.--All batt insulation, including facings such as vapor barriers, shall have a flame-spread rating not to exceed 25 and a smoke density not to exceed 450 when tested in accordance with UBC Standard No. 8-1.

The flame-spread and smoke density limitations do not apply to facings on batt insulation installed between ceiling joists, or in roof-ceiling or wall cavities, provided the facing is installed in substantial contact with the surface of the ceiling or wall finish.

PART 2.- PRODUCTS

INSULATING MATERIALS.--

General.--Fiberglass batts shall be thermal insulation produced by combining glass fibers with thermosetting resins to comply with ASTM Designation: C 665.

Insulation.--

Insulation shall be glass fiber batt. Areas without interior finish shall have insulation and integral vapor retarder. Minimum thermal resistance rating shall be $R5.3 \text{ K} \cdot \text{m}^2/\text{W}$ for the roof and $R3.3 \text{ K} \cdot \text{m}^2/\text{W}$ for the walls.

Polyethylene vapor-retarder.--

Polyethylene vapor-retarder shall be factory-applied, 0.15 mm, white polyethylene film, a blend of fiberglass and polyester reinforcement, and metallized polyester film laminated with a flame resistant adhesive.

Fasteners, supports and adhesive.--

Fasteners, supports and adhesive shall be as recommended by the insulation manufacturer. Adhesives shall be non flammable, water resistant and nontoxic vehicle.

PART 3.- EXECUTION

INSTALLATION.--

General.--The insulation shall be installed to completely cover the exterior walls and the underside of the roof areas.

The vapor retarder shall be toward the interior of the building. Joints in the vapor retarder shall be sealed by application of a continuous bead of sealant approved by the insulation manufacturer.

Seams, tears, and punctures in the vapor retarders shall be sealed promptly, and before the insulation is contaminated with moisture condensation.

Installing batt insulation.--Batt type insulation shall be installed in accordance with the manufacturer's recommendations and shall completely cover the area between the framing members. Insulation shall be sized to fit tightly between framing members without being doubled over or unnecessarily compressed. Openings shall not be covered.

Installation at electrical apparatus.--Insulation shall be kept a minimum of 75 mm clear of lighting fixtures, ballasts, motors, fans blowers, heaters, wiring components, and other heat producing devices.

Thermal insulation shall not surround conduits for No. 8 or larger conductors.

Thermal insulation shall not impair accessibility of devices that may require periodic servicing.

Damaged insulation.--All punctures and tears in the vapor retarder facing shall be sealed with pressure sensitive patching tape matching the facing.

12-7.02C LOOSE-FILL INSULATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and pneumatically placing loose-fill insulation in existing stud walls in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Descriptive data shall indicate the amount of loose fill insulation material required to completely fill the wall cavities and produce the resistance rating of R-5.3 $K \cdot m^2/W$ in the completed installation.

QUALITY ASSURANCE.--

Codes and standards.--All insulation shall have a flame-spread rating not to exceed 25 and a smoke density not to exceed 450 when tested in accordance with UBC Standard No. 8-1.

PART 2.- PRODUCTS

Insulation.--

Insulation shall be mineral fiber blowing wool consisting of fine glass fibers formed into resilient nodules with a stable thermosetting resin and shall conform to ASTM Designation: C 764, Type I.

PART 3.- EXECUTION

Preparation.--Access to the cavities in the stud walls shall be achieved by removing 35 mm to 75 mm diameter portions of interior wall surface above and below the fire stops. Holes shall be located to limit blowing in the vertical direction to 508 mm upward and 1.2 m downward.

Installation.--The loose fill insulation shall be placed by the double blow method using a swivel nozzle. The lower portion of the cavity shall be filled first and the upper portion last. The cavities shall be completely filled, horizontal surfaces leveled to a uniform thickness, lightly settled to uniform density, but not compacted.

Finish work.--All access holes shall be patched to match the existing surrounding surfaces.

The entire surface of walls that have been insulated and patched shall be painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

12-7.03 METAL ROOF AND SIDING

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing manufactured metal roof and siding panels, in accordance with the details shown on the plans and these special provisions.

Metal roof and siding system shall consist of underlayment, prefinished metal roof and siding panels, fasteners, sealants, and accessories and components, not mentioned, which are required for a complete, securely fastened and weathertight installation.

SYSTEM DESCRIPTION.--

Design Requirements.--The roof and siding system shall conform to the wind design requirements for uplift or outward pressures in accordance with Chapter 16 of the Uniform Building Code for the wind speed and exposure shown on the plans.

SUBMITTALS.--

Product Data.--Manufacturer's technical product data, installation instructions, and recommendations for each type of sheathing material shall be submitted for approval.

Product data shall include the manufacturer's name and a complete material description of all components of the metal sheathing system.

Samples.--Material samples shall include a 305 mm x 305 mm sample of the roofing and siding panels for each color to be installed and a sample of each anchor clip and fastening device.

A sample of each type of snow guard shall be submitted for approval.

Working Drawings.--Working drawings showing the layout and details of the roofing and siding system shall be submitted for approval.

Working drawings shall include the shape, size, thickness, and method of attachment for each component used in the work; the layout and spacing of fasteners; details of connections and closures; and details for expansion joints and weathertight joints.

Design calculations for the fastening system of the roof and wall panels with the substrate shown on the plans shall be submitted to verify compliance with the design requirements.

Working drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown. The Engineer's signature shall be original.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of compliance shall be furnished for the metal sheathing system in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, HANDLING AND STORAGE.--

Delivery and handling.--Metal panels shall be protected against damage and discoloration.

Storage.--Metal panels shall be stored above ground, with one end elevated for drainage and protected against standing water and condensation between adjacent surfaces.

PART 2.- PRODUCTS

MATERIALS.--

SHEET MATERIALS.--

Base metal.--

Base metal shall be cold formed, 0.71 mm (24-gage), galvanized sheet steel with G90 coating, conforming to ASTM Designation: A 446, Grade A except where a higher strength is required for performance, extra smooth, or cold formed aluminum-zinc alloy-coated, commercial quality, sheet steel with AZ55 coating conforming to ASTM Designation: A 792, Grade 40, extra smooth.

Configuration.--

Where shown on the plans metal roofing system shall be a batten system. Battens may be snap-on or integral to the metal panels. Panel edges at batten shall stand a minimum of 25 mm high. Battens shall be a minimum of 45 mm high and spaced not less than 305 mm nor more than 455 mm on center.

Where shown on the plans metal roofing and siding system shall be a standing seam system with standing seams a minimum of 45 mm high and spaced not less than 305 mm nor more than 455 mm on center.

METAL FINISHES.--

General--Coatings shall be applied before or after forming and fabricating panels, as required for maximum coating performance capability.

Colors or color matches shall be as shown on the plans or, if not otherwise shown, shall be as selected by the Engineer from the manufacturer's standard color palette.

Fluoropolymer coating.--

Finish shall be the manufacturer's standard Kynar coating with a baked on primer (0.005 mm) and a finish coat of 0.02 mm nominal for a total dry film thickness of approximately 0.025 mm nominal.

Interior finish shall consist of a 0.004 mm epoxy primer and a backer coat.

MISCELLANEOUS METAL SHAPES.--

Flashings.--

Flashings shall be formed from the same material, gage and in the same finish as the metal roofing and siding panels.

MISCELLANEOUS MATERIALS.--

Fastener clips.--

Fastener clips shall be noncorrosive, ferrous metal fasteners as recommended by the metal panel system manufacturer to resist the design loads.

Fasteners.--

Fasteners shall be as recommended by the metal panel system manufacturer. Sheet metal screws shall not be used except to fasten trim and flashings.

Underlayment.--

Underlayment shall be as recommended by the metal panel system manufacturer, but not less than 15-pound minimum asphalt impregnated fiber glass mat roofing felt.

Sealant and sealant tape.--

Sealant and sealant tape shall be as recommended by the panel system manufacturer.

Closures.--

Closures shall be rubber, neoprene, closed cell plastic or prefinished metal.

FABRICATION.--

General.--Unless otherwise shown on the plans, or specified herein, roof panels shall be fabricated in continuous lengths for the length of the roof, from ridge or peak to eaves, except such length shall not exceed the manufacturer's maximum production length.

Unless otherwise shown on the plans, or specified herein, siding panels shall be fabricated in continuous lengths for the height of the structure, from eaves to sill, except such length shall not exceed the manufacturer's maximum production length.

Flashings shall be fabricated in the longest practical lengths.

Roofing and siding panels shall be factory formed. Field formed panels are not acceptable.

PART 3.- EXECUTION

INSTALLATION.--

Underlayment.--The roof and siding panels shall be installed over underlayment. Underlayment shall be laid parallel to the eaves, shingle fashion with 152 mm edge laps and 305 mm end laps and shall be fastened as recommended by the metal roofing system manufacturer.

Roof and siding panels.--The roof and siding shall be installed and fastened in accordance with the details shown on the plans and the approved working drawings. Cutting and fitting shall present a neat and true appearance with exposed burrs removed. Openings through roof panels shall be cut square and shall be reinforced as recommended by the metal roofing system manufacturer.

Metal panels shall be adjusted in place and properly aligned for the detailed conditions before fastening. Panels shall not be warped, bowed or twisted. The surface finish on the panels shall not be cracked, blemished or otherwise damaged.

Fasteners shall not be driven through roof panels or batten covers.

Miscellaneous metal shapes.--Trim, fascia, flashings, gutters, downspouts, scuppers, caps, and other prefinished metal work shall be positioned to the correct alignment for each detailed condition. Metal work shall be securely attached to backing construction using fasteners at the spacing shown on approved working drawings. Prefinished metal to be installed over concrete, masonry or plaster shall be back-coated with asphaltic paint as recommended by the metal roofing system manufacturer.

Metal panels, trim, and other prefinished metal that are marred, punctured, incorrectly bent, or incorrectly installed will be considered damaged and shall be replaced with undamaged units.

The metal panel system shall be installed weathertight. Closures shall be tight fitting and shall be provided at the ends of panels, at the boundary of the roof, and as indicated on the approved working drawings.

CLEAN UP AND CLOSE OUT.--

Clean up.--Adjacent surfaces shall be protected during the roofing system installation and sealant work. Excess sealant shall be removed as the installation progresses.

Roof panels, molding, trim, and other prefinished metal surfaces shall be cleaned after installation as recommended by the manufacturer. Exposed cuts shall be touched-up with a matching durable primer and paint as recommended by the metal roofing system manufacturer.

Touch up.--Damaged paint surfaces shall be touched up by using an air dry touch up paint supplied by the metal roofing system manufacturer. Only a small brush shall be used for touching up. No spraying of touch up paint is to be performed.

Damaged units.--Panels and other components of the work which have been damaged or have deteriorated beyond successful repair shall be removed and replaced.

12-7.04 SHEET METAL FLASHING

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of fabricating, furnishing and installing sheet metal flashing in accordance with the details shown on the plans and these special provisions.

Sheet metal shall include metal flashings, counterflashings, straps, roof jacks, and screen type vents.

Alternatives.--Premolded roof flashings may be used in lieu of sheet metal flashings where shown on the plans.

QUALITY ASSURANCE.--

Codes and standards.--Sheet metal work shall in accordance with the requirements in the latest edition of the Sheet Metal and Air Conditioning Contractors National Association "Standard Practice in Architectural Sheet Metal Work."

PART 2.- PRODUCTS

MATERIALS.--

Galvanized sheet steel.--

Galvanized sheet steel shall conform to ASTM Designation: A 361, not less than 0.71 mm (24-gage), unless otherwise shown on the plans. Surfaces to be painted shall not have factory coatings on galvanizing that cannot be removed by paint thinner.

Sheet aluminum.--

Sheet aluminum shall be not less than 0.81 mm thick, mill finish, 3003-H14 alloy, conforming to ASTM Designation: B 209.

Sheet lead.--

Sheet lead shall be not less than 1.6 mm thick, made from chemical lead, conforming to ASTM Designation: B 29.

Premolded roof flashing.--

Premolded flashing shall be premolded neoprene or ethylene propylene diene monomer (EPDM) flashing, resistant to ozone and ultraviolet. Units shall have overlapping tab to flash the seam.

Hardware and fastenings.--

Hardware and fastening for premolded roof flashings shall be stainless steel.

Solder.--

Solder shall conform to ASTM Designation: B 32, Alloy Grade Sn50.

Soldering flux.--

Soldering flux shall be acid type, conforming to Federal Specification: O-F-506C, Type I, Form A.

Insect screen.--

Insect screen shall be industrial wire cloth and screen, medium grade, 18 mesh, 0.43 mm diameter, 1 mm openings, plain weave, galvanized steel conforming to ASTM Designation: E 437.

Lap joint sealant.--

Lap joint sealant for concealed locations shall be a non-drying butyl.

Flashing cement.--

Flashing cement shall be a bituminous plastic cement, asbestos free, conforming to ASTM Designation: D 4586, Type II.

Sealant.--

Sealant for exposed locations shall be a silicone sealant conforming to ASTM Designation: C 920.

Primer.--

Primer shall be as recommended by the sealant manufacturer.

Coal tar paint.--

Coal tar paint shall be coal-tar epoxy coating conforming to U.S. Corps of Engineers Specification: C-200 or Steel Structures Painting Council Paint Specification: SSPC-16-68T.

FABRICATION.--

General.--Sheet metal shall be assembled to Sheet Metal and Air Conditioning Contractors National Association Standards.

Sheet metal shall be formed to the sizes, shapes and dimensions shown on the plans or as specified herein with angles and lines straight, sharp and in true alignment. The number of joints shall be kept to a minimum.

Angle bends and folds for interlocking the metal shall be made with full regard for expansion and contraction to avoid buckling or fullness in the metal after it is installed.

Joints in sheet metal work shall be closed watertight unless slip joints are specifically required. Watertight joints shall be mechanically interlocked and then thoroughly soldered for metals other than aluminum. Watertight joints in aluminum or between aluminum and other metals shall be sealed with acrylic sealant.

Sheet metal joints to be soldered shall be cleaned with steel wool or other means, pre-tinned and soldered watertight.

All joints shall be wiped clean of flux after soldering. Acid flux shall be neutralized by washing the joints with sodium bicarbonate.

Flashings shall have a 45 degree drip return at bottom edges. Unless otherwise shown on the plans, counterflashing shall extend not less than 100 mm over roofing or other materials protected by the counterflashing and shall be arranged so that roofing or materials can be repaired without damage to the counterflashing. Where reglets are indicated, counterflashing shall be fastened by lead wedges or snap-in flashing.

PART 3.- EXECUTION

PREPARATION.--Surfaces to receive sheet metal shall be clean, smooth and free from defects.

PROTECTION.--Aluminum surfaces to be in contact with concrete, mortar, or dissimilar metals shall be given a heavy coat of coal tar paint.

INSTALLATION.--

Roof penetration flashings.--All pipes, ducts, vents and flues passing through roofs shall be made waterproof with flashings of storm collars or counterflashings.

Roof penetration flashings shall be fabricated from galvanized sheet steel, not less than 0.71 mm (24-gage). Size and shape shall be as shown on the plans.

On built-up roofing, 2 flashings shall be furnished for each pipe, vent or flue through roof. Flashings shall be constructed so that the lower flashing shall sit directly on the roof deck, with the top flashing set over it on top of the roof felts.

The lower flashing shall be galvanized sheet metal, 0.71 mm (24-gage), and extend 150 mm minimum from outside of the pipe in all directions and 38 mm above the top of the roofing.

The top flashing shall be galvanized sheet steel or sheet lead as shown on the plans.

Premolded roof flashings.--Premolded roof flashings shall be installed in accordance with the manufacturer's instructions.

SECTION 12-8. DOORS AND WINDOWS**12-8.01 HINGED DOORS**

GENERAL.--This work shall consist of furnishing and installing hinged doors and frames in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions for fire rated assemblies and a door schedule shall be submitted for approval. The door schedule shall include a description of the type, location and size of each door and frame.

PRODUCTS.--

Metal door.--

Metal door shall be flush, seamless steel door factory prepared and reinforced to receive hardware and having cold rolled stretcher leveled sheet steel face sheets not less than 1.2 mm thick (18-gage). Face sheets shall be bonded with thermosetting adhesive to rigid board honeycomb or precured foam core; or face sheets shall be welded to all parts of an assembled grid of cold formed pressed metal stiffeners and framing members located around edges, ends, openings and at all locations necessary to prevent buckling of face sheets. Seams shall be tack welded, filled and ground smooth. Bottom edge and internal stiffeners of grid type core shall have moisture vents. Welds on exposed surfaces shall be ground smooth. Louvered or glazed openings shall be provided where shown on the plans.

Where fire rated doors are required, doors shall be listed and labeled for the fire rating shown on the plans.

Door shall be cleaned and treated by the bonderized process or approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Glazing for doors.--

Glazing for doors shall be safety glass as specified under "Glazing" in Section 12-8, "Doors and Windows," of these special provisions. Glazing shall be not less than 5 mm thick.

Pressed metal frame.--

Pressed metal frame shall be not less than 1.5 mm thick (16-gage) sheet steel with integral stop, mitered corners, face welded and ground smooth corners. Frames shall be reinforced for all hardware and shall be cleaned and treated by the bonderized process or an approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Frames for fire rated doors shall be listed for the same rating shown on the plans for fire rated doors.

Sealants.--

Sealants shall be ultraviolet and ozone resistant, gun grade polysulfide or polyurethane, multicomponent, Federal Specification: TT-S-227.

EXECUTION.--

INSTALLATION.--Doors and frames shall be installed rigidly, securely, plumb and true and in such a manner that the doors operate freely without rubbing or binding. Clearance between frame and door shall be not more than 3 mm. The exterior frame shall be sealed weathertight.

Pressed metal frames shall be secured with clips and anchors as shown on the plans.

Fire rated assemblies shall be installed according to the manufacturer's recommendations.

Fire rated assemblies shall include doors, door frames, automatic smoke-actuated closers, self-closing mechanisms, panic hardware, wire glass, and fire rated louvers. Assemblies shall be approved by the California State Fire Marshal.

PAINTING.--Except for the primer application specified herein, doors and frames shall be cleaned, prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

12-8.02 SECTIONAL OVERHEAD DOORS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing sectional overhead doors in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, roughing-in diagram and installation instructions for each size and type of door shall be submitted for approval.

Manufacturer's descriptive data shall include door panel construction and material thickness, door track size and material thickness, counterbalance spring service life and motor operator specifications.

Materials list shall contain all items proposed to be furnished and installed under this section of these special provisions.

Working drawings shall show details of special components and installations which are not fully dimensioned in manufacturer's descriptive data.

QUALITY ASSURANCE.--

Single source.--Each sectional door shall be provided as a complete unit produced by one manufacturer, including frames, sections, bracket guides, tracks, counterbalance mechanisms, hardware, operators and installation accessories, to suit opening and head room available.

Wind loading.--Design and reinforce section overhead doors to withstand a 960 PA wind load with a midspan deflection not to exceed 1/120 span.

PART 2.- PRODUCTS

MANUFACTURERS.--

Available manufacturers.--Subject to compliance with the specifications, manufacturers offering products which may be incorporated into the work include, but are not limited to the following: Clopay Corp.; Overhead Door Corp.; Raynor Garage Doors.

STEEL SECTIONS.--

Door sections.--

Door sections shall be galvanized commercial quality steel sheets and a minimum of G60 zinc coating complying with ASTM Designation: A 525.

Face sheets shall be not less than 0.86mm (20-gage). Back sheet shall be not less than 0.45 mm (26-gage).

Sections shall be fabricated from a single sheet to provide sections not more than 610 mm high, and nominal 50 mm deep. Meeting horizontal edges shall be rolled to a continuous shiplap, rabbeted or keyed weather seal with a reinforcing flange return.

Intermediate and end stiles shall be 1.52 mm (16-gage) galvanized steel welded in place. Intermediate stiles shall be spaced at not more than 1220 mm on center.

Bottom section shall be reinforced with a continuous channel or angle conforming to the bottom section profile.

Insulation.--

Insulation shall be the manufacturer's glass fiber, polystyrene or polyurethane foam type insulation and have an R-Value not less than $1.4 \text{ K}\cdot\text{m}^2/\text{W}$.

Finish.--

Finish shall be the manufacturer's standard baked on polyester or epoxy prime and finish coats, applied to interior and exterior faces.

TRACKS, SUPPORTS AND ACCESSORIES.--**Door tracks.--**

Door tracks shall be the manufacturer's standard galvanized steel track system, sized for door size and weight, and designed for the clearances shown on the plans. Complete track assembly shall be provided, including brackets, bracing and reinforcing for rigid support of ball bearing roller guides, for required door type and size.

Track reinforcement and supports.--

Track reinforcement and supports shall be galvanized steel. Tracks shall be reinforced and supported as required for the size and weight of door to provide strength and rigidity, and to ensure against sag, sway and vibration during operation.

Door seals.--

Doors shall have perimeter gasket seals at head and jambs and seal shall have a replaceable vinyl or neoprene bottom seal.

Vision panels.--

Vision panels shall be door manufacturer's standard glazed opening with wire safety glass, metal frame and vinyl or neoprene glazing gasket for water tight construction. The approximate size shall be as shown on the plans.

Adjustable louvers.--

Adjustable louvers shall be factory fabricated units of extruded aluminum alloy not less than 2.0 mm thick or galvanized steel not less than 0.91 mm thick (20-gage) with standard "Z" type blades set in a continuous channel frame, with a 6 mm mesh galvanized bird-screen in a removable frame on the inside.

Blades shall have center pivot on 10 mm aluminum rods in stainless steel ball bearings in cadmium plated races.

Adjustable louvers shall be equipped with hand-hold fixed to the operating bar for easy adjustment with wingnut spring tension to lock louvers in desired position.

HARDWARE.--

General.--Hardware shall be heavy-duty, rust-resistant, with galvanized or cadmium-plated or stainless steel fasteners, to suit type of door.

Hinges.--

Heavy steel hinges shall be provided at each end stile and at intermediate stiles, per manufacturer's recommendations for size of door.

Rollers.--

Rollers shall be heavy-duty with steel ball bearings in case-hardened steel races, mounted to suit slope of track. Rollers shall have case-hardened tires.

COUNTERBALANCE MECHANISMS.--**Counterbalance spring.--**

The door shall have a torsion spring counterbalance on a continuous cross header shaft; the entire assembly shall be all-bearing mounted. The spring shall have a rated service life of not less than 25,000 cycles.

ELECTRIC DOOR OPERATORS.--

Door operator shall be heavy duty, commercial type. Motor shall be a 240-volt, single-phase, high starting torque motor with single reduction worm gear, completely housed and running in an oil bath. Motor shall be of sufficient capacity to raise and lower the door at speed of approximately 0.2 m per second.

Door operator and assembly shall be equipped with solenoid brake, limit switches for upper and lower limits of door travel, emergency hand chain with electrical interlock to break motor circuit when hand chain is engaged, 3-button operating station in a NEMA Type 4 enclosure, and a factory wired NEMA Type 1 control panel.

Control panel shall contain an instrument transformer, reversing magnetic contractor with overload relay, and all necessary control relays and other devices required for complete automatic operation of the door. Motor shall be removable for repair without affecting emergency operation. Motor shall be centermounted or sidemounted as shown on the plans.

Reversing door edge.--

Reversing door edge shall be an electrically or pneumatically operated safety device extending across the full width of the bottom of the door which shall cause the door to stop automatically and return to open position upon contact with any obstruction.

PART 3.- EXECUTION

INSTALLATION.--

General.--Door, track, and operating equipment, complete with necessary hardware, jamb and head mold stops, anchors, inserts, hangers, and equipment supports, shall be installed in accordance with the final drawings, manufacturer's installation instructions and these special provisions.

Vertical track assembly shall be fastened to framing at not less than 610 mm on center. Horizontal track shall be hung from structural overhead framing with angle or channel hangers, welded or bolted into place. Sway bracing, diagonal bracing, and reinforcing as required for rigid installation of track and door operating equipment.

12-8.03 WINDOWS

GENERAL.--This work shall consist of furnishing and installing windows in accordance with the details shown on the plans and these special provisions.

Windows shall be commercial (C) grade aluminum prime windows unless otherwise shown on the plans.

Windows shall meet the construction and performance requirements in Section 2 of ANSI/AAMA 101-88 and shall meet the C20 (Commercial) product designation unless otherwise shown on the plans.

Finish for windows shall be Architectural Class I, clear anodized finish meeting American Architectural Manufacturer's Association Standard 607 unless otherwise shown on the plans.

Glazing for windows shall be in accordance with the requirements specified under "Glazing" in Section 12-8, "Doors and Windows," of these special provisions.

CERTIFICATES OF COMPLIANCE.--Certificates of compliance shall be furnished for all windows in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions and schedule shall be submitted for approval.

Manufacturer's descriptive data and installation instructions shall show window elevations, plan views, full size sections, anchoring details to all substrates, anchors and hardware.

Installation schedule shall show location, size and type for each window.

PRODUCTS.--

Fixed windows.--

Fixed windows shall be non-operable glazed panel inserted into a frame to include muntins, glazing stops, and glazing accessories.

Horizontal sliding windows.--

Horizontal sliding windows shall be horizontal slide by windows with tightly contacting weatherstripped meeting stiles, self-lubricating rollers, glazing accessories, tubular sill, snap locks and push handle. Vents shall be screened.

Aluminum.--

Aluminum shall be extruded 6063-T5 aluminum alloy.

Screws, fasteners and window accessories.--

Screws, fasteners and window accessories shall be non-corrosive metals compatible with aluminum except guides and rollers may be vinyl and nylon respectively. Finish for locks, operators, strikes, keepers and other metal hardware shall match window finish.

Weatherstripping.--

Weatherstripping shall be continuous, replaceable type, wool pile mounted in metal or double runs of ultraviolet resistant neoprene or vinyl.

Vent screen.--

Vent screen shall be aluminum frame with 18 x 14 mesh aluminum screening and polyvinyl-chloride splines. Screen frames shall be removable from interior of building. Finish of screen frame shall match window finish.

Sealant.--

Sealant shall be single-component, solvent type acrylic, self-leveling, non-sag, conforming to Federal Specification: TT-S-230.

Tape.--

Tape shall be compatible with sealant; Pecora, "B-44 Extra-Seal;" Pittsburg Plate Glass, "Duribbon;" Protective Treatment, "PTU 606;" Tremco, "440 Tape;" or equal.

EXECUTION.--

FABRICATION.--Frame and sash shall be accurately machined and fitted to hairline joinery that develops the members. Joints shall be factory sealed weathertight.

Sash shall be removable from the interior only. Sash shall have concealed condensation weeps to the outside.

DELIVERY AND STORAGE.--Windows shall be delivered in original, unopened, unbroken containers, wrappings, or bags with labels bearing the brand name, name of manufacturer or supplier, standard of manufacture, and product description.

Windows and accessories shall be stored off the ground, kept dry, fully protected from weather and damage.

INSTALLATION.--Window units shall be set straight, level, plumb and in true alignment in prepared openings. Windows shall be centered in openings. Clearance between the window unit and the building framing shall be from 4 mm to 6 mm at the sides and 13 mm at the top. Ventilator sash shall be adjusted after glazing for easy, smooth and proper operation.

The installation shall be flashed and sealed weathertight.

All aluminum surfaces in contact with masonry, steel or other incompatible materials shall be isolated with pressure sensitive tape, zinc chromate primer, bituminous paint or such other material recommended by the window manufacturer and approved by the Engineer.

12-8.04 FINISH HARDWARE

GENERAL.--This work shall consist of furnishing and installing hardware items for doors in accordance with the details shown on the plans and these special provisions.

Hardware assemblies shall comply with the fire code and the disabled accessibility requirements indicated on the plans and specified in these special provisions.

SUBMITTALS.--Manufacturer's technical information and catalog cuts for each item of door hardware and a door hardware schedule shall be submitted for approval prior to installation.

Manufacturer's catalog cuts shall include catalog numbers, material, grade, type, size, function, design, quality and finish of hardware.

The door hardware schedule shall indicate the location and size of door opening, the door and frame material, and the size, style, finish and quantity of the hardware components required.

FINISHES.--Hardware shall be provided with standard US 26D metal plated finish.

KEYING INSTRUCTIONS.--New locks shall be compatible with the master key system of the existing facility and shall be keyed to the existing lock system in use.

Locks and cylinders shall be provided with six pin "O" cylinders and blank keys. Cylinders and blank keys shall be delivered to the Engineer for combining of cylinders and cutting of keys.

The Contractor shall provide cylinders for use during construction. Construction cylinders shall remain in place until permanent cylinders are installed. Construction cylinders shall remain the property of the Contractor.

Key bows shall be stamped "State of California" and "Do Not Duplicate."

PRODUCTS.--

GENERAL.--Door hardware equal in material, grade, type, size, function, design, quality and manufacture to that specified herein may be submitted for approval.

Butt hinges.--

Butt hinges shall be steel, 1 1/2-pair per door unless otherwise specified or shown on the plans. Nonremovable pins shall be provided at outswing exterior doors. Hinge size shall be 114 mm x 114 mm unless otherwise noted.

Standard weight hinges shall be:

Heavy weight hinges shall be:

Hager	BB 1168
McKinney	T4B 37869
Stanley	BB 168
or equal.	

Mortise locksets.--

Mortise locksets shall be steel case with 32 mm x 203 mm face plate and 70 mm backset. Door and frame preparation for mortise locksets shall conform to ANSI A115.1.

Lever operated lockset shall be:

Best	35H 6FW 15H
Falcon	LM521 DG
Schlage	L9453P x 06
or equal.	

Cylindrical locksets and privacy sets.--

Cylindrical locksets and privacy sets shall be steel chassis, 54 mm diameter, 70 mm backset. Door and frame preparation for cylindrical lockset and privacy sets shall conform to ANSI A115.1.

Lever operated lockset shall be:

Best	83K6 AB 9C
Schlage	D53PD RHO
Falcon	LY501 DG
or equal.	

Lever operated privacy set shall be:

Best	83K OL 9C
Falcon	LY301 DG
Schlage	D40S RHO
or equal.	

Door closers.--

Parallel arms for closers shall be installed at outswing exterior doors. Closers shall have sprayed finish to match other hardware on door.

Door closers shall be:

LCN	4040
Norton	85001
Dorma	7800
or equal.	

Kickplates.--

Kickplates shall be 254 mm in height x 51 mm less than door width x 1.52 mm (16-gage).

Kickplates shall be:

Builders Brass	37
Quality	48
Trimco	6000
or equal.	

Floor mounted stops.--

Floor mounted stops shall be dome type. The height of the stop shall be determined by the clearance required when a threshold is used or not used.

Stops for openings with thresholds shall be:

Builders Brass	8063
Quality	431
Trimco	1213
or equal.	

Wall bumpers.--

Wall bumpers base diameter shall be 64 mm with a 25 mm projection.

Bumpers shall be:

Builders Brass	WC9
Quality	302
Trimco	1272-1/4-CCS
or equal.	

Thresholds, rain drips and door shoes.--

Thresholds, rain drips and door shoes shall conform to the sizes and configurations shown on plans. Thresholds at door openings with accessibility requirements shall not exceed 13 mm in height.

Threshold, rain drip and door shoe manufacturers shall be Pemko, Reese, Zero, or equal.

Threshold bedding sealant.--

Threshold bedding sealant shall conform to Federal Specification: SS-C-153.

Weatherstrip.--

Weatherstrip shall conform to the sizes and shapes shown on plans. Assemblies shall be UL listed and shall be provided where shown on the plans or as specified in these special provisions.

Weatherstrip manufacturers shall be Pemko, Reese, Zero, or equal.

Door signs and name plates.--

Door signs and name plates shall be as specified under "Signs" in Section 12-10, "Specialties," of these special provisions.

EXECUTION.--

DOORS AND FRAMES.--Doors and frames shall be set square and plumb and be properly prepared before the installation of hardware.

INSTALLATION.--Hardware items shall be accurately fitted, securely applied, and adjusted and lubricated in accordance with the manufacturer's instructions. Installation shall provide proper operation without bind or excessive play.

Hinges shall be installed at equal spacing with the center of the end hinges not more than 244 mm from the top and bottom of the door. Locksets and privacy sets shall be 1024 mm from the finished floor. Kickplates shall be mounted on the push side of the doors, 25 mm clear of door edges.

Thresholds shall be set in a continuous bed of sealant material.

Door controls shall be set so that the effort required to operate doors with closers shall not exceed 3.9 kg maximum for exterior doors and 2.7 kg maximum for interior doors. The effort required to operate fire doors may be increased above the values shown for exterior and interior doors but shall not exceed 6.8 kg maximum.

Door stops located on concrete surfaces shall be fastened rigidly and securely in place with expansion anchoring devices. Door stops mounted elsewhere shall be securely attached with wood screws or expansion devices as required.

Backing shall be provided in wall framing at wall bumper locations.

The location and inscriptions for door signs and name plates shall be as shown on the plans.

Hardware, except hinges, shall be removed from surfaces to be painted before painting.

Upon completion of installation and adjustment, the Contractor shall deliver to the Engineer all dogging keys, closer valve keys, lock spanner wrenches, and other factory furnished installation aids, instructions and maintenance guides.

DOOR HARDWARE GROUPS AND SCHEDULE.--Hardware groups specified herein shall correspond to those shown on the plans:

GROUP 1

- 1 1/2-pair butt hinges
- 1 each lever operated mortise lockset
- 1 each closer
- 1 each floor mounted door stop
- 1 each kickplate
- 1 each threshold, rain drip and door shoe
- 1 each weatherstrip

GROUP 2

- 1 1/2-pair butt hinges
- 1 each lever operated cylindrical lockset
- 1 each kickplate
- 1 each floor mounted door stop
- 1 each weatherstrip

GROUP 3

- 1 1/2-pair butt hinges
- 1 each lever operated privacy set
- 1 each kickplate
- 1 each wall bumper

12-8.05 GLAZING

GENERAL.--This work shall consist of furnishing and installing glazing in accordance with the details shown on the plans and these special provisions.

Glazing shall consist of glass and acrylic sheets for windows, doors and other glazed openings.

All glass shall conform to ASTM Designation: C 1036 and the classifications specified herein and shall be clear glass except as noted.

All acrylic sheets shall conform to ASTM Designation: D 702, Type III, Grade 3.

Safety glass shall be furnished and installed at all locations designated in Consumer Product Safety Commission's Safety Standard For Architectural Glazing Materials 16 CFR 1201.

SUBMITTALS.--A detailed list of glazing materials including glass, sheet, sealants, tapes, setting blocks, shims, compression seals, and glazing channels shall be submitted for approval. The list shall include a schedule of the materials to be used at each location.

LABELS.--Each individual pane of heat strengthened or fully tempered glass shall bear an identification label in accordance with ASTM Designation: C 1048.

PRODUCTS.--

Wire glass.--

Wire glass shall be Type II, Class 1, Form 1, Mesh m1; 6 mm thick clear polished wire glass with diamond mesh.

Safety glass.--

Safety glass shall conform to Consumer Product Safety Commission Safety Standard For Architectural Glazing Materials: 16 CFR 1201, and ANSI Standard Z97.1 and shall be one of the following:

Tempered glass.--

Tempered glass shall conform to ASTM Designation: C 1048, Kind FT, Condition A, Type 1, Quality q4 or better.

Seals, caulks, putties, setting blocks, shims, tapes, compression seals, felt, spacers, and channels.--

Seals, caulks, putties, setting blocks, shims, tapes, compression seals, felt, spacers, and channels shall be top grade, commercial quality, as recommended by the glass or sheet manufacturer and shall conform to the requirements in the publications of the Flat Glass Marketing Association.

EXECUTION.--

INSTALLATION.--Glazing shall conform to the general conditions and applicable details in the publications of the Flat Glass Marketing Association.

Panes shall be bedded fully and evenly, set straight and square within panels in such a manner that the pane is entirely free of any contact with metal edges and surfaces.

For all panes on the exterior of the building, the glazing on both sides of window panes shall provide a watertight seal and watershed. Seals shall extend not more than 2 mm beyond the holding members. A void shall be left between the vertical edges of the panes and the glazing channel. Weep systems shall be provided to drain condensation to the outside.

Panes in assemblies using extruded gasket glazing shall be set in accordance with the assembly manufacturer's instructions using gaskets and stops supplied by the manufacturer.

Whenever welding or burning of metal is in progress within 4.6 m of glazing materials, a protective cover shall be provided over exposed surfaces.

REPLACEMENT AND CLEANING.--All broken or cracked glass and glass with scratches which reduce the strength shall be replaced before completion of the project.

Panes shall be kept clean of cement and plaster products, cleansers, sealants, tapes and all other foreign material that may cause discoloration, etching, staining, or surface blemishes to the materials.

Excess sealant left on the surface of the glass or surrounding materials shall be removed during the work life of the sealant.

Solvents and cleaning compounds shall be chemically compatible with materials, coatings and glazing compounds to remain. Cleaners shall not have abrasives that scratch or mar the surfaces.

All panes shall be cleaned just before the final inspection. All stains and defects shall be removed. Paint, dirt, stains, labels (except etched labels), and surplus glazing compound shall be removed without scratching or marring the surface of the panes or metal work.

SECTION 12-9. FINISHES

12-9.01 GYPSUM WALLBOARD

GENERAL.--This work shall consist of furnishing, installing and finishing gypsum wallboard in accordance with the details shown on the plans and these special provisions.

Where assembly fire ratings are indicated on the plans, construction shall provide the fire resistance in accordance with the applicable standards in the Fire Resistance Design Manual published by the Gypsum Association.

Wallboard backing for use in restroom areas shall be water-resistant gypsum backing board.

PRODUCTS.--

Gypsum wallboard.--

Gypsum wallboard shall conform to ASTM Designation: C 36.

Joint tape and joint and finishing compound.--

Joint tape and joint and finishing compound shall conform to ASTM Designation: C 475.

Corner beads, metal trim and control joints.--

Corner beads, metal trim and control joints shall be galvanized steel of standard manufacture.

Resilient metal channel.--

Resilient metal channel shall be galvanized sheet steel channels of standard manufacture for reducing sound transmission in wood frame partitions.

Fasteners.--

Fasteners shall be gypsum wallboard nails conforming to ASTM Designation: C 514 or steel drill screws conforming to ASTM Designation: C 1002.

EXECUTION.--

DELIVERY AND STORAGE.--Materials shall be delivered in original packages, containers or bundles bearing brand name, applicable standard of manufacture, and name of manufacturer or supplier and shall be kept dry and fully protected from weather and direct sunlight exposure. Gypsum wallboard shall be stacked flat with adequate support to prevent sagging or damage to edges, ends and surfaces.

INSTALLATION.--Wallboard panels to be installed on ceilings and soffits shall be installed with the long dimension of the panels perpendicular to the framing members. Wallboard panels to be installed on walls may be installed with the long dimension of the panels either parallel or perpendicular to the framing members. The direction of placing the panels shall be the same on any one wall or partition assembly.

Edges of wallboard panels shall be butted loosely together. All cut edges and ends shall be smoothed as needed for neat fitting joints.

All edges and ends of gypsum wallboard panels shall coincide with the framing members, except those edges and ends which are perpendicular to the framing members. End joints on ceiling and on the opposite sides of a partition assembly shall be staggered.

Except where closer spacings are shown on the plans, the spacing of fasteners shall not exceed the following:

Nails	175 mm
Screws	300 mm

Nails or Type W steel drill screws shall be used to fasten wallboard to wood framing. Except as shown on the plans, screws shall not be used in fire resistive assemblies.

Adhesives shall not be used for securing wallboard to framing.

Gypsum wallboard panels shown on the plans for shear wall sheathing or for fire resistive assemblies shall be fastened to all framing members. Gypsum wallboard panels at other locations and gypsum wallboard finish over plywood sheathed shear walls shall be fastened to all framing members except at the following locations:

At internal angles formed by ceiling and walls; ceiling panels shall be installed first with the fasteners terminating at a row 175 mm from the walls, except for walls parallel to ceiling framing. Wall panels shall butt the ceiling panels. The top row of wall panel fasteners shall terminate 200 mm from the ceiling.

At internal vertical angles formed by the walls; fasteners shall not be installed along the edge or end of the panel that is installed first. Fasteners shall be installed only along the edge or end of the panel that butts and overlaps the panel installed first.

Fasteners shall be located at least 10 mm from wallboard panel edges and ends. Nails shall penetrate into wood framing at least 30 mm. Screws shall penetrate into wood framing at least 20 mm. All metal fasteners shall be driven slightly below surface level without breaking the paper or fracturing the core.

Metal trim shall be installed at all free edges of panels, at locations where wallboard panels abut dissimilar materials and at locations shown on the plans. Corner beads shall be installed at external corners. Control joints shall be installed at the locations shown on the plans.

Joints between face panels, the internal angles formed by ceiling and walls and the internal vertical angles formed by walls shall be filled and finished with joint tape and at least 3 coats of joint compound. Tape in the corners shall be folded to conform to the angle of the corner. Tape at joints and corners shall be embedded in joint compound.

Dimples at nail and screw heads, dents, and voids or surface irregularities shall be patched with joint compound. Each patch shall consist of at least 3 coats and each coat shall be applied in a different direction.

Flanges of corner beads, control joints and trim shall be finished with a least 3 coats of joint compound.

Each coat of joint compound shall be feathered out onto the panel surface and shall be dry and lightly sanded before applying the next coat. The finished surfaces of joint compound at the panel joints, internal angles, patches and at the flanges of trim, corner beads and control joints shall be flat and true to the plane of the surrounding surfaces and shall be lightly sanded.

Good lighting of the work area shall be provided during the final application and sanding of the joint compound.

Gypsum wallboard used as backing boards for tile or rigid sheet wall covering or wainscoting shall be water resistant. Joints in backing board shall not be taped or filled and dimples at the fastener heads shall not be patched. Edges of cuts and holes in backing board shall be sealed with a primer or sealer that is compatible with the wall covering or wainscoting adhesive to be used.

Surfaces of wallboard to be textured shall receive an orange peel texture.

12-9.02 RUBBER STAIR STRIPS

GENERAL.--This work shall consist of furnishing and installing rubber stair strips in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions, and a color sample shall be submitted for approval.

PRODUCTS.--

Rubber stair strip.--

Rubber stair strip shall conform to California Standard Code Title 24, Section 2-3305

(R). Treads shall have a nominal thickness of 3 mm and shall have be a pebbly surface texture abrasive strip ribbons.

EXECUTION.--The rubber stair treads shall be installed in accordance with the manufacturer's instructions.

12-9.03 PAINTING

GENERAL.--This work shall consist of preparing surfaces to receive coatings, and furnishing and applying coatings, in accordance with the schedules and details shown on the plans, and these special provisions.

The coatings specified in this section are in addition to any factory finishes, shop priming, or surface treatment specified elsewhere in these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, a materials list, and color samples shall be submitted for approval.

Product descriptive data shall include product description, manufacturer's recommendations for product mixing, thinning, tinting, handling, site environmental requirements, product application and drying time.

Materials list shall include manufacturer's name, trade name, and product numbers for each type coating to be applied.

Color samples shall be manufacturer's color cards, approximately 50 mm x 75 mm, for each color of coating shown on the plans.

REGULATORY REQUIREMENTS.--Coatings and applications shall conform to the rules for control of volatile organic compound emissions adopted by the air quality control district in the air basin in which the coatings are applied.

SITE ENVIRONMENTAL REQUIREMENTS.--Coatings shall not be applied when the air temperature is below 10°C (20°C for varnishes) or when the relative humidity exceeds 75 percent.

The surface to be coated shall be maintained at a minimum temperature of 7°C for a period of 24 hours prior to, and 48 hours after the application of the coating. Heating facilities shall be provided when necessary.

Continuous ventilation shall be provided during application of the coatings.

A minimum lighting level of 865 lux, measured 1 m from the surface to be coated, shall be provided while surfaces are being prepared for coatings and during coating applications.

DELIVERY, STORAGE, AND HANDLING.--Products shall be delivered to the site in sealed, labeled containers and stored in a well ventilated area at an ambient air temperature of not less than 7°C. Container labeling shall include manufacturer's name, type of coating, trade name, color designation, drying time, and instructions for tinting, mixing, and thinning.

MAINTENANCE STOCK.--Upon completion of coating work, a full 3.8 liter container of each type and color of finish coat and stain used shall be delivered to the location at the project site designated by the Engineer. Containers shall be tightly sealed and labeled with color, texture, and room locations where used, in addition to the manufacturer's standard product label.

PRODUCTS.--

GENERAL.--The products shall be the best quality grade coatings of the specified types as regularly manufactured by nationally recognized paint and varnish manufacturers that have not less than 10 years experience in manufacturing paints and varnishes. Products that do not bear the manufacturer's identification as the best quality grade product shall not be used. Products for each coating system shall be by a single manufacturer and shall not contain lead type pigments.

Thinners, shellac, fillers, patching compounds, coloring tint, and other products required to achieve the specified finish shall be the manufacturer's best quality and shall be used as recommended.

EXECUTION.--

INSPECTION.--Surfaces to be coated at the jobsite shall be approved by the Engineer prior to the application of coatings. The Contractor shall notify the Engineer at least 3 working days prior to the application of coatings.

SURFACE PREPARATION.--Surfaces scheduled to be coated shall be prepared in accordance with the following, except that the surfaces not specified herein shall be prepared as recommended by the coating manufacturer.

GENERAL.--Hardware, cover plates, light fixture trim, and similar items shall be removed prior to preparing surfaces for coating. Following the application of the finish coating, the removed items shall be reinstalled in their original locations.

WOOD.--Oil and grease shall be removed by solvent wash. Mildew shall be removed by mildew wash. Surfaces to be coated shall be cleaned of all dirt, excess material, or filler by hand cleaning. Smooth surfaced wood shall be sanded lightly.

A sealer composed of equal parts of shellac and alcohol shall be spot applied to knots, sap, pitch, tar, creosote, and other bleeding substances.

After the application of the prime coat, all nail holes, cracks, open joints, dents, scars, and surface irregularities shall be filled, hand cleaned, and spot primed to provide smooth surfaces for the application of finish coats.

GALVANIZED METAL.--Oils, grease, and fabrication lubricants shall be removed by solvent wash. Surfaces shall be cleaned of remaining surface treatments by hand cleaning. New surfaces shall be roughened by hand cleaning or light abrasive blasting.

Abraded or corroded areas shall be hand cleaned and spot coated with one coat of vinyl wash pretreatment. Abraded or corroded areas on new surfaces not scheduled to be painted shall be cleaned by solvent wash, hand cleaned, and given 2 spot applications of zinc rich paint.

STEEL AND OTHER FERROUS METALS.--Oils, grease, and fabrication lubricants shall be removed by solvent wash. Dirt, water soluble chemicals, and similar surface contamination shall be removed by detergent wash or steam cleaning. Mill scale and rust shall be removed by hand cleaning or abrasive blasting.

ALUMINUM AND OTHER NON-FERROUS METALS.--Oils, grease, and fabrication lubricants shall be removed by solvent wash. Dirt, water soluble chemicals, and similar surface contamination shall be removed by detergent wash.

GYPSON BOARD.--Holes, cracks, and other surface imperfections shall be filled with joint compound or suitable filler prior to application of coatings. Taped joints and filled areas shall be hand sanded to remove excess joint compound and filler.

PREVIOUSLY COATED AND SHOP PRIMED SURFACES.--Dirt, oil, grease, or other surface contaminants shall be removed by water blasting, steam cleaning, or TSP wash. Minor surface imperfections shall be filled as required for new work. Mildew shall be removed by mildew wash. Chalking paint shall be removed by hand cleaning. The surfaces of existing hard or glossy coatings shall be abraded to dull the finish by hand cleaning or light abrasive blasting. Abrasive blasting shall not be used on wood or non-ferrous metal surfaces.

Chipped, peeling, blistered, or loose coatings shall be removed by hand cleaning, water blasting, or abrasive blasting. Bare areas shall be pretreated and primed as required for new work.

DEFINITIONS.--

DETERGENT WASH.--Removal of dirt and water soluble chemicals by scrubbing with a solution of detergent and water, and removal of all solution and residues with clean water.

HAND CLEANING.--Removal of dirt, loose rust, mill scale, excess base material, filler, aluminum oxide, chalking paint, peeling paint, or paint which is not firmly bonded to the surfaces by using hand or powered wire brushes, hand scraping tools, power grinders, or sandpaper and removal of all loose particles and dust prior to coating.

MILDEW WASH.--Removal of mildew by scrubbing with a solution of detergent, hypochlorite-type household bleach, and warm water, and removal of all solution and residues with clean water.

ABRASIVE BLASTING.--Removal of oil, grease, form release agents, paint, dirt, rust, mill scale, efflorescence, weak concrete, or laitance, by the use of airborne abrasives, and removal of loose particles, dust, and abrasives by blasting with clean air.

Abrasives shall be limited to clean dry sand, mineral grit, steel grit, or steel shot, and shall be graded to produce satisfactory results. Unwashed beach sand containing salt or silt shall not be used.

Abrasive blasting shall conform to the requirements of SSPC-SP6-85, Commercial Blast Cleaning, as defined in the Steel Structures Painting Council Manual.

Light abrasive blasting shall conform to the requirements of SSPC-SP7-85, Brush-Off Blast Cleaning, as defined in the Steel Structures Painting Council Manual.

SOLVENT WASH.--Removal of oil, grease, wax, dirt, or other foreign matter by using solvents, such as mineral spirits or xylol, or other approved cleaning compounds.

STEAM CLEANING.--Removal of oil, grease, dirt, rust, scale, or other foreign matter by using steam generated by commercial steam cleaning equipment, from a solution of water and steam cleaning compounds, and removal of all residues and cleaning compounds with clean water.

TSP WASH.--Removal of oil, grease, dirt, paint gloss, and other foreign matter by scrubbing with a solution of trisodium phosphate and warm water, and removal of all solution and residues with clean water.

WATER BLASTING.--High pressure, low volume water stream for removing dirt, light scale, chalking or peeling paint. Water blasting equipment shall produce not less than a 13 800 MPa minimum output pressure when used. Heated water shall not exceed 66°C. If a detergent solution is used, it shall be biodegradable and shall be removed from all surfaces with clean water.

PROTECTION.--The Contractor shall provide protective devices, such as tarps, screens or covers, as necessary to prevent damage to the work and to other property or persons from all cleaning and painting operations.

Paint or paint stains on surfaces not designated to be painted shall be removed by the Contractor at his expense and the original surface restored to the satisfaction of the Engineer.

APPLICATION.--

GENERAL.--Coatings shall be applied in accordance with the printed instructions and at the application rates recommended by the manufacturer to achieve the dry film thickness specified in these special provisions.

Mixing, thinning and tinting shall conform to the manufacturer's printed instructions. Thinning will be allowed only when recommended by the manufacturer.

Coatings shall be applied only when surfaces are dry and properly prepared.

Cleaning and painting shall be scheduled so that dust and other contaminants from the cleaning process will not fall on wet, newly coated surfaces.

Materials required to be coated shall have coatings applied to all exposed surfaces, including the tops and bottoms of metal doors and other surfaces not normally visible from eye level.

APPLICATION SURFACE FINISH.--Each coat shall be applied to a uniform finish. Finished surfaces shall be free of surface deviations and imperfections such as skips, cloudiness, spotting, holidays, laps, brush marks, runs, sags, curtains, ropiness, improper cutting in, overspray, drips, ridges, waves, and variations in color and texture.

Each application of a multiple application finish system shall closely resemble the final color coat, except each application shall provide enough contrast in shade to distinguish the separate applications.

WORK REQUIRED BETWEEN APPLICATIONS.--Each application of material shall be cured in accordance with the coating manufacturer's recommendations before applying the succeeding coating. Enamels and clear finishes shall be lightly sanded, dusted, and wiped clean between applications.

Stain blocking primer shall be spot applied whenever stains bleed through the previous application of a coating.

TIMING OF APPLICATIONS.--The first application of the specified coating system shall be applied prior to any deterioration of the newly prepared surface. Metal surfaces shall be prepared and prime coated the same day that cleaning of bare metal is performed. Additional prime coats shall be applied as soon as drying time of the preceding coat permits.

Metal surfaces shall be prime coated within 12 hours of application of vinyl wash pretreatment.

Shellac sealer shall be allowed to dry at least 12 hours before applying the next coat.

Drying time between applications of water borne coatings shall be at least 12 hours.

APPLICATION METHODS.--Coatings shall be applied by brush, roller or spray. Rollers shall be of a type which do not leave a stippled texture in the paint film. Extension handles for rollers shall not be greater than 2 m in length.

If spray methods are used, surface deviations and imperfections such as, overspray, thickness deviations, lap marks, and orange peel shall be considered as evidence that the work is unsatisfactory and the Contractor shall apply the remainder of the coating by brush or roller, as approved by the Engineer.

DRY FILM THICKNESS.--

Vinyl wash pretreatment	0.007 mm to 0.13 mm, maximum.
Bituminous paint	0.1 mm, minimum.
Other primers, undercoats, sealers, and coatings	As recommended by the manufacturer.

BACKPRIMING.--The first application of the specified coating system shall be applied to all wood surfaces (face, back, edges, and ends) of wood materials that are not factory coated, immediately upon delivery to the project site, except surfaces of interior finish woodwork that adjoin concrete or masonry shall be coated with one application of alkyd exterior wood primer before installation.

When clear coatings are required on millwork, trim, or paneling, varnish, reduced 25 percent by mineral spirits, shall be used for coating the back faces.

All primed metal surfaces in contact with concrete or concrete block exterior walls shall be coated with a bituminous paint on those surfaces in contact with the wall.

PATCHES IN PREVIOUSLY COATED SURFACES.--Where patches are made on surfaces of previously coated walls or ceilings, the entire surface to corners on every side of the patch shall be coated with a minimum of one application of the finish coat.

FINISHING MECHANICAL AND ELECTRICAL COMPONENTS.--Shop primed mechanical and electrical components shall be finish coated in accordance with the coating system entitled, "Shop Primed Steel." Louvers, grilles, covers, and access panels on mechanical and electrical components shall be removed and coated separately.

Interior surfaces of air ducts which are visible through grilles or louvers shall be coated with one application of flat black enamel, to limit of the sight line.

Exposed conduit, piping, and other mechanical and electrical components visible in public areas shall be painted.

Both sides and all surfaces, including edges and back of wood mounting panels for electrical and telephone equipment shall be finish coated before installing equipment.

CLEANING.--Upon completion of all operations, the coated surfaces shall be thoroughly cleaned of dust, dirt, grease, or other unsightly materials or substances.

Surfaces marred or damaged as a result of the Contractor's operations shall be repaired, at his expense, to match the condition of the surfaces prior to the beginning of the Contractor's operations.

COATING SYSTEMS.--The surfaces to be coated shall be as shown on the plans and as specified elsewhere in these special provisions. When a coating system is not shown or specified for a surface to be finish coated, the coating system to be used shall be as specified for the substrate material. The number of applications specified for each coating system listed herein is a minimum. Additional coats shall be applied if necessary to obtain a uniform color, texture, appearance, or required dry film thickness.

SYSTEM 1- ALUMINUM AND OTHER NON-FERROUS METALS.--

1 pretreat coat: vinyl wash pretreatment
1 prime coat: aluminum primer
2 finish coats: acrylic, exterior enamel, semi-gloss

SYSTEM 2- GALVANIZED METAL.--

1 pretreat coat: vinyl wash pretreatment
1 prime coat: galvanized metal primer
2 finish coats: acrylic, exterior enamel, semi-gloss

SYSTEM 3- GYPSUM BOARD.--

1 prime coat: PVA wall sealer
2 finish coats: acrylic, interior enamel, semi-gloss

SYSTEM 4- PREVIOUSLY COATED EXTERIOR SURFACES.--

1 prime coat : alkyd exterior enamel undercoat
2 finish coats: acrylic, exterior enamel, semi-gloss

SYSTEM 5- PREVIOUSLY COATED INTERIOR SURFACES.--

1 prime coat: alkyd interior wood primer
2 finish coats: acrylic, interior enamel, semi-gloss

SYSTEM 6- SHOP PRIMED STEEL.--

1 prime coat : red oxide ferrous metal primer
2 finish coats: alkyd, exterior enamel, semi-gloss

SYSTEM 7- STEEL AND OTHER FERROUS METALS.--

2 prime coats: red oxide ferrous metal primer
2 finish coats: alkyd, exterior enamel, semi-gloss

SYSTEM 8- WOOD, CLEAR FINISH.--

1 prime coat: polyurethane varnish, satin, reduced 25 percent by mineral spirits
2 finish coats: polyurethane varnish, satin

SYSTEM 9- WOOD, PAINTED.--

1 prime coat: alkyd, exterior wood primer
2 finish coats: acrylic, exterior enamel, semi-gloss

COLOR SCHEDULE.--Colors shall be as shown on the plans.

12-9.04 FIBERGLASS REINFORCED PLASTIC PANELS

GENERAL.--This work shall consist of furnishing and installing fiberglass reinforced plastic (FRP) panels and trim molding in accordance with details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions, and finish options shall be submitted for approval.

Product descriptive data shall show the manufacturer's name and shall indicate conformance to these special provisions.

Installation instructions shall show the FRP panel manufacturer's recommended method of installation.

Finish options shall show the manufacturer's standard color palette for FRP panels and trim molding. Color shall be as shown on the plans.

PRODUCTS.--

FRP panel.--

FRP panel shall be Class I flame-spread, minimum nominal thickness of 2 mm; Marlite, Class A/I FRP; Kemlite, Fire-X Glasbord; or equal.

Trim molding.--

Trim molding shall be manufacturer's standard vinyl molding with nailing flanges and a 9 mm deep channel of sufficient width to receive panels and sealant.

Adhesive and sealant.--

Adhesive and sealant shall be as recommended by the FRP panel manufacturer.

EXECUTION.--

INSTALLATION.--The FRP panels and trim molding shall be installed in accordance with the manufacturer's installation instructions.

Trim molding shall be nailed through the flange into solid wood backing. All nails shall be concealed by FRP panels in the completed installation. Trim shall be one continuous piece along each wall unless the wall length exceeds the manufacturer's standard trim length. If more than one piece is used on one wall, the pieces shall be approximately equal length, with no piece less than 1 m in length. All FRP panel edges shall be covered by a trim molding.

Panels shall be one continuous piece along each wall unless the wall length exceeds the manufacturer's standard panel length. If more than one panel piece is used on one wall, the pieces shall be approximately equal length, with no piece less than one meter in length.

CLEAN-UP.--Adjacent surfaces shall be protected from adhesive or sealant. Excess adhesive and sealant shall be removed as the installation progresses using a solvent or cleaning agent recommended by the FRP panel manufacturer.

SECTION 12-10. SPECIALTIES

12-10.01 LOUVERS

GENERAL.--This work consists of furnishing and installing louvers in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PRODUCTS.--

Louvers.--

Louvers shall be factory fabricated units of extruded aluminum alloy not less than 2 mm thick (12-gage) or galvanized steel sheet not less than 1.63 mm thick (16-gage) with standard "Z" type blades, and removable bronze 16 x 16 mesh insect screens mounted on the inside of the units.

Gravity units shall have blades center pivoted on a 10 mm diameter aluminum rod set in stainless steel ball bearings with cadmium plated races. Blades of gravity louvers shall be equipped with vinyl bulb seals on the edges.

Louvers shall have integral caulking strips and retaining beads.

The finish on louvers shall be baked on primer and fluorocarbon polymeric resin.

EXECUTION.--

INSTALLATION.--Louvers shall be installed in accordance with the manufacturer's instructions. The completed louver installation shall be weather tight.

12-10.02 METAL SIGNS

GENERAL.--This work shall consist of furnishing and installing metal signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, colors, graphics and fastening details shall be submitted for approval.

PRODUCTS.--

Signs.--

Signs shall be sheet steel, not less than 1.22 mm thick (18-gage) with a baked-on enamel coating.

Signs shall have a white background with contrasting red letters. Red letters shall be 50 mm minimum in height.

Fasteners.--

Fasteners shall be as recommended by the sign manufacturer.

EXECUTION.--Sign inscriptions shall read as shown on the plans.

Each sign shall be located as shown on the plans and shall be fastened in place with a minimum of 6 fasteners for each sign.

12-10.03 SIGNS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for sign materials, colors and graphics, and for fastening hardware and material shall be submitted for approval.

PART 2.- PRODUCTS

Plastic signs (permanent room identification).--

Plastic signs for permanent room identification for other than restrooms shall be scratch resistant, non-static, fire retardant, washable melamine laminate with a non-glare surface, not less than 3 mm thick. Letters and numbers shall be upper case Helvetica, 25 mm in height, 0.80 mm above and integral with sign material, accompanied by Grade 2 Braille.

Grade 2 Braille dots shall be 2.5 mm on centers in each cell with 5 mm space between cells. Dots shall be raised a minimum of 0.6 mm above the background.

Plastic sign (restroom).--

Plastic sign for restroom shall be not less than 6 mm acrylic plastic. Sign background shall be blue and shall conform to Federal Standard 595a, Color No. 15090. Male/female symbol and lettering shall be white and shall conform to Federal Standard 595a, Color No. 17886.

Accessible building entrance sign.--

Accessible building entrance sign shall be not less than 3 mm acrylic plastic, not less than 102 mm x 102 mm, with the international symbol of accessibility.

Accessible building entrance sign shall be pressure sensitive decal, not less than 102 mm x 102 mm with the international symbol of accessibility.

Sign background shall be blue and shall conform to Federal Standard 595a, Color No. 15090. Symbol and border shall be white and shall conform to Federal Standard 595a, Color No. 17886.

Metal sign (loft).--

Metal sign for loft shall be sheet steel, not less than 0.76 mm thick (22-gage), black enamel letters on a white enamel background. Sign size shall be 610 mm wide by 457 mm high with 64 mm minimum height letters.

Fastening hardware and material.--

Fastening hardware and material shall be as recommended by the sign manufacturer. Fasteners shall be noncorrosive.

PART 3.- EXECUTION

Inscription.--Except for loft, sign messages shall be as shown on the plans.

Metal loft sign shall read as follows:

**LOFT
LOAD LIMIT
125 LB./SQ.FT.**

Installation.--Plastic signs for room identification and restrooms shall be fastened or secured to clean, finished surfaces in accordance with the sign manufacturer's instructions. Signs shall be installed at a location and height as shown on the plans.

Metal signs shall be attached securely with galvanized or cadmium plated fasteners.

Fastening hardware and material shall be installed within the sign as shown on the plans.

12-10.04 FIRE EXTINGUISHERS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing fire extinguishers with mounting brackets in accordance with the details shown on the plans and these special provisions.

REFERENCES.--

General.--Fire Extinguishers shall conform to the requirements in National Fire Protection Association (NFPA) 10, "Portable Fire Extinguishers," and Title 19, California Code of Regulations, Division 1, Chapter 3.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

QUALITY ASSURANCE.--

Codes and standards.--Fire extinguishers shall be Underwriters Laboratories or Factory Mutual Laboratories approved for the type, rating and classification of extinguisher specified.

PART 2.- PRODUCTS

MANUFACTURER'S.--

Acceptable manufacturers.--Subject to contract compliance, manufacturers shall be J. L. Industries; Larsen's Manufacturing; Potter-Roemer; or equal.

COMPONENTS.--

Fire extinguisher.--

Fire extinguisher shall be fully charged, multi-purpose dry chemical type, with charge indicator, hose and nozzle, and attached service record tag. Fire extinguisher shall be of the capacity and type rating shown on the plans.

Mounting bracket.--

Mounting bracket shall be the manufacturer's standard painted, surface mounted type.

PART 3.- EXECUTION

INSTALLATION.--

General.--Fire extinguishers shall be installed in locations and at mounting heights indicated, or if not indicated, at heights to comply with applicable regulations of governing agencies.

Fire extinguisher mounting brackets shall be attached to structure, square and plumb, in accordance with the manufacturer's recommendations.

IDENTIFICATION.--

Bracket-mounted.--Extinguishers shall be identified with red letter decals spelling "FIRE EXTINGUISHER" applied to wall surface. Letter size, style and location as selected by the Engineer.

SERVICING.--

General.--Fire extinguishers shall be service, charged, and tagged not more than 5 days prior to contract acceptance.

12-10.05 FREE STANDING STEEL SHELVING

GENERAL.--This work shall consist of furnishing and installing free standing steel shelving in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions and standard color palette shall be submitted for approval. The color will be selected by the Engineer after the award of the contract.

PRODUCTS.--

Shelving.--

Shelving shall be factory fabricated steel shelves and supports capable of supporting loads of 1200 Pa of shelf area. Shelves shall not deflect more than 8 mm when subjected to the loads specified herein and shall show no permanent deflection after removal of such loads. Shelves shall be supported and attached by means of clips. Studs or bolts shall not be used. Shelves shall be adjustable in vertical increments of 75 mm or less. Shelving shall be of the approximate dimensions and number shown on the plans and shall have a baked enamel finish.

EXECUTION.--Free standing steel shelving shall be installed in accordance with the manufacturer's instructions.

12-10.06 TOILET ACCESSORIES

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and installing toilet accessories in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and installation instructions and details shall be submitted for approval.

PART 2.- PRODUCTS

Toilet tissue dispenser.--

Toilet tissue dispenser shall be dual roll, surface mounted, stainless steel with satin finish, approximately 150 mm x 290 mm x 150 mm deep. Dispenser shall utilize standard toilet tissue rolls. The top roll shall automatically drop into place after the bottom roll is depleted. One dispenser per toilet stall.

Clothes hook.--

Clothes hook shall be stainless steel clothes hook with 2 prongs.

Paper towel dispenser.--

Paper towel dispenser shall be white enameled sheet steel towel dispenser with a capacity of 1000 single fold paper towels. One dispenser per lavatory.

Liquid soap dispenser.--

Liquid soap dispenser shall be surface mounted, heavy duty plastic dispenser for industrial use with a capacity of at least 710 mL. One dispenser per lavatory.

Mirror, wall hung.--

Mirror, wall hung shall be Number 1 quality, 6 mm thick, electrolytically copper plated float or plate glass mirror with nonmoisture-absorbing filler. Mirror shall have a heavy gage galvanized steel back and stainless steel frame. The frame shall have a satin finish and shall be mitered and welded and the corners shall be ground smooth. Fasteners shall not penetrate surfaces of the frame exposed to view. Mirror shall conform to Federal Specification: DD-M-411b and shall be guaranteed against silver spoilage for not less than 10 years.

Steel grab bars.--

Steel grab bars shall be stainless steel, 38 mm diameter bars and escutcheon covered integral mounting flanges.

PART 3.- EXECUTION

Installation.--Toilet accessories shall be installed in accordance with the manufacturer's recommendations. Fasteners for mounting accessories shall be concealed and tamper proof.

Expansion anchors shall be used for mounting accessories on masonry or concrete walls.

Toilet accessories shall be mounted after painting work is complete.

All toilet room accessories shall be mounted plumb, secure and rigid. Grab bars shall be supported adequately so the bars will withstand an applied load of 113 kg at any point.

Support assembly for folding seat shall bear solidly on the wall without rocking and shall be fastened rigidly and securely to the wall in accordance with the manufacturer's recommendations.

SECTION 12-11. EQUIPMENT

12-11.01 LUBRICATION AND COMPRESSED AIR SYSTEMS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing lubrication and compressed air systems in accordance with the details shown on the plans and these special provisions.

The lubrication system shall include drum dollies; pneumatic pumps for dispensing chassis lubricant, motor oil, gear lubricant and hydraulic fluid; chassis lubricant hose; all outlet control valves and accessories.

The compressed air system shall include a compressor, regulators, gauges, compressed air piping and compressed air reel.

Pipes and fittings shall be in accordance with the requirements specified under "Pipes, Fittings, and Valves," in this Section 12-15, "Mechanical," of these special provisions.

Permits to operate.--Attention is directed to the latest Division of Industrial Safety (DIS) regulations regarding tank mounted air compressors.

The Contractor shall provide all permits to operate pressure vessels in accordance with the requirements of the DIS and shall pay all costs for such permits. Such permits shall be posted under glass at the work site.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data shall be submitted for approval.

Manufacturer's descriptive data shall include a complete description, performance data and installation instructions for the materials and equipment specified herein.

Performance data shall include the product delivery rate and discharge pressure for each type of pump assembly.

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be in a bound manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

WARRANTY.--

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

PART 2.- PRODUCTS

Chassis lubrication hose and control valve.--

The chassis lubricant hose and control valve shall have a 5 m nominal length, minimum 6 mm outside diameter, high pressure delivery hose. The delivery hose shall be rated for 34.5 Mpa working pressure and 137.9 MPa bursting pressure. The hose shall be Lincoln, 75240; Graco,109152, or equal.

Motor oil disperser.--

The motor oil disperser shall have a 16 quart metering shutoff valve assembly with totalizer, non-drip nozzle. The motor oil reel dispenser shall be Lincoln, 877; Graco, 238451; or equal.

Hydraulic dispenser.--

Hydraulic dispenser shall have a 16 quart metering shutoff valve assembly with totalizer and non-drip nozzle. The hydraulic fluid dispenser assembly shall be a Lincoln, 877; Graco, 238452; or equal.

Gear lubricant dispenser.--

Gear lubricant dispenser shall have a 4 pintt metering shut-off valve assembly with totalizer and non-drip nozzle. The gear lubricant dispenser shall be Lincoln, 878; Graco, 2384538; or equal.

PUMP ASSEMBLIES.--

General.--Pump assemblies shall be lubricant and oil type pump assemblies with air driven motors and shall be suitable for operation with stationary, exposed drums. Pump assemblies shall include pressure relief kits. Air connector hose shall be rated for 1720 kPa minimum working pressure. Product connector hose shall be as specified for the individual reel assembly. Pump assemblies shall produce the flowrates and pressures as specified under "Testing".

Chassis lubricant pump assembly and regulator.--

Chassis lubricant pump assembly shall be suitable for use with stationary, exposed 55 kg drums, complete with drum cover, air coupler and follower plate, and shall have a minimum pressure ratio of 45:1 and a maximum pressure ratio of 50:1. The regulator shall include a pressure gage supplied by the pump manufacturer and be compatible with the pump. The chassis lubricant pump assembly shall be Lincoln, 918; Graco, 225-014; or equal. The regulator shall be Lincoln, 82413; Graco, 109075; or equal.

Motor oil, hydraulic fluid and gear oil pump assemblies and regulator.--

Motor oil, hydraulic fluid and gear oil pump assemblies shall be suitable for use with stationary, exposed 205 liter drums and equipped with a bung bushing and an air expeller in the pump tube and shall have a 76 mm air motor. The motor oil pump assembly shall be equipped with a flow compensator. Pump assemblies shall be Lincoln, 424;Graco, 225-640; or equal. The regulator shall be Lincoln, 82413; Graco, 109075; or equal.

Compressed air reel assembly.--

Compressed air reel assembly shall have 15 m minimum length of 9.5 mm inside diameter delivery hose with heavy duty air gage control valve and with dual foot truck chuck. The air chuck shall have a 300 mm length of hose to an in-line valve and gage.

Compressed air reel assembly shall be Lincoln; Alemite; or equal.

MISCELLANEOUS COMPONENTS.--**Air compressor.--**

Air compressor shall be 2-stage, 1210 kPa design, 860 kPa output, mounted on an ASME code horizontal type receiver. The air compressor shall be complete with unloader, V-belt drive, belt guard, oil and air pressure gauges, automatic pressure controller, outlet valve, ASME relief valve, air intake filter, ball valve drain and an automatic tank drain operated by either the compressor unloader or a governor. Motor shall be high efficiency type, open dripproof with class B insulation. Air compressor shall be Champion, Ingersol Rand, Kellogg, or equal.

Pressure regulator.--

Pressure regulator shall be combination type with filter, bowl, pressure regulator and pressure gauge.

The filter bowl shall be the quick disconnect type, plastic with metal guard, manual drain, and 5 micron filter.

Pressure regulator shall be diaphragm controlled, balanced valve type, rated for 0 to 1100 kPa operation and shall be equipped with pressure gage, bottom clean-out plugs and internal strainers. Regulator shall be Wilkerson, Lincoln, Wabco, or equal.

Flexible coupling.--

Flexible coupling shall be brass flexible metal hose with threaded union ends and a minimum working pressure of 1380 kPa.

Pressure gage.--

Pressure gage shall be rotary type ANSI Standard: B40.1, Grade A, with 90 mm dial, liquid filled with cover, plain case, reset screw and bottom inlet. Pressure gage movement shall be phosphor bronze bushed. Gage shall read from 0 kPa to 1400 kPa. Each gage shall be equipped with a gage cock. Pressure gage shall be Marsh, Ashcroft, US Gage, or equal.

Drum dolly.--

Drum dolly shall have welded steel construction with a cross braced bottom and a 50 mm continuous perimeter lip, 4 ball bearing casters with steel or semi-steel wheels. Drum dolly shall be sized for 55 kg, drums or 205 liter drums as applicable.

PART 3.- EXECUTION

INSTALLATION.--

General.--The air hose reel shall be installed rigidly and securely to the reel mounting bracket. The mounting bracket shall be attached to the wall.

The recyclable oil storage tank and transfer pump shall be installed as shown on the plans.

Pipelines shall be cleaned and flushed immediately prior to connecting the control valves.

Pressure relief kits shall be installed on the discharge side of the recyclable oil, gear lube, hydraulic fluid and motor oil pumps as recommended by the pump manufacturer.

Air compressor shall be installed with drain piping, vibration isolation pads and expansion anchors.

Unions shall be installed before and after the pressure regulator/ball valve assembly.

Each pump assembly drum shall be supplied with a drum dolly.

Motor oil, hydraulic fluid and gear lubricant dispensing assemblies with accessories shall be delivered to the Engineer.

FIELD QUALITY CONTROL.--

Testing.--All tests, including general performance tests to demonstrate the proper operation of the lubrication systems and the air compressor, shall be performed by the Contractor in the presence of the Engineer.

The air compressor system shall be tested for the operational range, the cut-off pressure and the operation of air drops and system components.

The lubrication system, including hoses, shall be tested for leaks and the rates of delivery specified herein. The lubrication connections shall show no visible signs of leaks when the system is filled with the specified lubricant and tested at 1040 kPa lubricant pump inlet air pressure.

The Contractor shall demonstrate that the completed lubrication system will deliver the given product at the flowrate and discharge pressure specified by the pump assembly manufacturer. If no specification is given the lubricants shall be delivered at the following rates at 1040 kPa lubricant pump inlet air pressure:

Lubricant Material	Delivery Rate
Chassis lubricant NLGI No. 2 grease	0.7 liters per minute
Motor oil (10W/40)	7 liters per minute
Gear oil (85W/140)	6 liters per minute
Hydraulic fluid	8 liters per minute

The required delivery rate values may be adjusted, as determined by the Engineer, when testing for delivery rates with different materials or at temperatures other than 21°C.

The drums and lubricating material for testing the lubrication system will be State-furnished as provided under "State-Furnished Materials" in Section 8, "Materials," of these special provisions.

12-11.02 CLARIFIER TANK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a precast concrete clarifier tank in accordance with the details shown on the plans and these special provisions.

Pipes, fittings, devices, aprons, appurtenances, and other items or details, not mentioned, which are required for the construction and proper operation of the clarifier shall be furnished, placed, constructed, or installed as required.

Pipes, fittings and similar equipment shall conform to the applicable requirements in "Sanitary Sewer Disposal System," in Section 12-2 of these special provisions.

SUBMITTALS.--

Materials list.--Material list for material to be used shall be submitted for approval and shall include the name of the manufacturer and the source, model number, description, and standards of manufacturer.

Manufacturer's descriptive data and catalog cuts for manhole frames and covers, traffic frames and covers, and traffic frames and grates shall be submitted for approval.

Working drawings.--Working drawings and design calculations for the precast concrete tank used in the work shall be submitted for approval. The drawings and calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. Bedding, assembly, installation and backfilling instructions for the precast tank shall be submitted for approval.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of compliance shall be furnished for manhole covers and frames, traffic covers and frames and traffic grates and frames in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2.- PRODUCTS

MANUFACTURED UNITS.--

Precast tank.--

Precast concrete tank shall be precast, reinforced concrete tank by Nottingham, Cook Concrete Products (Redding), Bakersfield Precast Concrete, or equal. The design and details shall comply with the minimum requirements of the American Concrete Institute (ACI) 318 Code. Minimum concrete compressive strength (f'c) shall be 21 MPa. Tanks shall be designed to support the concrete slab over the tank, the truck loading shown on the plans and all loads and pressures resulting from the vertical and lateral earth loadings listed below:

1. Minimum earth cover over the tanks as shown on the plans.
2. Earth density: 1922 kilograms per cubic meter.
3. Equivalent fluid pressure for lateral pressure due to earth: 1436 Pa.

ACCESSORIES.--

Cast-in-place concrete and reinforcement.--

Cast-in-place concrete and reinforcement for collars shall conform to the requirements for minor work specified under "Cast-In-Place Concrete" in Section 12-3, "Concrete and Reinforcement," of these special provisions.

Cement mortar.--

Cement mortar shall consist of one part cement to 2 to 3 parts clean plaster or concrete sand mixed with just enough water for suitable consistency.

Epoxy mortar.--

Epoxy mortar shall be commercial quality, low viscosity paste polysulfide extended epoxy formulated primarily for use in bonding new portland cement concrete to old portland cement concrete.

Pea gravel backfill.--

Pea gravel for precast concrete tank backfill shall be clean aggregate, free from clay or organic material and graded such that 90 percent to 100 percent passes the No. 4 sieve size.

Backfill.--

Backfill, unless otherwise shown on the plans, shall be native material, free of rocks greater than 50 mm in greatest dimension, vegetable matter, trash or other deleterious material. The thickness of each layer of backfill before compaction shall not exceed 150 mm.

Sealant.--

Sealant for precast concrete tank shall be closed cell expanded neoprene conforming to ASTM Designation: D 1056, Grade RE 41.

Manholes.--

Manholes shall be precast, reinforced concrete manhole sections, conforming to ASTM Designation: C 478; or nonreinforced concrete pipe conforming to ASTM Designation: C 14; or precast reinforced concrete pipe conforming to ASTM Designation: C 76.

Manhole frames and covers.--

Manhole frames and covers shall be gray cast iron, conforming to ASTM Designation: A 48, Class 30 or greater (traffic type). Cover shall be no bolt, gas tight, closed pick hole, and shall be marked "SS," "SEWER," or "SANITARY SEWER." The side or bottom of the cover shall be machine grooved for an integral O-ring gasket. The frame seat for the bottom O-ring gasket shall be a minimum of 22 mm in width. The machine groove may be omitted and a flat gasket may be used, provided that the gasket is molded to the frame seat with contact cement.

PART 3.- EXECUTION**INSTALLATION.--**

General.--Manufactured precast clarifier tank and manhole frames and covers, traffic frames and covers, traffic frames and grates, and other appurtenances shall be installed in accordance with the manufacturer's recommendations and the approved working drawings.

FIELD QUALITY CONTROL.--

Testing.--The clarifier tank shall be tested for leakage by filling the tank with water to the level of the outflow line for a period of 24 hours. All seams and joints shall be left exposed (except the bottom of the tank) for inspection purposes. The tank shall remain watertight. Repairs, if necessary, shall be made at the Contractor's expense.

12-11.03 WORKBENCH**PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of furnishing and installing a workbench in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and standard color palette shall be submitted for approval.

PART 2.- PRODUCTS

Workbench.--

Workbench shall be standard, factory fabricated and factory painted heavy duty workbench unit with plywood reinforced steel top, drawers, curb and shelves. Plywood top reinforcement shall consist of two layers of securely fastened 19 mm thick exterior type plywood. The drawers, shelves and curb shall be as shown on the plans. Paint shall be an industrial grade enamel.

Leg anchors.--

Leg anchors shall be ICBO approved, integral stud type expansion anchors or internally threaded type anchors with independent stud.

PART 3.- EXECUTION

Installation.--The workbench shall be installed with the top level and the legs rigidly and securely fastened to the floor. Anchors for the legs shall be installed in accordance with the manufacturer's instructions.

SECTION 12-12. (BLANK)

SECTION 12-13. SPECIAL CONSTRUCTION

12-13.01 PRE-ENGINEERED STEEL BUILDING

GENERAL.--This work shall consist of designing, fabricating, furnishing and erecting a pre-engineered steel building in accordance with the details shown on the plans and these special provisions.

Pre-engineered steel building shall be of the rigid frame type with tapered or non-tapered columns and shall include structural steel framing, permanent lateral bracing, anchor bolts, base plate ties, fasteners, roof panels, wall panels, gutters and downdrains, sealants, doors, windows, louvers, insulation, ventilators, flashings, and such other parts, elements or components of the frame and outside walls and roof, not mentioned, which are required for the complete construction of a rigid, waterproof building.

The building dimensions shown on the plans are minimal and may be increased to accommodate manufacturer's standards. No additional compensation will be allowed for any changes required by such increased dimensions.

DESIGN CRITERIA.--The building and the building design shall be in accordance with the applicable requirements in the latest edition of the following publications: "Specification for the Design, Fabrication and Erection of Structural Steel for Buildings," published by AISC; "Specification for the Design of Cold-Formed Steel Structural Members," published by AISI; the "Metal Building Systems Manual," published by the Metal Building Manufacturers Association and the Uniform Building Code, including the modification to loads or stresses indicated therein.

The building shall be designed for simple erection with only bolted type field connections for framing.

The building shall be designed to support the weight of the building components, including overhead trolley and hoist and accessories, and the live load, wind load, seismic load, and other loads shown in the design notes on the plans. The design shall include wind and earthquake bracing, weathertight features, and reinforcement at openings for accessories.

Horizontal acting forces shall be applied parallel and perpendicular to the direction of the bents.

Diagonal rods or rigidly connected structural framing shall be used to resist lateral loads, except wall and roof panels may be used to resist lateral loads, provided that design calculations and laboratory test data, satisfactory to the Engineer, are submitted to substantiate their adequacy. Cables shall not be used for permanent lateral bracing.

The roof covering system shall be designed for an Underwriter Laboratory Class 60 minimum wind uplift rating.

Weathertight features of the design shall include closures and continuous seals at panel ends and sides, flashing, sealing, lapping of panels in the direction of prevailing winds, and seals under fastener heads.

SUBMITTALS.--Complete working drawings, erection instructions and drawings, design calculations, complete material descriptive information and manufacturer's standard color palette shall be submitted for approval. Submittals shall be approved prior to the start of fabrication.

Working drawings, erection drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown.

Working drawings shall show the size, thickness, shape, configuration, type, grade, class, description and coating, if any, of all materials used in the building. Joint details, connection and anchoring details and details of all temporary and permanent bracing shall be shown.

Calculations for the design of the building and the bracing shall include a list of applied loads and load combinations with the resulting member forces and member stresses. Maximum upward acting, downward acting and horizontal acting forces at the base of columns shall be included.

If the design calculations consist of computerized or tabulated calculations, the values pertaining to the building design for this project shall be identified, described or indexed in such a manner that a design check can be performed.

The manufacturer's color palette shall show the standard color line of baked polyester enamel coatings for building and accent colors. The colors shall be as shown on the plans. The colors will be selected by the Engineer after the award of the contract.

CERTIFICATES OF COMPLIANCE.--Certificates of Compliance shall be furnished for the pre-engineered steel building in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, STORAGE AND HANDLING.--The pre-engineered steel building components shall be transported and handled in such a manner as to prevent damage due to twisting, distortion or deformation. Building components shall be stored off the ground.

PRODUCTS.--

Primary and secondary steel framing members.--

Primary and secondary steel framing members shall be manufacturer's standards for the type, size and shape of building to be constructed. The minimum steel strength shall be as shown on the plans.

Roof panels.--

Roof panels shall be not less than 0.55 mm thick (26-gage), cold-formed, galvanized sheet steel with G90 coating, conforming to ASTM Designation: A 446M, Grade A. Panels shall have primary vertical ribs spaced at 300 mm maximum with 3 intermediate secondary ribs located between the primary ribs. The depth of the primary ribs shall be between 19 mm and 38 mm. The net minimum width of the panels shall be 600 mm. Each roof panel shall have an integral anti-siphon trough or break. Roof panels shall be continuous from ridge to eaves for all roof slopes 10.7 meters or less in length.

Wall panels.--

Wall panels shall be not less than 0.55 mm thick (26-gage), cold-formed, galvanized sheet steel with G90 coating, conforming to ASTM Designation: A 446M, Grade A. Wall panels shall be continuous from eaves or gables to sill except at wall openings.

Insulation.--

Insulation shall be as specified under "Insulation for Pre-engineered Steel Building" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

Fastener.--

Fasteners for the steel frame, roof panels, wall panels and accessories shall be the building manufacturer's standards and shall be of the size, type and spacing required by the design.

Sealant.--

Sealant shall be single component polysulfide or butyl conforming to Federal Specification: TT-S-230A and ASTM Designation: C 920. Sealant shall be clear, translucent or opaque white.

Backer rod.--

Backer rod shall be round, open cell polyurethane, sized such that it must be compressed between 25 and 75 percent of its uncompressed diameter when inserted in the joint.

Bituminous sealant.--

Bituminous sealant shall conform to Federal Specification: SS-C-153.

Louvers.--

Louvers shall be 50 mm deep Z shaped blades, brake formed from galvanized sheet steel 0.71 mm thick (24-gage), set in a continuous channel frame, with a 6 mm mesh bird screen in a removable frame on the inside.

Rib and flute closures.--

Rib and flute closures shall be ultraviolet and weather resistant rubber, neoprene or closed cell polyethylene.

Accessories.--**Hinged doors and frames, windows, overhead doors, and finish hardware.--**

Hinged doors and frames, windows, overhead doors, and finish hardware shall be as specified in Section 12-8, "Doors and Windows," of these special provisions.

Roof vents.--

Roof vents shall be building manufacturer's standard with operable damper and screen as shown on the plans.

Roof and wall jacks (flue and plumbing vents).--

Roof and wall jacks (flue and plumbing vents) shall be building manufacturer's standard galvanized sheet . The size and shape of the base assemblies shall be as required to the fit the profile of the roof and wall panels and the flues and vents.

Access door.--

Access door shall be building manufacturer's standard with frame, semi-concealed hinges and provisions for padlocking in the closed position.

Fascia, trim, coping, ridge cover, flashings, clips and miscellaneous support shapes.--

Fascia, trim, coping, ridge cover, flashings, clips and miscellaneous support shapes shall be building manufacturer's standards.

EXECUTION.--

FABRICATION.--Building frame components shall have all the bolt holes necessary for erecting, assembling and fastening made at the factory.

Bolt holes shall be either punched full size, drilled full size, subpunched and reamed, or subdrilled and reamed. The finished holes shall be cylindrical, perpendicular to the plane of the connection and shall be not more than 2 mm larger than the nominal diameter of the bolt. Mispunched or misdrilled holes shall not be corrected by welding unless approved by the Engineer.

FRAMING ERECTION.--Framing shall be erected plumb and true in accordance with the requirements of the AISC specifications and shall be secured rigidly in place in accordance with the details shown on the approved working drawings and the recommendations to the building manufacturer.

Anchor bolts for the framing columns and the lateral tie rods shall be cast into the foundation foundations.

Temporary bracing shall be installed during erection to hold the framing plumb and true and in a safe position until sufficient permanent bracing and construction is in place to provide full stability. All permanent bracing shall be secured in place before any sustained permanent loads are applied to the framing system. Bracing shall be positioned to clear electrical work and openings for accessories.

Openings for accessories shall be plumb and level, of the correct dimensions, located approximately where shown on the plans and reinforced to support the loads of the accessories.

Cutting, welding or altering of the framing members at the site shall not be allowed without written approval of the Engineer.

ROOF AND WALL PANEL INSTALLATION.--Roof and wall panels shall be installed in accordance with the manufacturer's recommendations.

Prior to the installation of the wall panels, the joint between the concrete and the wall base angle shall be waterproofed by fully bedding the angle in bituminous sealant.

Panels shall be adjusted to final position and brought to bear on the structural supports prior to fastening. Side laps shall be as recommended by the building manufacturer and shall be located over structural supports.

Cutting and fitting of the panels shall present a neat and true appearance with exposed burrs removed. Openings through the panels shall be cut square and shall be reinforced as recommended by the manufacturer.

Fasteners for panels shall be installed with an electric screwdriver equipped with a depth sensing nosepiece. Adjustment of the depth sensing nosepiece shall be checked prior to each day's use and when directed by the Engineer.

Isolation coatings shall be provided between surfaces of dissimilar metals.

Closures shall be installed and sealant shall be applied as recommended by the manufacturer to prevent weather penetration.

Roof and wall jacks for flues and vents and louvers shall be installed with the roof and wall panels and shall be weathertight.

The completed installation shall be without defacements, bends, sags, dimples, undulations, or other deformations; shall be free of vibration, rattles and noise due to wind or thermal movement; and shall be weathertight.

SEALING JOINTS.--Joints shall be sealed as shown on the plans. Sealant shall be applied in accordance with manufacturer's recommendations. Applications shall be a continuous operation for the length of the joint. Following the application of the sealant, the joint shall be tooled using a tool similar to that used to produce concave masonry joints. The joint shall remain undisturbed after tooling for not less than 48 hours.

PAINTING.--Surfaces of wall and roof sheathing panels and trim exposed to view shall be cleaned, treated by either the bonderizing or an approved phosphatizing process, given at least 2 applications of the polyester enamel finish paint, and then oven baked.

All surfaces of steel framing shall be cleaned and painted with 2 coats of primer at the factory. Two applications of the finish coating shall be applied to exposed surfaces of steel framing either at the factory or after erection. Cleaning and painting shall be in accordance with the requirements specified for steel and other ferrous metals under "Painting" in Section 12-9, "Finishes," of these special provisions.

After erection, all areas where the factory applied primer or finish coatings have been damaged or have deteriorated shall be thoroughly cleaned and spot painted. Spot painted areas of primer shall be approved prior to the application of the finish coats. Spot painting of the finish coating shall extend to edges, corners or other features that conceal the differences between new painting and shop applied coatings.

Other surfaces exposed to view, that are not coated at the factory, shall be coated. Cleaning and coating shall be in accordance with the requirements specified for the particular type of substrate material under "Painting" in Section 12-9, "Finishes," of these special provisions.

CLEAN-UP.--Sheathing panels, trim and other prefinished metal surfaces shall be cleaned after installation as recommended by the building manufacturer. Exposed cuts in sheathing panels shall be touched-up with a durable primer and paint as recommended by the building manufacturer.

SECTION 12-14. CONVEYING SYSTEMS

12-14.01 MOBILE VEHICLE LIFT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing an above ground, 4-post, mobile vehicle lift and accessories in accordance with these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for all equipment, including installation instructions, shall be submitted for approval.

Submittals shall include, but not necessarily be limited to the following:

Assembly Drawings
Dimensional Drawings
Control Schematic Diagrams
Wiring Diagrams
Test Report Certifying Compliance with ANSI Standard B153.1.

CLOSEOUT SUBMITTALS.--

Operations and maintenance manuals--Prior to completion of the contract, 3 identified copies of the operation and maintenance instructions for the vehicle lift shall be delivered to the Engineer at the jobsite. Manuals shall be bound and shall include the following:

Manufacturer's name
Name, address, and telephone number of factory authorized repair facility
Model and serial number
Service manual shall show:

Assembly drawings, parts list, and simplified system diagrams
Descriptions of all equipment and their basic operating features
Routine maintenance and service requirements
Troubleshooting and repair procedures
Accessories and their features and requirements

Inadequate or incomplete manuals will be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

QUALITY ASSURANCE.--

Manufacturer's qualifications.--The vehicle lift shall be furnished and installed by a manufacturer or authorized representative who has not less than 5 years experience in the manufacture and installation of this type of equipment and who maintains an authorized service representative within the State of California.

Codes and standards.--All work, including equipment, materials and installation, shall conform to the California Building Standards Code, Title 24; the California Code of Regulations, Title 8, Chapter 4, Division of Industrial Safety (DIS); and the American National Standards Institute, Inc. (ANSI) Standard B153.1.

The lift including all components necessary for operation shall be tested as a unit for conformance to ANSI Standard B153.1. Where strength factors are specified, actual load tests shall be performed and the results documented. Where component assembly is specified to a particular code or standard, a statement of compliance with that code or standard shall be included. All tests shall be performed by an independent testing laboratory recognized by the Occupational Safety and Health Administration (OSHA) under the Nationally Recognized Testing Laboratories (NRTL) Recognition Program, Office of Variance Determination.

WARRANTY.--

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

PART 2.- PRODUCTS

EQUIPMENT.--

Lift.--

Lift shall be comprised of four portable electrically operated components that are connected by electrical cable with at least one of the components having controls to operate all four components. Lift shall be an electromechanical device featuring a screw drive, support base and lifting fork to raise vehicles by their wheels. The lift shall include a fail-safe mechanical locking system at each component to secure the lift at all required height positions.

Lift shall be heavy duty type with a minimum rated capacity of 27 216 kg and a minimum lifting height of 1.6 meters measured from the finish floor to the bottom of the lifting fork.

Lifting speed shall be a minimum of 508 mm per minute.

Each portable component shall be driven by an open dripproof electric motor suitable for operation on 3-phase, 230-volt, and 60 Hz service. Electrical controls for all lift components shall be designed for complete synchronized automatic operation, such that all lifting forks shall have parallel and simultaneous movement when going up or down. All movement shall be stopped if the controls are unable to maintain synchronous motion. Electrical control shall be suitable for operation on the supply voltage.

ACCESSORIES.--

Wheel adapters.--

Wheel adapters shall be included to allow lifting of large trucks with tire sizes up to 24 R 22.5 and passenger automobiles with tire sizes down to P175 80 R 13.

High lift tripod.--

Each high lift tripod shall have a lift capacity of not less than 6804 kg. Coarse adjustment of height shall be mechanically assisted using either a spring, pneumatic, or hydraulic system which will permit adjustment of the coarse height by one person. Fine adjustment of height shall be accomplished with a screw drive similar to the one used for the lift. Height shall be adjustable from 1.4 to 2 meters. A total of 4 high lift tripods shall be supplied.

Cables.--

Provide all interconnecting cables necessary to operate the equipment. Provide a 10 meter long power cable suitably sized for the maximum current draw of the equipment. All cables shall come complete with quick disconnect plugs for connecting to each of the units. Power cable shall be provided with a quick disconnect plug for connecting to the power source. Manufacturer shall furnish a receptacle suitable for being hardwired to the electrical system which will mate with the power cable plug.

Information plate.--

Information plate with the following inscriptions shall be attached to the lift:

- Manufacturer's name and address
- Model number
- Serial number
- Lift capacity
- Date of installation
- Statement of compliance with ANSI B153.1

PART 3.- EXECUTION

INSTALLATION.--

General.--All equipment shall be installed in accordance with the vehicle lift manufacturer's recommendations and the applicable codes.

FIELD QUALITY CONTROL.--

TESTS.--

Acceptance tests.--Testing of the vehicle lift shall be conducted by the Contractor in the presence of the Engineer, using a State-furnished vehicle under various loads up to the maximum specified. If the lift malfunctions or a failure develops, the parts causing the failure shall be replaced or repaired and the test repeated until the vehicle lift performs satisfactorily. The electric motors shall not exceed the full load current as listed on the nameplate of the motor.

The Contractor shall notify the Engineer in writing not less than 5 days prior to the time that the testing is scheduled.

Manufacturer's field service.--The Contractor shall arrange for a manufacturer's authorized representative at the site of the work to supervise installation, check start-up, and train State personnel.

DEMONSTRATION.--

Training.--The Contractor shall arrange instruction and training for up to 6 State personnel on the operation and maintenance of the equipment. Training shall be scheduled with the Engineer to occur within 2 weeks of the installation of the hoist. Training shall include 8 hours of instruction on equipment operation and maintenance.

12-14.02 BRIDGE CRANE AND HOIST

PART 1.- GENERAL

SUMMARY.--

Scope.--This work consists of designing, constructing, furnishing and installing a 2700-kilogram electric bridge crane with an electric powered hoist on a motorized trolley, in accordance with the details shown on the plans, the requirements specified in these special provisions, and the recommendations and instructions of the hoist manufacturer.

The work shall also include the design, construction, furnishing and installation of the crane runway rails and the bridge girder for the trolley and hoist.

SYSTEM DESCRIPTION.--

Runway and girder design requirements.--The crane runway rails and the bridge girder(s) shall be designed to support the crane and hoist loads, including the required safety factors, as recommended by the crane and hoist manufacturer for the crane capacity specified herein and as recommended by the Materials Handling Institute Standard No. 74, "Top Running and Underhung Single Girder Electric Overhead Traveling Cranes," and as required by Title 24 of the California Building Standards Code, and Title 8 of the California Code of Regulations.

The crane runway rails shall be located as shown on the plans and shall be designed based on points of support at the primary structural support frames of the building. The approximate spacing of the structural steel support frames is as shown on the plans. The minimum vertical clearance shall be as shown on the plans.

The building structure and crane support beams have been designed to handle the bridge crane and rails.

The bridge girder(s) shall be designed for the span between the crane runways. The approximate length of span between the crane runways shall be as shown on the plans. Final span length shall be determined by the building manufacturer. The length of travel of the trolley at each end shall be determined by the Contractor and shall be the maximum that can be attained while maintaining adequate operating clearances between the crane assembly and any existing building support component or other appurtenance that would interfere with the proper installation and safe operation of the crane.

Before fabrication, the bridge crane and hoist manufacturer shall coordinate with the manufacturer of the pre-engineered steel building regarding span length, crane and hoist loads, runway rail support locations, and connection details.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, performance data, parts list and installation instructions for bridge crane and hoisting equipment shall be submitted for approval.

Working drawings.--Working drawings and design calculations for the runways rails and bridge girder(s) shall be submitted for approval.

Working drawings shall include control panel schematic and wiring diagram, and a listing of electrical equipment and devices to be furnished.

Working drawings and design calculations for the crane runways and bridge girder shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California.

CONTRACT CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be indexed and bound in a manual form and shall be complete and adequate for the

equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

QUALITY ASSURANCE.--

Certificate of Compliance.--Certificates of compliance shall be furnished for the crane runways and bridge girder(s) in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the General Conditions.

Codes and standards.--All welding shall be in accordance with the requirements in American Welding Society (AWS) D14.1, "Specifications for Welding Industrial and Mill Crane and Other Material Handling Equipment."

PART 2.- PRODUCTS

MANUFACTURERS.--

Acceptable manufacturers.--Subject to project conditions, bridge crane shall be CraneVeyor Corp.; Detroit Hoist; Lift-Tech International, Inc.; or equal.

MANUFACTURED UNITS.--

Bridge crane.--

General.--The electric bridge crane with a 2700-kilogram capacity shall include an electric powered hoist on a motorized trolley, power bar conductors, and pendant-type electrical controls.

The bridge crane shall be a 2700-kilogram capacity, motor driven, underhung, single or dual girder type crane. Bridge crane shall include bridge girder(s), end trucks, wheels, crane drive shaft, motor drive head, and drive motor. Bridge crane speed shall be 15 meters per minute.

The hoist and trolley shall be a 2700-kilogram, close headroom, wire rope or chain hoist mounted on a single-speed, electric motor driven trolley.

Crane control system shall consist of a bridge girder mounted control panel, festooned bridge conductor system, conductor bar system, travel limit switches, fully solid-state softstart for the bridge crane and trolley motors, and 7 button pendant station complete with strain relief hardware for full operation of hoist, trolley and bridge. Controls shall be actuated by the pendant station.

COMPONENTS.--

Bridge girder and trucks.--

Bridge girder(s) shall be fabricated from structural steel conforming to ASTM Designation: A 36, and shall have a maximum deflection of 1/600 of the span length under maximum loading conditions. The bridge girder shall be provided with travel stops.

The end trucks shall be designed to run on the lower flange of the runway rails and shall be constructed of welded structural steel shapes conforming to ASTM Designation: A 36. The end trucks shall be motorized and shall have not less than 4 forged steel wheels with sealed, tapered roller bearings.

The drive motor shall be a single gear driven motor with a common drive shaft or a dual drive motor system. The drive motor shall be rated for Class C Service, crane travel duty, and shall be reversible with motor brake. Horsepower, voltage and phase shall be as shown on the plans.

The crane drive shaft for single motor operation shall be supported on lubricated pillow blocks with precision ball bearings.

Hoist and trolley.--

The trolley shall be motorized and shall have not less than 4 hardened forged steel wheels with sealed, tapered roller bearings. The trolley frame shall be of rigid construction. The trolley operating speed shall be nominal 12 meter per

minute. The trolley motor shall be continuous duty, reversible, with motor brake. Horsepower, voltage and phase shall be as shown on the plans.

The hoist shall be oil bath gear driven flanged drum with machined grooves, mechanical type disc brake, heavy duty ball bearings, have a high limit switch for the hook travel, and shall be equipped with a load limiting clutch to prevent damage from overloads. Hook shall be forged steel, with 360 degree swivel and spring latch. The hoist motor shall be continuous duty, reversible, with motor brake. Hoist Duty Service Classification shall be H3. Horsepower, voltage and phase shall be as shown on the plans.

Runway rails.--

Runway rails shall include all beams, rails, and stiffeners required to span between primary framing members of the building. Runway rails shall be fabricated from structural steel conforming to ASTM Designation: A 36. The rails shall have a maximum deflection of 1/600 of the span length under maximum loading conditions. The runway rails shall be provided with travel stops.

Control panel.--

Control panel shall be UL or FM listed for crane operation and shall include main disconnect, mainline contactor, hoist motor disconnect, bridge motor disconnect, trolley motor disconnect, hoist motor reversing starter, bridge motor reversing starter, trolley motor reversing starter, thermal overload relays, control transformer disconnect, control transformer, control relays, power terminal block and control terminal block. All contactors and starters shall be NEMA rated. Components shall be mounted on the interior mounting panel.

Control panel shall be a NEMA 12 enclosure, with interior mounting panel and hinged exterior dead front door. Control panel shall be factory prewired in conformance with Class-II Type 1C wiring. All wires entering or leaving the control panel shall terminate on terminal blocks. Control wires shall be 7 strand No. 14 Type MTW wires. Wiring shall be arranged such that any component may be removed without removing any wiring except that component's leads.

Control panel shall be a complete system, routinely advertised, furnished by the bridge crane and hoist manufacturer.

Power and control cable.--

Power and control cable shall be as recommended by the bridge crane and hoist manufacturer.

Festooned bridge conductor system.--

Festooned bridge conductor system shall consist of multiconductor cable, cable grip, messenger chain, tag-line wire, 50 mm (inside diameter) conductor cable rings, take up brackets, 10 mm eye-bolts and other necessary hardware. Conductor sizes shall be as recommended by the hoist and trolley manufacturer.

Conductor bar system.--

Conductor bar system shall consist of enclosed power conductors, collectors and related covers, hangers, couplings and appurtenances. Conductor bar system shall be rated for 600 volts, 90 amperes continuous duty and 135 amperes intermittent duty. Conductor bars shall be one piece, copper conductors with thermoplastic insulating covers. End covers shall be provided. Collectors shall be spring loaded, replaceable shoe type rated for 50 meters per minute (minimum) travel.

FABRICATION.--

Shop finishing.--Bridge crane and hoist shall be cleaned and receive 2 coats of the manufacturer's standard paint.

Identification.--An information plate, with the following information, shall be attached to the bridge crane hoist and trolley.

- Manufacturer's name and address
- Model number
- Serial number
- Crane capacity
- Hoist capacity
- Date of installation

PART 3.- EXECUTION

INSTALLATION.--

General.--The bridge crane and hoist shall be installed in accordance with the manufacturer's instructions and the approved working drawings.

Crane runway sections shall be installed with couplings at joints to provide flush and level connections with a maximum gap between adjacent ends at the load-carrying flange not exceeding 2 mm except at free ends.

The bottom flanges of all crane runways shall be parallel and level with one another within a tolerance of plus or minus 6 mm throughout their entire length.

Hanger system should provide for vertical adjustment in order to properly adjust the elevation of the runway beam. After the runways are positioned vertically, a lateral antisway brace should be attached at each hanger location. In addition to the lateral antisway braces, longitudinal braces should be installed parallel to the runway beams to prevent sway along the length of the runway. These braces should be placed at approximately 30 meter intervals and at all turns in the runway.

The crane control panel shall be mounted on the crane bridge and shall be actuated from a pendant station, suspended 1.2 meters above the floor. Main power and trolley power shall be by festooned bridge conductor system and shall be installed along the bridge crane from the control panel to the conductor bar system and trolley motor.

Each soft start unit for the bridge and trolley motors shall be enclosed in a NEMA 12 enclosure and may be installed near the bridge or trolley motor.

Power and control cables shall be fastened to the structural members with one-hole steel straps at a spacing of not to exceed 0.9 meter on center.

Field painting.--After installation, damaged and abraded areas of the shop paint shall be repainted using the same materials as applied in the shop.

FIELD QUALITY CONTROL.--

Tests.--The bridge crane and hoist shall be tested in the presence of the Engineer. Any equipment failure or malfunction shall be corrected by the Contractor at his expense.

Tests shall be as described herein:

NO LOAD TEST.--The trolley and hoist shall be operated to throughout the full length of the crane runways and the limits of hook travel. Travel limit switches shall be engaged.

LOAD TEST.--The minimum test load shall be 125 percent of the rated load capacity. The trolley shall be operated for the full length of the crane runways under the test load. The test load shall be raised to the hook height limit and lowered until the cable is slack. After a 5-minute waiting period, the test load shall be raised one foot and held in that position, without slipping, for a minimum time period of ten minutes.

LOSS OF POWER TEST.--The main power switch shall be opened while the test load is being lowered. The test load shall stop completely and immediately when the power switch is opened.

Manufacturer's field service.--The Contractor shall arrange for the bridge crane manufacturer's representative to be present during testing.

SECTION 12-15. MECHANICAL

12-15.01 MECHANICAL WORK

GENERAL.--

Scope.--This work shall consist of performing mechanical work in accordance with the details shown on the plans and these special provisions.

Mechanical work shall include furnishing all labor, materials, equipment and services required for providing heating, ventilating, air conditioning, plumbing and liquefied petroleum gas (LPG) distribution systems.

Earthwork, foundations, sheet metal, painting, electrical, and such other work incidental and necessary to the proper installation and operation of the mechanical work shall be in accordance with the requirements specified for similar type work elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of pipes, ducts, etc., and location of equipment is to be governed by structural conditions and obstructions. Equipment requiring maintenance and inspection is to be readily accessible.

Roof penetrations shall be flashed and sealed watertight in accordance with the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for plumbing fixtures, and component layout shall be included where applicable.

Manufacturer's descriptive data shall be submitted for the following:

Access door	Gate valves
Air conditioning unit	Grilles
Air maintenance systems	Hose faucet
Alarm bell	Lavatory
Ball valves	Lavatory carrier
Check valve	Lavatory faucets
Compression stop	Low intensity radiant heating system
Cleanouts	Pipe insulation
Dry pipe valve	Register
Ductile iron pipe and fittings	Sprinkler heads
Electric wall heater	Thermostats
Electric water cooler	Time switches
Emergency shower and eyewash	Trap seal primer valve
Evaporative cooler	Unit heaters
Emergency shower and eyewash	Valve box
Evaporative cooler	Water closet
Exhaust fans	Water hammer arrestor
Fire department inlet connection	Water heater
Floor drains	Water meter
Flow indicator	

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be indexed and bound in a manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

Operation and maintenance manuals shall be submitted for the following equipment:

- Evaporative cooler
- Air conditioning unit
- Exhaust fans
- Radiant heating system components
- Electric water cooler
- Unit heaters

QUALITY ASSURANCE.--

Codes and standards.--Mechanical work, including equipment, materials and installation, shall conform to the California Building Standards Code, Title 24, and to the California Code of Regulations, Title 8, Chapter 4, Division of Industrial Safety (DIS).

WARRANTY.--

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

SYSTEM IDENTIFICATION.--

Piping, ducts, valves and equipment.--Identification of piping, ducts, valves and equipment shall be as shown on the plans or these special provisions:

Equipment.--All equipment shall be identified with a plastic laminated, engraved nameplate which bears the unit mark number as indicated on the drawings (for example, AC-4). Provide 13 mm high lettering, white on black background. Nameplates shall be permanently secured to the unit.

12-15.02 PIPE, FITTINGS AND VALVES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing pipes, fittings and valves in accordance with the details shown on the plans and these special provisions. Pipe, fittings and valves shall include such plumbing and piping accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the plumbing and piping systems.

All piping insulation and wrapping material shall be in accordance with the requirements specified under "Mechanical Insulation," in this Section 12-15.

The pipe sizes shown on the plans are nominal pipe size (NPS). No change in the pipe size shown on the plans shall be permitted without written permission from the Engineer.

The pipe and fitting classes and material descriptions shall be as specified herein. No change in class or description shall be permitted without written permission from the Engineer.

QUALITY ASSURANCE.--

Codes and standards.--Pipe, fittings and valves shall be installed in accordance with the requirements in the latest edition of the Uniform Plumbing Code, the manufacturer's recommendations and the requirements specified herein.

PART 2.- PRODUCTS

MATERIALS.--

PIPE AND FITTINGS --

Class Description

A1.--

Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with 1040 kPa galvanized malleable iron banded screwed fittings and galvanized steel couplings. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

- A2.--**
Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with black cast iron recessed drainage fittings. For rainwater leaders, neoprene-gasket compression couplings, Smith Blair, Dresser, or equal, may be used. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.
- A3.--**
Schedule 5 steel pipe conforming to ASTM Designation: A 135 with pressfit fittings and couplings for service as designated.
- A4.--**
Pipe and fittings shall be UL or FM listed, ferrous (Schedule 20 minimum) or copper (Type L minimum), suitable for the working pressure involved but not less than 1210 kPa. Pipe and fittings shall be in accordance with NFPA Code requirements.
- B1.--**
Schedule 40 black steel pipe conforming to ASTM Designation: A 53, with screwed fittings suitable for working pressure involved, but not less than 1210 kPa. Fittings shall be listed for fire protection.
- B2.--**
Schedule 40 black steel pipe conforming to ASTM Designation: A 53, with 1040 kPa black malleable iron banded screwed fittings and black steel couplings.
- Steel pipe coating, where required, shall be factory applied plastic. Pipe coating shall be Standard Pipe Protection, X-Tru-Coat (0.50 mm thick); Pipe Line Service Corporation, Republic; 3M Company, Scotchkote 205 (0.30 mm thick); or equal.
- C1.--**
Hub and plain end cast iron soil pipe with neoprene gaskets conforming to Cast Iron Soil Pipe Institute's Standard 301. Pipe, fittings and gaskets shall be of one manufacturer.
- C2.--**
Hubless cast iron soil pipe with neoprene gaskets, corrugated stainless steel shields and stainless steel clamps conforming to Cast Iron Soil Pipe Institute's Standard 301. Joint materials shall be furnished by pipe manufacturer.
- D1.--**
Ductile iron push on joint pipe conforming to AWWA Designation: C151. Fittings shall be push on ductile iron conforming to AWWA Designation: C153. Joints shall be rubber gasketed and designed for a working pressure of 2420 kPa. Pipe and fittings shall be supplied with bituminous outer coating and cement lining. Pipe shall be listed for fire protection.
- H1.--**
Type DWV hard copper tubing conforming to ASTM Designation: B 306, with DWV drainage fittings, stop type couplings and threaded adapters.
- H2.--**
Type K hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.
- H3.--**
Type L hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.
- P2.--**
Polyvinyl chloride (PVC) plastic pipe and fittings conforming to ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa working pressure at 23°C, National Sanitation Foundation approved. Pipe shall have bell ends conforming to ASTM Designation: D 3139 with triple edge rubber sealing ring. For pipe sizes NPS 2 diameter and smaller, plain end pipe with solvent welded fittings ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa may be used.

P3.--

Polyvinyl chloride (PVC) standard weight pipe and fittings, Schedule 40, conforming to ASTM Designation: D 1785. Pipe shall meet or exceed requirements of National Sanitation Foundation Standard No. 14. Pipe shall have bell ends conforming to ASTM Designation: D 2672. For pipe sizes NPS 3 and smaller, plain end pipe with solvent welded fittings conforming to ASTM Designation: D 2241, may be used.

P4.--

Polyvinyl chloride (PVC) plastic pipe and fittings shall conform to AWWA Designation: C900, class 150, Standard Dimension Ratio (SDR) 18. Pipe shall have bell end with a solid cross section elastomeric ring conforming to ASTM Designation: D 1869. Pipe shall be listed for fire protection.

Unions (for steel pipe).--

Unions (for steel pipe) shall be 1730 kPa, threaded malleable iron, ground joint, brass to iron seat, galvanized or black to match piping.

Unions (for copper or brass pipe).--

Unions (for copper or brass pipe) shall be 1040 kPa cast bronze, ground joint, bronze to bronze seat with silver brazing threadless ends or 860 kPa cast brass, ground joint, brass to brass seat with threaded ends.

Unions (for brass waste and flush pipes).--

Unions (for brass waste and flush pipes) shall be slip or flange joint unions with soft rubber or leather gaskets. Unions shall be placed on the fixture side of the traps.

Insulating union.--

Insulating union or flange as applicable shall be suitable for the service on which used. Connections shall be constructed such that the 2 pipes being connected are completely insulated from each other with no metal to metal contact. Insulating couplings shall not be used. Insulating union shall be F. H. Maloney; Central Plastics; EPCO; or equal.

Insulating connection (to hot water tanks).--

Insulating connection (to hot water tanks) shall be 150 mm minimum, flexible copper tubing with dielectric union at each end and designed to withstand a pressure of 1040 kPa and a temperature of 93°C.

VALVES.--

Gate valve (NPS 2 1/2 and smaller).--

Gate valve (NPS 2 1/2 and smaller) shall be bronze body and trim, removable bonnet and non rising stem, Class 125 and same size as pipe in which installed. Gate valve shall be Crane, 438; Nibco Scott, T-113; Jenkins, 370; or equal.

Gate valve in nonferrous water piping systems may be solder joint type with bronze body and trim. Valve shall be Kitz, 59; Nibco Scott, S-113; Jenkins, 1240; or equal.

Gate valve (NPS 3 and larger, below ground).--

Gate valve (NPS 3 and larger, below ground) shall be AWWA double disc, hub or rubber ring type, removable bonnet and non-rising stem, equipped with operating nuts, 1380 kPa working pressure, and Tee handle wrench for each valve. Valve shall be Mueller, A-2380; American Valve, Model 28; or equal.

Ball valve.--

Ball valve shall be two piece, minimum 2760 kPa WOG, bronze body and chrome plated or brass ball with full size port. Valve shall be Nibco Scott, T-580; Watts, B-6000; Kitz, 56; or equal.

LPG gas valve.--

LPG gas valve shall be listed, 1730 kPa (minimum) WOG bronze ball valve. Valve shall be Jenkins, Model 30-A; Crane, Accesso; Watts; or equal.

Automatic trap seal primer valve.--

Automatic trap seal primer valve shall be bronze body with removable operating parts and intergal vacuum breaker. Trap seal primer valve shall be designed for horizontal in-line installation and shall operate automatically on pressure fluctuation in the water supply. Valve shall be Josam, 88250; Zurn, Z-1022; Jonespec, 77250; or equal.

FAUCET.--

Hose faucet.--

Hose faucet shall be compression type, angle pattern, wall flange at exterior locations, tee handle, NPS 3/4 female thread with hose end, rough chrome or nickel plated finish for locations inside building, rough brass finish for others. Hose faucet shall be supplied with an integral or nonremovable threaded outlet vacuum breaker which meets the requirements of the American Society of Sanitary Engineering (ASSE) Standard: 1011. Hose faucet shall be Nibco, No. 63VB; Chicago, No. 15T; or equal.

CLEANOUTS.--

Cleanout through floor.--

Cleanout through floor shall have nonslip scoriated nickel bronze access plate and adjustable frame with square pattern top for ceramic tile and round pattern top for other finishes. Where floors are constructed with a membrane, access frame shall be provided with membrane clamping flange. Plug shall be countersunk brass or bronze with tapered threads. Cleanout shall be Wade, W-7000 Series; Smith, 4023 Series; Zurn, No. 1400; or equal.

Cleanout through floors in exterior locations shall be heavy duty, floating pipe type with cast iron cover. Cleanouts shall be Wade, No. W-8300-HF; Smith, No. 4253; Zurn, No. 1474; or equal.

Cleanout to grade.--

Cleanout to grade shall be cast iron ferrule type. Plug shall be countersunk brass or bronze with tapered threads. Cleanout to grade shall be Wade, No. W-8450; Smith, 4420; Zurn, No 1440; or equal.

MISCELLANEOUS ITEMS.--

Water hammer arrestor.--

Water hammer arrestor shall be stainless steel body with bellows or piston. Arrestor compression chambers shall be pneumatically charged. Water hammer arrestors shall be tested and certified in accordance with the Plumbing and Drainage Institute Standard: PDI-WH201 and sized as shown on the plans.

Access door.--

Access door shall be 1.52 mm prime coated steel, face mounting square frame, minimum 300 mm x 300 mm door with concealed hinge and screwdriver latch.

Compression stop (exposed).--

Compression stop (exposed) shall be metal full free waterway, angle type, ground joint union, non-rising stem, molded rubber seat and wheel handle.

Gas regulator.--

Gas regulator shall be listed as suitable for LPG and equipped with full capacity relief valve, low pressure safety shut-off and weatherproof and insect proof vent for outside installation. Capacity shall be as shown on the plans. Gas regulator shall be Fisher; Reliance; Rockwell; or equal.

Pipe hanger (for piping supported from overhead).--

Pipe hanger (for piping supported from overhead) shall be Grinnell, Model 269; Super Struct, C711; or equal.

Pipe wrapping tape and primer.--

Pipe wrapping tape shall be pressure sensitive polyvinyl chloride or pressure sensitive polyethylene tape having nominal thickness of 0.50 mm. Wrapping tape shall be Polyken, 922; Manville, Trantex VID-20; Scotchrap, 51; or equal.

Pipe wrapping primer shall be compatible with the pipe wrapping tape used.

Floor, wall, and ceiling plates.--

Floor, wall, and ceiling plates shall be chromium plated steel or plastic plates having screw or spring clamping devices and concealed hinges. Plates shall be sized to completely cover the hole.

Valve box.--

Valve box shall be traffic rated, precast high density concrete with polyethylene face and cast iron traffic rated cover marked "WATER," "GAS" or "CO-SS" as applicable. Extension shall be provided as required. Valve box shall be Christy; Brooks Products Company; Frazer; or equal.

Floor drain (in service bays).--

Floor drain (in service bays) shall be cast iron body with caulk or no hub bottom outlet, adjustable extension frame with NPS 10 heavy duty cast iron deep flange slotted grate. Floor drain shall be Zurn; Wade; T.R. Smith; or equal.

PART 3.- EXECUTION

INSTALLATION.--

INSTALLATION OF PIPES AND FITTINGS.--

Pipe and fittings.--Pipe and fittings shall be installed in accordance with the following designated uses:

Designated Use	Pipe and Fitting Class
Domestic water (CW and HW) in buildings	H3 or A1
Domestic water underground within 1.5 m of the building	A1 or H2
Domestic water underground 1.5 m beyond the building	P2, P3, P4, A1 or H2
Fire protection water, underground	B1,D1 or P4
Fire protection water riser	B1, D1 or H3
Fire protection sprinkler piping in building	A1, A3, A4 or B1
Sanitary drain piping above ground in building	H1, C1, or C2
Sanitary drain and vent piping underground within 1.5 m of the building	C1 or C2
Sanitary vent piping above ground in building	A2, H1, C1, or C2
Liquefied petroleum gas (LPG), 860 kPa or less, above ground	A1 or B2
LPG, 860 kPa or less, underground	B2 (plastic coated)
Compressed air	A1
Equipment drains and relief valve discharge	H3 or A1

Installing piping.--Water piping shall be installed generally level, free of traps and bends, and arranged to conform to the building requirements.

Piping installed underground shall be tested as specified elsewhere in these special provisions before backfilling.

Public use areas, offices, rest rooms, storage rooms in office areas, shall have concealed piping.

Warehouse rooms, equipment bays, and loft areas shall have exposed piping.

Piping shall not be run in floor fill, except as shown on the plans.

Piping shall be installed parallel to walls. All obstructions shall be cleared, headroom preserved and openings and passageways kept clear whether shown or not. Piping shall not interfere with other work.

Where pipes pass through exterior walls, a clear space around pipe shall be provided. Space shall be caulked water tight with silicone caulk.

Underground copper pipe shall have brazed joints. Underground plastic pipe shall be buried with No. 14 solid bare copper wire. Wire ends at pipe ends shall be brought up 200 mm and looped around pipe.

Exposed supply and drain piping in restrooms shall be chrome finished.

Compressed air piping shall be pitched to low point. Ball valved drips shall be provided at all low points. Branches shall be taken off top of main.

Gas piping shall not be installed under building concrete slabs or structure. An insulating connection and valve shall be installed above ground at each building supply.

Gas piping shall be pitched to equipment or to low point and provided with a 200 mm minimum dirt leg.

Forty-five degree bends shall be used where offsets are required in venting. Vent pipe headers shall be sloped to eliminate any water or condensation.

Vent piping shall extend a minimum of 200 mm above the roof.

Horizontal sanitary sewer and drain pipe inside buildings shall be installed on a uniform grade of not less than 2 percent unless shown otherwise on the plans.

Drainage pipe shall be run as straight as possible and shall have easy bends with long turns.

Wye fittings and 1/8 or 1/16 bends shall be used where possible. Long sweep bends and combination Wye and 1/8 bends may be used only for the connection of branch pipes to fixtures and on vertical runs of pipe.

Water pipe near sewers.--Water pipe shall not be installed below sewer pipe in the same trench or at any crossing, or below sewer pipe in parallel trenches less than 3 m apart.

When a water pipe crosses above a sewer pipe, a vertical separation of at least 300 mm between the top of the sewer and the bottom of the water pipe shall be maintained.

When water and sewer pipe is installed in the same trench, the water pipe shall be on a solid shelf at least 300 mm above the top of the sewer pipe and 300 mm to one side.

Pipe sleeves.--The Contractor shall provide sleeves, inserts and openings necessary for the installation of pipe, fittings and valves. Damage to surrounding surfaces shall be patched to match existing.

PVC pipe sleeves shall be provided where each pipe passes through concrete floors, footings, walls or ceilings. Inside diameter of sleeves shall be at least 20 mm larger than outside diameter of pipe. Sleeves shall be installed to provide at least 10 mm space all around pipe the full depth of concrete. Space between pipes and pipe sleeves shall be caulked watertight.

Cutting pipe.--All pipe shall be cut straight and true and the ends shall be reamed to the full inside diameter of the pipe after cutting.

Damaged pipe.--Pipe that is cracked, bent or otherwise damaged shall be removed from the work.

Pipe joints and connections.--Joints in threaded steel pipe shall be made with teflon tape or a pipe joint compound that is nonhardening and noncorrosive, placed on the pipe and not in the fittings.

The use of thread cement or caulking on threaded joints will not be permitted. Threaded joints shall be made tight. Long screw or other packed joints will not be permitted. Any leaky joints shall be remade with new material.

Exposed polished or enameled connections to fixtures or equipment shall be made with special care, showing no tool marks or threads.

Cleaning and closing pipe.--The interior of all pipe shall be cleaned before installation. All openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of any materials. The caps or plugs shall remain in place until their removal is necessary for completion of the installation.

Securing pipe.--Pipe in the buildings shall be held in place by iron hangers, supports, pipe rests, anchors, sway braces, guides or other special hangers. Material for hangers and supports shall be compatible with the piping or neoprene isolators shall be used. Allowances shall be made for expansion and contraction. Steel pipe shall have hangers or supports every 3 m. Copper pipe NPS 1 or smaller shall have hangers or supports every 2 m and sizes larger than NPS 1 shall have hangers or supports every 3 m. Plastic pipe shall have hangers or supports every 1 m. Cast iron soil pipe with neoprene gaskets shall be supported at each joint. Vertical pipes shall be supported with clamps or straps. Horizontal and vertical piping shall be securely supported and braced to prevent swaying, sagging or flexing of joints.

Hangers and supports.--Hangers and supports shall be selected to withstand all conditions of loading to which the piping and associated equipment may be subjected and within the manufacturer's load ratings. Hangers and supports shall be spaced and distributed so as to avoid load concentrations and to minimize the loading effect on the building structure.

Hangers and supports shall be sized to fit the outside diameter of pipe or pipe insulation. Hangers shall be removable from around pipe and shall have provisions for vertical adjustment after erection. Turnbuckles may be used.

Materials for holding pipe in place shall be compatible with piping material.

Hanger rods shall be provided with locknuts at all threaded connections. Hanger rods shall be sized as follows:

NPS Designator	Minimum Hanger Rod Diameter
1/2 to 2	10 mm
2 1/2 to 3 1/2	13 mm

Wrapping and coating steel pipe.--Steel pipe buried in the ground shall be wrapped or shall be plastic coated as specified herein:

1. Wrapped steel pipe shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
2. Tapes shall be tightly applied with 1/2 uniform lap, free from wrinkles and voids with approved wrapping machines and experienced operators to provide not less than 1.00 mm thickness.
3. Plastic coating on steel pipe shall be factory applied. Coating imperfections and damage shall be repaired to the satisfaction of the Engineer.
4. Field joints, fittings and valves for wrapped and plastic coated steel pipe shall be covered to provide continuous protection by puttying and double wrapping with 0.50 mm thick tape. Wrapping at joints shall extend a minimum of 150 mm over the adjacent pipe covering. Width of tape for wrapping fittings shall not exceed 50 mm. Adequate tension shall be applied so tape will conform closely to contours of fittings. Putty tape insulation compounds approved by the Engineer shall be used to fill voids and provide a smooth even surface for the application of the tape wrap.

Wrapped or coated pipe, fittings, and filed joints shall be approved by the Engineer after assembly. Piping shall be placed on temporary blocks to allow for inspection. Deficiencies shall be repaired to the satisfaction of the Engineer before backfilling or closing in.

Thrust blocks.--Thrust blocks shall be formed by pouring concrete between pipe and trench wall. Thrust blocks shall be sized and so placed as to take all thrusts created by maximum internal water pressure.

Plastic pipe underground shall be provided with thrust blocks and clamps at changes in direction of piping, connections or branches from mains NPS 2 and larger, and all capped connections.

Union.--Unions shall be installed where shown and at each threaded or soldered connection to equipment and tanks. Unions shall be located so piping can be easily disconnected for removal of equipment or tanks. Unions shall be omitted at compression stops.

Insulating union and insulating connection.--Insulating union and insulating connection shall be provided where shown and at the following locations:

1. In metallic water and gas service connections into each building; within 300 mm of building wall or slab penetration. Insulating connections shall be installed above ground and before shut-off valve. When the shut-off valve is installed below ground, insulating connection shall be installed above ground and after shut-off valve.
2. In water, gas and air service connections in ground at point where new metallic pipes connect to existing metallic pipes. Install valve box above insulating connection.
3. At points of connections of copper or steel water pipes to steel domestic water heaters and tanks.

Bonding at insulating connections.--Interior water piping and other interior piping that may be electrically energized and are connected with insulating connections shall be bonded in accordance with the National Electrical Code. Bonding shall all be coordinated with electrical work.

Compression stop.--Each fixture, including hose faucets, shall be equipped with a compression stop installed on water supply pipes to permit repairs without shutting off water mains. Ball valves may be installed where shown on the plans or otherwise permitted by the Engineer.

INSTALLATION OF VALVES.

Exterior valves.--Exterior valves located underground shall be installed in a valve box marked "Water." Extensions shall be provided as required.

INSTALLATION OF FAUCETS.

Hose faucet.--Faucets shall be installed with outlets 0.5 m above finished grade.

INSTALLATION OF CLEANOUTS.--

Cleanouts.--A concrete pad 0.5 m long and 100 mm thick shall be placed across the full width of trench under cleanout Wye or 1/8 bend. Cast iron soil pipe (C1 or C2) and fittings shall be used from Wye to surface. Required clearance around cleanouts shall be maintained.

Cleanout risers outside of a building installed in a surface other than concrete shall terminate in a cleanout to grade. Cleanout to grade shall terminate in a valve box with cover marked "CO-SS". Top of box shall be set flush with finished grade. Cleanout plug shall be 100 mm below grade and shall be located in the box to provide sufficient room for rodding.

Cleanout risers installed in tile and concrete floors, including building aprons and sidewalks, shall terminate in a cleanout through floor.

INSTALLATION OF MISCELLANEOUS ITEMS.--

Water hammer arrestor.--Water hammer arrestor shall be installed so that they are vertical and accessible for replacement. Water hammer arrestor shall be installed with access door when in walls or there is no access to ceiling crawl spaces. Access door location shall be where shown on the plans or as approved by the Engineer.

Gas appliance connection.--Gas valve and flexible connector shall be provided for gas piping at each appliance. Appropriately rated gas cocks may be used in NPS 1/2 gas pipe. Cock or valve shall be within 1 m of the appliance.

Gas regulator.--Gas regulator shall be installed complete with dirt leg, capped test tee, union, insulating union, gas valve and fittings.

Water meter.--Water meter shall be installed in horizontal piping run with no fittings located within 750 mm of either side of the meter.

Flushing completed systems.--All completed systems shall be flushed and blown out.

Chlorination.--The Contractor shall flush and chlorinate all domestic water piping and facilities with disinfecting solutions.

Calcium hypochlorite granules or tablets, if used, shall not be applied in the dry form, but shall first be dissolved into a solution before application.

The Contractor shall take adequate precautions in handling chlorine so as not to endanger workmen or damage materials. All pipes and fittings shall be completely filled with water containing a minimum of 50 ppm available chlorine. Each outlet in the system shall be opened and water run to waste until a strong chlorine test is obtained. The line shall then be closed and the chlorine solution allowed to remain in the system for a minimum of 24 hours so that the line shall contain no less than 25 ppm chlorine throughout. After the retention period, the system shall be drained, flushed and refilled with fresh water.

FIELD QUALITY CONTROL.--

Testing.--The Contractor shall test piping at completion of roughing in, before backfilling, and at other times as directed by the Engineer.

The system shall be tested as a single unit, or in sections as approved by the Engineer. The Contractor shall furnish necessary materials, test pumps, instruments and labor and notify the Engineer at least 3 working days in advance of testing. After testing, the Contractor shall repair all leaks and retest to determine that leaks have been stopped. Surplus water shall be disposed of after testing as directed by the Engineer.

The Contractor shall take precautions to prevent joints from drawing while pipes and appurtenances are being tested. The Contractor shall repair damage to pipes and appurtenances or to other structures resulting from or caused by tests.

General tests.--All piping shall be tested after assembly and prior to backfill, pipe wrapping, connecting fixtures, wrapping joints and covering the pipe. Systems shall show no loss in pressure or visible leaks.

The Contractor shall test systems according to the following schedule for a period of not less than 4 hours:

Test Schedule		
Piping System	Test Pressure	Test Media
Sanitary sewer and vent	250 mm head	Water
Water	860 kPa	Water
Gas	690 kPa	Air
Air	860 kPa	Air
Lubrication piping	860 kPa	Air and Product

During testing of water systems, valves shall be closed and pipeline filled with water. Provisions shall be made for release of air.

Sanitary sewers shall be cleared of obstructions before testing for leakage. The pipe shall be proved clear of obstructions by pulling an appropriate size inflatable plug through the pipe. The plug shall be moved slowly through the pipe with a tag line. The Contractor shall remove or repair any obstructions or irregularities.

12-15.03 MECHANICAL INSULATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing mechanical insulation in accordance with the details shown on the plans and these special provisions.

Piping insulation shall be installed on all domestic hot water piping, and on exterior above grade cold water piping, in non-conditioned spaces.

P-trap, hot water supply pipes and angle valves for lavatories and sinks, except in janitor closets or similar enclosed spaces, shall be insulated.

Duct external insulation shall be installed on rectangular ductwork installed in exterior locations.

QUALITY ASSURANCE.--

Codes and standards.--Mechanical insulation shall conform to California State Energy Commission regulations and, where applicable, shall meet American Society of Testing and Materials (ASTM) standards.

All materials shall bear the label of the Underwriters Laboratory (UL) or other approved testing laboratory indicating that the materials proposed for use conform to the required fire hazard ratings.

Pipe safety insulation shall conform to Section 1504(b) of Title 24, Part 5, California Plumbing Code.

PART 2.- PRODUCTS

MATERIAL.--

General.--All pipe insulation and wrapping material, including adhesives and jackets, located within buildings shall be certified to have a composite flame spread rating of not more than 25 and smoke development rating of not more than 450 when tested in accordance with ASTM Designation: E 84.

Duct insulation and wrapping material, including adhesives and jackets, located within buildings shall be certified to have a composite flame spread of not more than 25 and smoke development rating of not more than 50 when tested in accordance with ASTM Designation: E 84.

Piping insulation.--

Piping insulation shall be glass fiber molded pipe insulation with factory applied jacket suitable for service temperatures up to 175°C. Covering jacket shall have pressure sealing lap adhesive joints. Pipe insulation shall have a minimum thermal resistance of R-0.5 K•m²/W. Insulation and jackets shall be Owens-Corning, Fiberglass 25 with ASJ/SSL All Service Jacket; Manville, Micro-Lok 650ML with AP-T All Purpose Jacket; or equal.

Piping insulation cement.--

Insulation cement shall be Fenco, All Purpose Cement; Manville, JM375; or equal.

Alternative pipe insulation.--

Alternative pipe insulation shall be closed cell, elastomeric material in a flexible tubular form. Insulation shall have a service temperature range between -40°C and 93°C, a minimum vapor transmission rating of 0.29 Perm-m, and a minimum thermal resistance of R-0.5 K•m²/W.

Pipe safety insulation.--

Pipe safety insulation for P-traps, hot water supply pipes and angle valves shall be molded closed cell vinyl or closed cell foam with exterior vinyl surface. Pipe safety insulation shall be configured to protect against contact. Pipe safety insulation shall be Truebro Inc., Handi Lav-guard; Plumberex Specialty Products, Handy Shield; or equal.

External duct insulation.--

External duct insulation shall be 38 mm thick, 0.5 kg density glass-fiber blanket type. Material and coatings shall be fire resistive and shall be approved by the State Fire Marshal. External duct insulation shall be Fiberglas, Type PF-336; Ultralite, No. 100; Pittsburgh Plate Glass, Superfine; Johns-Manville, Microlite; Silvercote, Silvercel; or equal.

Adhesive.--

Adhesive shall be non-flammable type: Benjamin Foster Company, No. 85-20 Spark Safe; Goodloe E. Moore Company, Tuff Bond No. 6; Permacel, No. PA-310; 3M, No. 38 Insulation Adhesive; Swift's, No. 7228 brush type or No. 7336 spray type; Chicago Mastic, 17-461; or equal.

PART 3.- EXECUTION

INSTALLATION.--

General.--Insulation materials shall be neatly installed with smooth and even surfaces, jackets drawn tight and smoothly cemented down.

Insulation material shall not be installed until all pipes or surfaces to be covered are tested for leaks, cleaned and dried, and foreign materials, such as rust, have been removed.

Piping insulation.--Piping insulation shall be in accordance with the following, except that unions, unless integral with valves, and flexible connections shall not be insulated.

- a. Where insulation butts against flanges or is discontinued, insulation shall be tapered to pipe to allow for covering jacket to completely seal off end of insulation.

Insulation shall be extended on the valve bodies up to the valve bonnet.

Extend insulation continuous through pipe hangers and pipe sleeves. At hangers where pipe is supported, provide an insulated protection shield.

Insulating cement shall be applied to fittings, valves, and strainers and troweled smooth to thickness of adjacent covering. Strainer cleanout plugs shall remain accessible. Covers fabricated from molded pipe covering may be used in lieu of cement, provided covers are neat and well secured.

- b. Jacket flap shall be sealed down with factory applied self-sealing lap. Seams shall be lapped not less than 40 mm. Jacket shall be secured with aluminum bands installed at 300 mm centers.
- c. Exposed outdoor insulation shall have an additional 0.40 mm minimum thickness aluminum jacket applied over the completed insulation. The jacket shall have a factory applied moisture barrier and shall be Childers; Smith; or equal.

End joints shall be lapped with aluminum holding traps located directly over the lap. Additional aluminum holding straps shall be placed at 200 mm centers. Jacket at ells and tees shall be mitered, or premanufactured fitting jackets

shall be provided, with additional aluminum holding bands, as required. All joints shall be sealed watertight using silicon type, heat resistant sealant.

Alternate pipe insulation, where used, shall be installed on hot water piping before connections are made or the insulation may be slit lengthwise, applied to pipe and sealed with adhesive.

Pipe safety insulation.--Pipe safety insulation shall be installed in accordance with the manufacturer's recommendations.

Duct insulation.--Ragged edges shall be repaired or taped. Coverings shall be neatly finished at joints and edges. Each joint shall have a 50 mm minimum lap.

Insulation shall be flush with but not cover control devices, damper controls or access doors.

Before insulation is wrapped around concealed ducts, an adhesive shall be spot applied at a maximum of 100 mm centers on each side of the ducts to prevent sagging of the insulation. Insulation shall be wrapped entirely around the ducts and shall be wired securely in place with No. 16 copper clad wire, metal bands at least 10 mm wide or plastic ties. Supports shall be spaced a maximum of 300 mm on centers. Metal bands shall be installed with the use of a banding machine. Seams in the insulation shall be taped. Exterior galvanized steel jacket shall be 24 gage minimum.

The finished insulation covering shall be even and level and shall not contain humps.

12-15.04 AUTOMATIC FIRE SPRINKLER SYSTEM (DRY)

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of designing, furnishing and installing an automatic dry pipe type fire sprinkler system, complete and ready for use, in accordance with the details shown on the plans and these special provisions.

The automatic fire sprinkling system shall include a U.L. listed outside screw and yoke (OS&Y) valve, dry pipe accelerator, air maintenance system, electric alarm bell, dry pipe valve sprinkler heads and related appurtenances, valves, piping and fittings.

Rules and regulations.--The design of the sprinkler system shall be in accordance with the code requirements for ordinary hazard occupancies, group 2, and shall provide coverage of the building area shown on the plans.

The water pressure and flow rate shall be verified with the local agency having jurisdiction.

SUBMITTALS.--

Working drawings.--Complete working drawings, including written verification of the water pressure and flow rate, shall be submitted for approval.

State Fire Marshal approval.--Prior to the submittal of the working drawings, the Contractor shall have said drawings reviewed and stamped "APPROVED" by the State Fire Marshal.

QUALITY ASSURANCE.--

Codes and standards.--All work shall be in accordance with the requirements of the State Fire Marshal, the National Fire Protection Association (NFPA) Standard No. 13, 1994 Edition "Installation of Sprinkler Systems," and the requirements of other regulatory authorities having jurisdiction.

PART 2.- PRODUCTS

Water flow indicator.--

Water flow indicator shall be UL or FM listed for fire protection, vane type switch designed for wet pipe systems. Water flow indicator shall be designed for minimum flow rate of 40 liters per minute, and shall have an adjustable delay setting of from 0 to 90 seconds. Water flow indicator shall have double-pole double-throw contacts rated 5 amps at 120 V AC. Water flow indicator shall be Viking, Model VSR-D; Grinnell, Model F620; Reliable, Model A; or equal.

Check valve.--

Check valve shall be UL or FM listed for use in fire protection service applications, swing type, self draining, iron body with brass trim and rubber clapper with removable cover plate. Check valve shall be Viking, Grinnell, Groeniger, or equal.

Alarm bell.--

Alarm bell shall be UL or FM listed electric bell type, 120 volt AC. with a minimum sound rating of 95 decibels at 3 m. Alarm bell shall have a die cast aluminum housing with built-in rubber gasket for dust proof seal for bell striking mechanism. Alarm bell shall be Viking, Grinnell, Reliable, or equal.

Pipe and fittings.--

Pipe and fittings shall be in accordance with the requirements specified under "Pipe, Fittings and Valves," elsewhere in this Section 12-15.

Pipe and fittings for dry pipe drain lines shall be as recommended by the valve manufacturer.

Pipe hangers.--

Pipe hangers shall be of types listed as acceptable for specific applications in NFPA No. 13.

Valves.--

Valves shall be UL or FM listed, outside screw and yoke (OS&Y) rising stem type.

Valves (OS&Y) NPS 2 1/2 and larger in size shall be Crane, 467; Walworth, 8713F; Nibco Scott, F-607-0; or equal.

Valves (OS&Y) NPS 2 and smaller in size shall be Crane, 459; Walworth, 873; Nibco Scott, T-104-D; or equal.

Optional; Valves NPS 4 and larger may be butterfly type, UL or FM listed, working pressure 1210 kPa, gear operated, indicator flag, ductile iron body, bronze trim, with provisions for locking.

Compressed air supply.--

Compressed air supply sconnection shall consist of 2 control valves, check valve, relief valve and accessories, in accordance with the NFPA.

Dry pipe valve.--

Dry pipe valve shall be of the differential type with a differential ratio of 3 to 1. The dry pipe valve shall be protected against mechanical injury and shall be UL listed. The dry pipe valve shall be Grinnell; Viking; Reliable; or equal.

Air maintenance system.--

Air maintenance system shall include a pressure regulator, pressure relief valve, strainer, globe valve, angle valve, check valve, restriction and all othper pipe, fittings and appurtenancers necessary for the proper performance of the system. The air maintenance system shall be supplied as a pre-assembled package from the manufacturer or installed as individual components with all components supplied by a single manufacturer. The air maintenance system or all components of the system shall be ULlisted. The air maintenance system shall be Grinnell; Viking; Reliable; or equal.

Sprinkler head.--

Sprinkler head shall be upright type above ceiling and pendant type below ceiling. Sprinkler head shall be brass body, chemical or solder fusing type, with proper temperature rating element. Sprinkler head shall be listed dry type and shall be Glove, Grinnell, Reliable, or equal.

Spare sprinkler cabinet.--

Spare sprinkler cabinet shall be metal cabinet as recommended by the sprinkler head manufacturer and conforming to NFPA requirements. The cabinet shall be painted red.

Fire department connection.--

Fire department connection shall be UL or FM listed, horizontal double Siamese with double clapper, as required, with nominal size 2 1/2 inlets, drain cock, caps, chain, and brass nameplate. Inlets shall have national standard hose threads. The fire department connection shall be Potter-Roemer, Grinnell, or equal.

Accessories.--

Drains, test connection, flush connections, pressure gauges, and other accessories shall be supplied as required.

Sign.--

Sign shall be sheet steel, not less than 0.76 mm thick, with red letters on a white background and a baked enamel coating.

PART 3.- EXECUTION

INSTALLATION.--

General.--Sprinkler piping and equipment shall be installed in accordance with the approved working drawings and shall be located to avoid interference with the lighting system, access openings, or other piping.

Reductions in pipe size shall be made with one piece reduction fittings. Bushings shall not be used. Reducers shall be installed to connect smaller piping to alarm valve.

Piping.--Dry pipe fire sprinkler system shall have branch lines pitched 0.4% and mains pitched 0.2%.

Connection to the shop air supply system shall be installed where shown on the plans.

Drain piping and test connections shall discharge into the nearest floor drain or to the outside of the building. Discharge piping shall not drain across walkways.

Spare sprinkler cabinet.--The spare sprinkler cabinet shall be installed where temperatures will not exceed 38°C at any time. Such location shall be approved by the Engineer. Six spare sprinklers and 2 sprinkler head wrenches shall be furnished and placed in the cabinet.

Securing main shutoff valve.--A galvanized chain, with a nominal material diameter of at least 5 mm, shall be provided to lock the main shutoff in the open position. The lock will be State-furnished as provided under "State-Furnished Materials" in Section 8, "Materials," of these special provisions.

Signs.--Signs and messages shall be as required by NFPA No. 13 and the regulatory authorities having jurisdiction. Lettering shall be standard-type of the following heights:

Item	Minimum Lettering Height
Nameplate date	6 mm
Drain signs	19 mm
Tamper sign	19 mm

FIELD QUALITY CONTROL.--

Acceptance tests.--The Contractor shall arrange for testing of the automatic fire sprinkler system in the presence of the Engineer and the State Fire Marshal. Three days written notice of said testing shall be provided by the Contractor.

The system shall be pressure tested for 2 hours at 1380 kPa. A successful test shall have no visible leaks or loss of pressure.

The Contractor shall perform such other tests as may be required by the State Fire Marshal.

In addition to the hydrostatic test, an air pressure leakage test at 280 kPa shall be conducted for 24 hours. Any leakage that results in a loss of pressure in excess of 10 kPa for the 24 hours shall be corrected.

12-15.05 PLUMBING FIXTURES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing plumbing fixtures in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

General.--Plumbing fixtures shall be white in color and shall meet the following requirements:

Water closet (disabled accessible, 6 liters per flush, floor mounted with tank).--

Disabled accessible water closet shall be 6 liters per flush maximum, vitreous china, siphonable jet, 410 mm to 440 mm high elongated bowl, close coupled tank, floor mounted, with solid plastic open front elongated seat with check hinges. Water closet shall meet or exceed American Disabilities Act guidelines and ANSI Standards: A117.1 and A112.19.2. Closet and accessories shall be of the following types or equal:

	American Standard	Crane	Universal Rundle
Closet	“Cadet 17 EL1.6/PA” 2168.100 or 4086.800	"Hymont" 3-154E or 3-152 with3-655	“Atlas 1.5” UR 4078-341 or UR 4078-342
Seat	Church 5321.070	Olsonite 95	Benke 527

Lavatory (wall-mounted).--

Lavatory shall be vitreous china, with back, integral perforated grid drain, drilled for 102 mm centers, size 508 mm x 457 mm, with single extra long lever mixing faucet and chair carrier with concealed arms. Lavatory and accessories shall be of the following types or equal:

	Eljer	Crane	Kohler
Lavatory	"Lucerne" 0355.012	"Norwich" 1-194-V	"Greenwich" K-2032
Drain	--	C-1065-G or Moen 52659	K-7715
Supplies	Brass Craft FR1711C	C-1151 or Moen 52664	K-7605
Faucet	2385.130	Moen 8400	K-15592-5
Trap	NPS 1 1/4 chromium plated brass exposed bent tube adjustable 1.37 mm (17-gage) minimum thickness.		
Carrier	Concealed wall mounted carrier with leveling screws and locking devices; Zurn, J.R. Smith, Josam, Wade, Jonespec, or equal.		

Water heater (electric).--

Water heater shall be minimum capacity as shown on plans, designed for minimum 860 kPa, interlocking (non-simultaneous) or single element, glass lined, and equipped with magnesium anodes, cold water drop tube, high temperature energy shut-off device, valved drain, high density R-1.4 minimum foam insulation and finished with a steel jacket with baked enamel finish. Water heater shall meet the requirements of the California Energy Commission.

Water heater shall be equipped with an ASME labeled, tank mounted, pressure and temperature relief valve sized for maximum input.

Electric water cooler (disabled accessible, wall mounted).--

Electric water cooler shall be wall mounted, wheelchair accessible, and shall produce a minimum of 28 liters of 10°C water per hour based upon an inlet water temperature of 27°C and an ambient room temperature of 32°C. Cooler shall have self closing, front and side mounted pushbar actuators, shielded bubbler, automatic stream regulator, loose key stop, adjustable thermostat and cast brass P-trap.

Compressor shall be hermetically sealed, positive start with fan cooled condenser and shall be mounted above the cooler top. Cooler shall operate on 120 volts, 1 and shall be provided with 3-wire grounded plug and cord.

Electric water cooler shall be Haws, HWCA8D; Sunroc, HCWC-8S; Elkay, EHFS-8; or equal.

Emergency eyewash and shower.--

Emergency eyewash and shower shall be separate drench shower and eye bath, NPS 1 1/4 minimum, galvanized steel pipe stand with 229 mm floor mounting flange and equipped with 216 mm x 279 mm pictorial and worded emergency identification sign.

Shower head shall have a 254 mm diameter ABS plastic head with a stay-open ball valve operated by a rigid pullrod with triangular handle.

Eyewash shall have a 254 mm diameter stainless steel bowl, anti-surge heads and circular chrome plated spray ring to bathe the entire face, dust cover assembly for each head, and a stay-open ball valve operated by a flag handle. Eyewash unit shall be mounted on the shower pipe stand.

Emergency eyewash and shower shall be Haws, 8300; Speakman, SE-607; Western, 9221; or equal.

PART 3.- EXECUTION

INSTALLATION.--

General.--All finish for exposed metal on any fixture, including wall flanges, bolts, nuts and washer, shall be polished chrome plated.

Fixtures shall be sealed to wall or floor with silicone caulk bead.

All exposed metal surfaces on fixture supports shall be enameled to harmonize with fixtures.

Wall mounted fixtures shall be installed on concealed chair carriers designed to support weight of fixture from the floor, made for the specific fixture to be supported and for the particular installation conditions.

All fixtures shall be provided with accessible metal stop valves.

Hot water supply, trap and tailpiece on lavatories shall be wrapped with insulating material.

Flush valves for fixtures designated on the plans as disabled accessible shall be installed so that the valve handle is on the widest side of the toilet space.

FIXTURE MOUNTING HEIGHTS.--

General.--Unless otherwise noted, fixtures shall be mounted at the heights shown on the plans.

Water heater.--Water heater shall be installed with seismic restraints, inlet ball valve and insulating connections, and NPS 3/4 pressure and temperature relief drain pipe.

Emergency eyewash and shower.--Emergency eyewash and shower shall be installed with a rigid bracket located 1.2 m above the floor. Bracket shall be minimum 1.52 mm (16-gage) steel and shall be braced to the wall.

FIELD QUALITY CONTROL.--

Testing.--The Contractor shall test piping in accordance with the requirements specified elsewhere in these special provisions.

All installed fixtures shall be tested for proper operation after all plumbing work has been completed.

12-15.06 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS

PART 1.- GENERAL

Scope.--This work shall consist of furnishing, installing and testing heating, ventilating and air conditioning (HVAC) equipment and systems in accordance with the details shown on the plans and these special provisions.

The performance rating and electric service of the HVAC equipment shall be as shown on the plans.

Temperature controls.--Thermostats, relays, timer switches, and other sensor type control devices required for this work shall be furnished and installed by the supplier of the heating, ventilating and air conditioning equipment. All temperature control wiring shall be furnished and installed in accordance with the requirements specified in Section 12-16, "Electrical," of these special provisions.

Codes and standards.--Equipment and systems shall conform to California State Energy Commission Regulations and, where applicable, shall be American Refrigeration Institute (ARI), American Gas Association (AGA), Sheet Metal and Air Conditioning Contractors National Association, Inc. (SMACNA), and Air Movement and Control Association (AMCA) approved for performance ratings and application shown on the plans.

Any appliance for which there is a California standard established in the Appliance Efficiency Standards may be installed only if the manufacturer has certified to the Commission, as specified in those regulations, that the appliance complies with the applicable standards for that appliance. Space conditioning equipment may be installed only if the manufacturer has certified that the equipment meets or exceeds all applicable efficiency requirements listed in the Energy Efficiency Standards.

PART 2.- PRODUCTS

HEATING AND COOLING UNITS.--

Evaporative cooler.--

Evaporative cooler shall be a factory assembled unit having removable side panels with filters and a bottom drain. The cabinet shall be fabricated from galvanized steel sheet metal with a baked-on enamel finish. Interior surfaces of the cabinet bottom shall be asphalt coated. The drain fitting shall be threaded for connection to drain piping.

Evaporative cooler shall be installed with cold weather damper.

All parts of the float valve and recirculating pump, which come into contact with water, shall be of stainless steel or other corrosion resistant material.

The control switch shall be a 6-position switch with the following selective settings: cooling, fan only, high speed, low speed, pump only and off.

The evaporative cooler shall be McGraw-Edison; Fan-Air; Artic Circle; or equal.

Unit heater.--

Unit heater shall be gas-fired, propeller fan type, AGA approved for LPG and shall be equipped with aluminized steel heat exchanger, built in backdraft diverter, adjustable discharge louvers, gas pressure regulator, intermittent ignition device, gas main and pilot shutoff valves, automatic gas valve, high limit shutoff, 24-volt transformer, and fan motor local disconnect. All components shall be factory assembled. Unit heater for Resident Mechanic Facility shall be separated combustion high efficiency unit with factory supplied horizontal concentric venting system. Unit heater shall be Reznor; Modine; Hastings; or equal.

Unit heater fan motor shall have integral thermal overload protection.

Low intensity radiant heater.--

Low intensity radiant heater shall be positive pressure, two stage, and shall include power burner, radiant tube, reflector, exhaust pipe, vent cap, controls, hangers, and appurtenances as necessary for proper installation and operation. System shall be AGA certified and rated for LPG.

Burner shall be two stage, equipped with direct spark ignition, flame safety control and combustion chamber inspection sight glass.

All components of the system shall be supplied by the manufacturer of the burner.

Low intensity radiant heater controls shall consist of gas and burner controls, thermostats and time switches and shall be supplied by the radiant heater manufacturer.

Reflectors, hangers, supports and fasteners shall conform to the low intensity radiant heater manufacturer's recommendations.

Combination heating/cooling unit (single package through-the-wall)

Combination heating/cooling unit shall be through-the-wall mounted combination sealed combustion gas heater and electric air conditioner. The unit shall be AGA certified and rated for LPG operation. The unit shall include slide-out chassis design, adjustable discharge grilles, intermittent ignition with 100 percent safety pilot shut-off, multi-speed fan and be complete with plug.

Capacities and electric service shall be as indicated on the plans. Fan motor shall have integral thermal overload protection. Unit shall have low voltage remote thermostat.

Electric wall heater.--

Electric wall heater shall be forced air, recessed type, and shall be equipped with a grille and integral thermostat.

FANS AND VENTILATORS.--

Exhaust fan (through-the-wall in restroom)--

Exhaust fan shall be through-the-wall type, AMCA certified and shall be equipped with grille, backdraft damper, metal housing and wall cap with bird screen. Exhaust fan motor shall have integral thermal overload protection. Ceiling exhaust fan shall be Broan Model No. 512; Nutone, Model No. 8870; or equal.

Exhaust fan (wall mounted)--

Exhaust fan shall be wall mounted, AMCA certified and shall be equipped with grille, metal housing, backdraft damper, centrifugal fan wheel and bird screen. Fan motor and fan assembly shall be isolated from base with rubber vibration isolators. Fan shall be completely weatherproof and shall have a disconnect means under the hood and fan motor shall have integral thermal overload protection.

Declassification fan shall be constructed in accordance with the requirements of the latest of AMCA Publication 99, "Standards Handbook."

Declassification fan motor shall be 3-phase, continuous duty and explosion proof. Wall exhaust fan shall be Penn; Greeheck; Carnes; or equal.

HVAC CONTROLS.--

Unit heater thermostat.--

Unit heater thermostat shall be low voltage type, single set point range internally adjustable from 4°C to 27°C, and provided with a blank cover.

Thermostat (for heating/cooling unit)--

Thermostat shall be 24-volt, 7-day programmable, electronic heating/cooling thermostat, and shall be provided with sub-base selector switches for "AUTO-HEAT-OFF-COOL" and fan "AUTO-ON". Thermostat shall be auto-changeover type, and have full temperature range setback capacity. Thermostat shall be Robertshaw, Energy Manager 2; Harper-Wyman Company, Pro-Stat; Honeywell, Chronotherm 111; or equal.

Time switch (for unit heater)--

Time switch shall be double pole six hour range, spring-wound, "OFF" type time switch without a "HOLD" feature. Time switch contacts shall be rated 20 amps at 120 volts. Time switch shall be Intermatic, Type F60M; Tork, A500 Series; or equal.

AUXILIARY HVAC COMPONENTS.--

Unless specified herein, all components shall be sized and have the characteristics as shown on the plans.

Rigid ductwork.--

Rigid ductwork shall be galvanized steel sheet metal conforming to the latest edition of the SMACNA "Low Velocity Duct Construction Standards." Galvanized steel shall be cleaned by washing with mineral spirit solvent sufficient to remove any oil, grease or other materials foreign to the galvanized coating.

Duct supports.--

Duct supports shall be hot-dip galvanized steel.

Duct inlet grille.--

Duct inlet grille shall be heavy duty all steel construction, 18-gage minimum, 70 percent free area minimum with one set of horizontal fixed bars at zero degrees, 13 mm minimum spacing duct mounted. Duct inlet grille shall be Carnes; Tuttle and Bailey; or equal.

Supply register.--

Supply register shall be double-deflecting adjustable type, steel with oven baked-on enamel bone white finish or extruded aluminum, flanged frame with sponge or felt gasket; Hart and Cooley T62; Air Mate 240-HO or equal.

Volume damper.--

Volume damper shall be opposed blade type cold rolled steel painted, operable from face with screw driver or Allen-head wrench, shall be same manufacturer as diffuser or may be furnished as part of the diffuser.

Vents and flues (for heaters).--

Vents and flues for heaters shall be approved Type B.

Condensate drain piping.--

Condensate drain piping shall be rigid, Type L copper tubing with brazed solder fittings.

PART 3.- EXECUTION**INSTALLATION.--**

Heaters.--Unit heaters, radiant heaters and wall heaters shall be installed in such a manner as to insure adequate furnace clearance and separation of combustion air and circulating air. Appliances shall be connected to a rigidly mounted gas pipe supply system by an AGA approved flex connector and gas valve.

Radiant heaters shall be suspended by 7 mm minimum carbon steel chain and eye bolts. Heaters shall be angled to minimize heating of adjacent walls.

Evaporative cooler.--Wall mounted evaporative cooler shall be provided with drain piping routed to within 150 mm of the ground.

Mounting heights.--Thermostats and time switches shall be installed as shown on the plans.

Temperature controls.--Temperature control for unit and radiant heaters shall be provided by 2 low voltage thermostats and a time switch. One thermostat shall be set at 7°C. for low-limit temperature control and the second thermostat shall be set at 21°C. The first thermostat shall energize the heater whenever the temperature is below the setpoint. The second thermostat shall be wired in series with the time switch and shall de-energize the heater above the setpoint.

Vents and flues.--Vents and flues shall be securely fastened to the building construction, shall be provided with a thimble at the wall penetrations and shall terminate with a weather cap fabricated of the same material.

Access door.--Access doors shall be provided in rigid ducts and plenums for access to volume dampers, fire dampers and control devices located within such ductwork; and shall be provided at such other locations as shown on the plans.

Ducts and vents.--Ductwork within the building shall be installed to clear lighting fixtures, doors, windows and other obstructions. Ductwork shall preserve head room and shall keep openings and passageways clear whether shown on plans or not.

Ductwork shall be installed and braced according to the latest edition of the SMACNA "HVAC Duct Construction Standards."

Slopes in sides at transitions shall be approximately one to five. The ductwork system shall not contain abrupt changes or offsets of any kind unless otherwise shown on the plans.

Where ducts pass through walls, galvanized sheet metal or steel angle collars shall be installed around the ducts.

Duct sections shall be connected by beaded sleeve-type couplings using joint sealer as recommended by the duct manufacturer. Duct sections shall be mechanically fastened with pop rivets or sheet metal screws and sealed with mastic or insulated, reinforced silver tape.

Flexible connections shall be provided at both inlet and outlet of ventilating units.

All standing seams and transverse joints of supply, return and exhaust ducts and seams around plenums, fan and coil housings shall be sealed with sealant and taped.

FIELD QUALITY CONTROL.--

Pre-test requirements.--Before starting or operating systems, equipment shall be cleaned and checked for proper installation, lubrication and servicing.

In each system, at least one air path, from fan to final outlet, shall have all balance dampers open. The final air quantities shall be achieved by adjusting the volume dampers or the fan RPM.

Final adjustments and balancing of the systems shall be performed in such a manner that the systems will operate as specified and as shown on the plans.

The Contractor shall replace or revise any equipment, systems or work found deficient during tests.

All automatic operating devices which are pertinent to the adjustment of the aforementioned air systems shall be set and adjusted to deliver the required quantities of air and at temperatures specified by the Engineer. All control work shall be done in collaboration with the control manufacturer's representative.

Project completion tests.--The Engineer shall be notified at least 3 working days in advance of starting project completion tests.

The project completion tests shall consist of the following:

1. **Air Systems.--**All air systems shall be tested and balanced to the conditions set forth on the plans and in these special provisions. This work shall be performed by an Associated Air Balance Council (AABC) or National Environmental Balancing Bureau (NEBB) certified contractor. The air systems include, but are not necessarily limited to, the following:

- a. Supply air systems
- b. Exhaust air systems

2. **Operational Data.--**The tests shall include operation of the heating, cooling, and ventilating systems for not less than two 8-hour days, each system shall operate at not less than 90 percent of their full specified capacities.

The required data shall be accurately measured. The data shall be measured during one operational cycle in the presence of the Engineer and shall be submitted for approval.

The following data shall be measured and tabulated:

- a. Ambient temperatures and conditions, °C
- b. Supply and return air quantities, m³/sec, each room
- c. Thermostat set point, °C
- d. Air temperatures at room center, °C
- e. Fan motor amperages and voltages
- f. System static pressures, Pa

SECTION 12-16. ELECTRICAL

12-16.01 ELECTRICAL WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing electrical work in accordance with the details shown on the plans and these special provisions.

Electrical work shall include furnishing all labor, materials, equipment and services required to construct and install the complete electrical system shown on the plans and the work of installing electrical connections for the thermostats, motors, and controls specified elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of conduits and other facilities and location of equipment is to be governed by structural conditions and other obstructions, and shall be coordinated with the work of other trades. Equipment requiring maintenance and inspection shall be located where it is readily accessible for the performance of such maintenance and inspection.

Related work.--Earthwork, foundations, sheet metal, painting, mechanical and such other work incidental to and necessary for the proper installation and operation of the electrical work shall be done in accordance with the requirements specified for similar work elsewhere in these special provisions.

QUALITY ASSURANCE.--

Codes and standards.--All work performed and materials installed shall be in accordance with the National Electrical Code; the California Building Standards Code, Title 24, Part 3, "California Electrical Code," and the California Code of Regulations, Title 8, Chapter 4, "Electrical Safety Orders," and all local ordinances.

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

TESTING.--

After the electrical system installation work has been completed, the electrical system shall be tested in the presence of the Engineer to demonstrate that the electrical system functions properly. The Contractor shall make necessary repairs, replacements, adjustments and retests at his expense.

12-16.02 BASIC MATERIALS AND METHODS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing conduits, conductors, fittings, and wiring devices in accordance with the details shown on the plans and these special provisions.

Conduits, conductors, fittings, and wiring devices shall include those accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the electrical system.

Related work.--Roof penetrations shall be flashed and sealed watertight conforming to the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

Where conduits pass through fire rated wall, floor or ceiling assemblies, the penetrations shall be protected in accordance with the requirements specified under "Through-Penetration Firestopping" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for recessed junction and pull boxes, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

CONDUITS AND FITTINGS.--

Rigid steel conduit and fittings.--

Rigid steel conduit shall be threaded, full weight rigid steel, hot-dip galvanized inside and outside with steel or malleable iron fittings. Fittings shall be threaded unless otherwise specified or shown on the plans.

Split or three-piece couplings shall be electroplated, malleable cast iron couplings.

Insulated grounding bushings shall be threaded malleable cast iron body with plastic insulated throat and steel, lay-in ground lug with compression screw.

Insulated metallic bushings shall be threaded malleable cast iron body with plastic insulated throat.

PVC coated rigid steel conduit and fittings.--

PVC coated rigid steel conduit and fittings shall meet the requirements of "Rigid steel conduit and fittings" and shall have an external PVC coating, 40 mil thick. PVC coating on conduit and fittings shall have no sags, blisters or other surface defects and shall be free of holes.

Electrical metallic tubing (EMT) and fittings.--

Electrical metallic tubing shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam with zinc coating outside and enamel or lacquer coating inside.

Couplings shall be electroplated, rain and concrete tight, gland compression type, steel body couplings with malleable iron nuts.

Connectors shall be electroplated, rain and concrete tight, gland compression type, steel body connectors with male hub, malleable iron nut and insulated plastic throat.

Flexible metallic conduit and fittings.--

Flexible metallic conduit shall be fabricated in continuous lengths from galvanized steel strip, spirally wound and formed to provide an interlocking design.

Fittings shall be electroplated screw-in type with malleable cast iron body and threaded male hub with insulated throat.

Liquid tight flexible metallic conduit and fittings.--

Liquid tight flexible metallic conduit shall be fabricated in continuous length from galvanized sheet steel, spirally wound and formed to provide an interlocking design with an extruded polyvinyl chloride cover.

Fittings shall be electroplated, malleable cast iron body, with cap nut, grounding ferrule, and connector body with insulated throat.

Rigid non-metallic conduit and fittings.--

Rigid non-metallic conduit shall be Schedule 40, high impact, nonconducting, self-extinguishing polyvinyl chloride (PVC) rigid non-metallic conduit for direct underground burial.

Couplings shall be PVC, socket type or thread on one end and socket type on the other end as required for the particular application.

Terminal adapters for adapting PVC conduit to boxes, threaded fittings, or metallic conduit system shall be PVC adapters with threads on one end and socket type on the other end.

CONDUCTORS.--

Conductors.--

Conductors shall be stranded copper wire.

Conductor insulation types unless otherwise shown or specified, shall be as follows:

1. Conductors across hinges of control panel enclosures shall be Type MTW.
2. Conductors shall be type XHHW in wet and outdoor locations.
3. Conductors shall be type THHN in dry locations.

Wire connections and devices.--

Wire connections and devices shall be pressure or compression type, except that connectors for No. 10 AWG and smaller conductors in dry locations may be preinsulated spring-pressure type.

ELECTRICAL BOXES.--

Outlet, device and junction boxes.--

Unless otherwise shown or specified, boxes shall be galvanized steel boxes with knock-outs and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 100 mm square by 40 mm deep, except that switch boxes for the installation of single switches and outlet boxes for flush-mounted light fixtures shall be 50 mm by 75 mm by 40 mm deep.

Multiple switches shall be installed in standard gang boxes, unless otherwise specified or shown on the plans.

Cast metal boxes shall be cast iron boxes with threaded hubs and shall be of the size and configuration best suited to the application shown on the plans.

Flush-mounted boxes shall have stainless steel covers, one mm thick. Cover screws shall be metal with finish to match cover finish.

Unless otherwise shown or specified, surface-mounted boxes shall have galvanized steel covers with metal screws.

Weatherproof junction boxes shall have cast metal covers with gaskets.

Weatherproof switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles. Weatherproof receptacle boxes shall maintain their weatherproof rating when a cord and plug are connected.

Unless otherwise shown or specified, all PVC boxes shall be PVC boxes with hubs or equivalent means for conduit entry and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 100 mm square by 40 mm deep, except that switch boxes for the installation of single switches and outlet boxes for light fixtures shall be 50 mm by 75 mm by 40 mm deep.

All PVC junction boxes shall have PVC covers with gaskets.

All PVC switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles.

Sectional device plates will not be permitted.

Underground pull boxes.--

Pull boxes shall be high density reinforced concrete box with ultraviolet inhibitor polyethylene etched face anchored in concrete and fiberglass cover with hold down bolts. The polyethylene and fiberglass material shall be fire resistant and show no appreciable change in physical properties with exposure to the weather. No. 3 1/2 pull box shall be Brooks Products, No 3 1/2; Christy Concrete Products, N9; or equal. No. 5 pull box shall be Brooks Products No. 5; Christy Concrete Products, N30; or equal. No. 6 pull box shall be Brooks Products, No 66; Christy Concrete Products, B1730; or equal. Traffic rated pull boxes shall be high density reinforced concrete box with steel cover with hold down bolts and bonding strap. Pull box and cover shall be designed for H20 loading. No. 3 1/2 pull box shall be 250 mm by 430 mm, No. 5 pull box shall be 320 mm by 610 mm, and No. 6 pull box shall be 430 mm by 760 mm.

RECEPTACLES AND SWITCHES.--

Ground fault circuit interrupter receptacles, (GFCI)--

Ground fault circuit interrupter receptacles shall be NEMA Type 5-20R, feed-through type, ivory color, 3-wire, 20-ampere, 125-volt AC, grounding type, specification grade, duplex receptacle with ground fault interruption. Receptacle shall detect and trip at current leakage of 5 milliamperes and shall have front mounted test and reset buttons.

Duplex receptacles.--

Duplex receptacles shall be NEMA Type 5-20R, 3-wire, 20-ampere, 125-volt AC, safety grounding, ivory color, specification grade receptacle suitable for wiring with stranded conductors.

Mobile vehicle lift receptacle.--

Mobile vehicle lift receptacle shall be surface mounted, 600 volt, 60-ampere, 3-wire, 4-pole circuit breaking, weather resistant, raintight, receptacle with female interior assembly. The receptacle shall be complete with back box, angle adapter and spring door. The receptacle shall be grounded through extra pole and shell, and shall have crimp or solder type connections. A mating plug for the receptacle shall be provided and connected to the mobile vehicle lift power cable.

Standby generator receptacle.--

Standby generator receptacle shall be surface-mounted, 600-volt, 100 ampere, 4-wire, 4-pole, circuit breaking, weather resistant, raintight, receptacle with female interior assembly. The receptacle shall be complete with back box, angle adaptor and spring door. The receptacle shall be grounded through extra pole and shell, and shall have crimp or solder type connections. A mating plug for the receptacle shall be provided.

Welding receptacles.--

Welding receptacles shall be surface-mounted, 600-volt, 100-ampere, 3-wire, 4-pole, circuit breaking, weather resistant, raintight receptacle with female interior assembly. The receptacle shall be complete with back box, angle adapter and spring door. The receptacle shall be grounded through extra pole and shell, and shall have crimp or solder type connections. A mating plug for the receptacle shall be provided.

Snap switches.--

Snap switches shall be 20-ampere, 120/277-volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

Three-way toggle switches.--

Three-way toggle switches shall be 20-ampere, 120/277-volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

MISCELLANEOUS MATERIALS.--

Warning Tape.--

Warning tape shall be 100 mm wide and contain the printed warning "CAUTION ELECTRICAL CONDUIT" in bold 19 mm black letters at 760 mm intervals on bright orange or yellow background. The printed warning shall be non-erasable when submerged under water and resistant to insects, acids, alkali, and other corrosive elements in the soil. The tape shall have a tensile strength of not less than 70 kg per 100 mm wide strip and shall have a minimum elongation of 700 percent before breaking.

Pull ropes.--

Pull ropes shall be nylon or polypropylene with a minimum tensile strength of 225 kg.

Watertight conduit plugs.--

Watertight conduit plugs shall be a hollow or solid stem expansion plugs complete with inner and outer white polypropylene compression plates and red thermoplastic rubber seal. Seal material shall be non-stick type rubber resistant to oils, salt, and alkaline substances normally available at the construction sites.

Anchorage devices.--

Anchorage devices shall be corrosion resistant, toggle bolts, wood screws, bolts, machine screws, studs, expansion shields, and expansion anchors and inserts.

Electrical supporting devices.--

Electrical supporting devices shall be one hole conduit clamps with clamp backs, hot-dipped galvanized, malleable cast iron.

Construction channel shall be 41 mm x 41 mm, 2.66 mm (12-gage) galvanized steel channel with 13 mm diameter bolt holes, 40 mm on center in the base of the channel.

Ground rod(s).--

Ground rod(s) shall be a 19 mm (minimum) galvanized or copper clad steel rod, 3 meters long.

Telephone outlet boxes.--

Telephone outlet boxes shall be 102 mm square boxes and plates with modular type telephone outlet. Boxes on stud walls shall have plaster ring.

Plates for flush mounting outlets in finished room shall be Type 430 stainless steel, 1 mm thick with satin finish.

PART 3.- EXECUTION**INSTALLATION.--**

Conduit, general.--Rigid steel conduit shall be used unless otherwise shown on the plans or specified in these special provisions.

PVC coated rigid steel conduit shall be used at the locations shown on the plans for the Salt Storage Building.

Electrical metallic tubing may be used in furred spaces and for exposed work indoors above the switch height.

Unless otherwise specified or shown on the plans, flexible metal conduit shall be used to connect suspended lighting fixtures, motors, HVAC equipment, and other equipment subject to vibration in dry locations.

Unless otherwise specified or shown on the plans, liquid-tight flexible metal conduit shall be used to connect motors, HVAC equipment, and other equipment subject to vibration in wet locations.

Rigid non-metallic conduit shall be used at the locations shown on the plans for direct underground burial outside the building foundation.

Conduit installation.--Conduit trade sizes are shown on the plans. No deviation from the conduit size shown on the plans will be permitted without written permission from the Engineer.

Conduit shall be concealed unless otherwise shown on the plans.

Conduits shall be tightly covered and well protected during construction using metallic bushings and bushing "pennies" to seal open ends.

Rigid non-metallic conduit bends of 30 degrees or greater shall be factory-made long radius sweeps. Bends less than 30 degrees shall be made using an approved heat box.

A pull rope shall be installed in all empty conduits. At least one meter of pull rope shall be doubled back into the conduit at each termination.

Locations of conduit runs shall be planned in advance of the installation and coordinated with the ductwork, plumbing, ceiling and wall construction in the same areas and shall not unnecessarily cross other conduits or pipe, nor prevent removal of ceiling tiles or panels, nor block access to mechanical or electrical equipment.

Where practical, conduits shall be installed in groups in parallel, vertical or horizontal runs and at elevations that avoid unnecessary offsets.

Exposed conduit shall be installed parallel and at right angles to the building lines.

Conduits shall not be placed closer than 300 mm from a parallel hot water or steam pipe or 75 mm from such lines crossing perpendicular to the runs.

All raceway systems shall be secured to the building structures using specified fasteners, clamps and hangers.

Single conduit runs shall be supported by using one hole pipe clamps. Where run horizontally on walls in damp or wet locations, conduit shall be installed with "clamp backs" to space conduit off the surface.

Multiple conduit runs shall be supported with construction channel secured to the building structure. Conduits shall be fastened to construction channel with channel compatible pipe clamps.

Raceways of different types shall be joined using approved couplings or transition fittings.

Expansion couplings shall be installed where conduit crosses a building separation or expansion joint.

All floor and wall penetrations shall be sealed water-tight.

Existing underground conduit to be incorporated into a new system shall be cleaned with a mandrel or cylindrical wire brush and blown out with compressed air.

Conduit terminations.--Rigid steel conduits shall be securely fastened to cabinets, boxes and gutters using 2 locknuts and specified insulating metallic bushing. Electrical metallic tubing shall be securely fastened to cabinets, boxes and gutters using specified connectors. Conduit terminations at exposed weatherproof enclosures and cast outlet boxes shall be made watertight using specified hubs.

Grounding bushings with bonding jumpers shall be installed on all type of conduits terminating at concentric knockouts and on all conduits containing service conductors, grounding electrode conductor, and conductors feeding separate buildings.

Rigid non-metallic conduits shall be securely fastened to the non-metallic boxes and lighting fixtures using specified connectors.

Rigid non-metallic conduits shall be terminated inside the underground pull boxes with an approved conduit bushings or fittings. All conduits shall enter the pull box at an angle of 45 degrees or more.

All conduits terminated in underground pull boxes or exposed indoor and outdoor shall be provided with watertight conduit plugs.

Warning Tape.--Warning tape shall be placed over each conduit in a trench. Each warning tape shall be centered over the conduit and shall be placed over the 150 mm layer of sand covering the conduit as described elsewhere in these special provisions.

Conductor installation.--Conductors shall not be installed in conduit until all work of any nature that may cause injury is completed. Care shall be taken in pulling conductors that insulation is not damaged. An approved non-petroleum base and insulating type pulling compound shall be used as needed.

All cables shall be installed and tested in accordance with manufacturer's recommendations.

Splices and joints shall be insulated with insulation equivalent to that of the conductor.

Provide 155 mm of slack at each outlet and device connection. If the outlet or device is not at the end of a run of wire, connection shall be made with correctly colored pigtails tapped to the runs with splices as specified herein.

Branch circuit conductors in panelboards and load centers shall be neatly trained along a path from the breaker terminals to their exit point. The conductors shall have ample length to transverse the path without strain, but shall not be so long as to require coiling, doubling back, or cramming. The path shall transverse the panelboard gutter spaces without entering a gutter containing service conductors and, unless otherwise shown on the plans, without entering the gutter space of any panelboard feeder.

All pressure type connectors and lugs shall be retightened after the initial set.

Splices in underground pull boxes and similar locations shall be made watertight.

Junction boxes in furred or accessible ceiling spaces shall be identified with felt-tip pen denoting the circuits contained in the box.

Conductor identification.--The neutral and equipment grounding conductors shall be identified as follows:

Neutral conductor shall have a white or natural gray insulation except that conductors No. 4 and larger may be identified by distinctive white marker such as paint or white tape at each termination.

Equipment grounding conductor shall be bare or insulated. If insulated, equipment grounding conductors shall have green or green with one or more yellow stripes insulation over its entire length except that conductors No. 4 and larger may be permanently identified by distinctive green markers such as paint or green tape over its entire exposed insulation.

Feeder and branch circuit ungrounded conductors shall be color coded by continuously colored insulation, except conductors No. 6 AWG or larger may be color coded by colored tape at each connection and where accessible. Ungrounded conductor color coding shall be as follows:

120/240V-Single phase	Black, blue
120/240V-Three phase	Black, orange, blue

Where more than one branch circuit enters or leaves a conduit, panel, gutter, or junction box, each conductor shall be identified by its panelboard and circuit number. All control conductors including control conductors of manufacturer supplied and field wired control devices shall be identified at each termination with the wire numbers shown on the plans, approved working drawings, and as directed by the Engineer where deemed necessary. Identification shall be made with one of the following:

1. Adhesive backed paper or cloth wrap-around markers with clear, heat shrinkable tubing sealed over either type of marker.
2. Self-laminating wrap around type, printable, transparent, permanent heat bonding type thermoplastic film markers.
3. Pre-printed, white, heat-shrinkable tubing.

Each terminal block shall have a molded marking strip attached with screws. The identifying numbers of the terminating conductors, as shown on the plans or on the submittal drawings, shall be engraved in the marking strip.

Outlet, device and junction box installation.--Where one or more threaded steel conduits are required to connect to an outlet, device, or junction box, the box shall be a cast metal box with threaded hubs. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall be sheet steel boxes. Weatherproof outlet, device and junction boxes shall have cast metal covers with gaskets. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall have standard galvanized covers.

All boxes shall finish flush with building walls, ceiling and floors except where exposed work is called for.

Raised device covers (plaster rings) shall be installed on all boxes concealed in concrete, masonry or stud walls.

No unused openings shall be left in any box. Knockout seals shall be installed as required to close openings.

Outlet, device, and junction boxes shall be installed at the locations and elevations shown on the plans or specified herein. Adjustments to locations may be made as required by structural conditions and to suit coordination requirements of other trades.

Boxes in stud walls and partitions shall not be mounted back to back. Through-wall boxes shall not be used.

Boxes installed in metal stud walls shall be equipped with brackets designed for attaching directly to the studs or shall be mounted on heavy gauge galvanized steel, snap-in box supports.

Fixture outlet boxes installed in suspended ceilings of gypsum board or lath and plaster construction shall be mounted on 1.52 mm (16-gage) metal channel bars attached to main ceiling runners.

Fixture outlet boxes for pendant-mounted fixtures installed in suspended ceilings supporting acoustical tiles or panels shall be supported directly from the structures above.

Underground pull box installation.--Electrical pull box covers or lids shall be marked "ELECTRICAL." Telephone service pull box covers or lids shall have plain, unmarked covers.

The bottom of pull boxes shall be bedded in 155 mm of clean, crushed rock or gravel and shall be grouted with 40 mm thick grout prior to installation of conductors. Grout shall be sloped to a 25 mm PVC pipe drain hole. Conduit shall be sealed in place with grout.

Top of pull boxes shall be flush with surrounding grade or top of curb. In unpaved areas where pull box is not immediately adjacent to and protected by a concrete foundation, pole or other protective construction, the top of pull box shall be set at plus 30 mm above surrounding grade. Pull boxes shown on the plans in the vicinity of curbs shall be placed adjacent to the back of curb. Pull boxes shown on the plans adjacent to lighting standards shall be placed on the side of foundation facing away from traffic.

Ground rod(s) installation.--The ground rod(s) shall be driven vertically until the top is 155 mm above the surrounding surface. When vertical penetration of the ground rod cannot be obtained, an equivalent horizontal grounding system, approved by the Engineer, shall be installed.

Anchorage.--Hangers, brackets, conduit straps, supports, and electrical equipment shall be rigidly and securely fastened to surfaces by means of toggle bolts on hollow masonry; expansion shields and machine screws, or expansion anchors and studs or standard preset inserts on concrete or solid masonry; machine screws or bolts on metal surfaces; and wood or lag screws on wood construction.

Anchorage devices shall be installed in accordance with the anchorage manufacturer's recommendations.

Mounting heights.--Electrical system components shall be mounted at the following mounting heights, unless otherwise shown on the plans. The mounting height dimensions shall be measured above the finished floor to the bottom of the device or component.

Thermostats	1.0 m maximum, office areas 1.25 m maximum, hallways
Wall switches	1.0 m maximum
Convenience outlets	510 mm minimum, office areas 1.25 m minimum, all other areas
Electric water cooler outlet	As recommended by the water cooler manufacturer.
Telephone and radio outlets	510 mm minimum

12-16.03 SERVICE AND DISTRIBUTION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing service and distribution equipment in accordance with the requirements of the serving utilities, the details shown on the plans and these special provisions.

Attention is directed to "Utility Connection" in Section 12-1, "General Requirements," of these special provisions regarding arrangements, permits, licenses, charges, fees and costs for utility connections and extensions.

Related work.--Concrete and reinforcement for service pedestal shall conform to the requirements specified for minor work under "Cast-in-Place Concrete," in Section 12-3, "Concrete and Reinforcement," of these special provisions.

SUBMITTALS.--

Installation details.--The Contractor shall submit complete service installation details to the serving utilities for approval. Prior to submitting installation details to the serving utility, the Contractor shall have said drawings reviewed and stamped "APPROVED" by the Engineer. Submittals shall be approved by the serving utility prior to commencing work.

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

Main Switchboard No.1.--

Main switchboard No.1--shall contain a pull section, metering CT compartment remote meter enclosure, service disconnect switch and distribution circuit breakers for 120/240-volt, 800-ampere, 3-phase, 4-wire service.

Enclosure.--

Enclosure shall be NEMA 12 enclosure. Exterior shall be 2.66 mm (12-gage) and interior shall be 1.90 mm (14-gage) sheet steel. All screws, latches, hinge pins and similar hardware shall be stainless steel. Circuit breaker shall be operable with the door closed. Enclosure finish shall be baked enamel or baked thermosetting polyester finish.

Remote meter enclosure.--

Remote meter enclosure shall be rated as shown on the plans and as required by the serving utility and shall be suitable for outdoor installation. Remote meter enclosure shall include a meter base meeting the requirements of the serving utility. Include provisions for sealing the enclosure to meet the serving utilities requirements.

Service disconnect switch.--

Service disconnect switch shall be 3-pole, 240-volt, 800-ampere frame, 800-ampere trip, molded case circuit breaker with AC magnetic trip adjusted to 800 amperes. The interrupting capacity of the circuit breaker shall be 42,000 amperes (symmetrical) at 240-volt. Breaker shall be Westinghouse; Square D; General Electric; or equal.

Distribution circuit breakers.--

Distribution circuit breakers shall be of the indicating type providing ON, Tripped and OFF positions of the operating handle. Circuit breakers shall be quick-make, quick-break, with thermal-magnetic action. An overload of one pole of all multiple-pole circuit breakers shall automatically cause all poles to open. Circuit breakers shall meet the requirements of UL and NEMA AB 1. Unless noted otherwise, interrupting rating shall not be less than 42,000 amps rms symmetrical at the rated voltage. Breakers shall be sized as shown on the plans and shall be manufactured by Westinghouse, Square D, General Electric, or equal.

Concrete.--

Concrete for service pedestal shall be commercial quality concrete, proportioned to provide a workable mix for the intended use; shall contain not less than 285 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Foundation for service pedestal shall be as shown on the plans.

Installation of service and distribution equipment shall be in accordance with the requirements of the serving utilities as shown on the approved installation details.

12-16.04 ELECTRICAL EQUIPMENT**PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of furnishing and installing trailer hookups, panelboards, starters, disconnect switches, transformers, and related accessories in accordance with the details shown on the plans and these special provisions.

Related work.--Anchorage devices shall be as specified under "Basic Materials and Methods" elsewhere in this Section 12-16.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS**TRAILER HOOKUPS.--****Trailer hookups.--**

Trailer hookups No. 1 and No. 2 shall be meter pedestals suitable for use outdoors, factory assembled, 1-phase, 3-wire, 120/240-volt, AC pedestals with a 200 amp main circuit breaker. Meter pedestal bases shall be configured such that the meter height above grade is 914 mm, shall be suitable for underground conduit entry with insulated groundable neutral and hinged door. Meter pedestal shall have a blank meter face and telephone terminal mounting bracket. Meter pedestal shall be Square D Company, Hitch-N-Post series; Westinghouse, WMB series; or equal.

PANELBOARDS.--**Panelboard EP.--**

Panelboard EP shall be indoor type, surface-mounted, bottom feed, factory assembled, 3-phase, 4-wire, 120/240-volt, AC panelboard at least 508 mm wide with 350-ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panel shall be Square D Company; Westinghouse; General Electric; or equal.

Panelboard EL.--

Panelboard EL shall be indoor type, surface-mounted, bottom feed, factory assembled, 3-phase, 4-wire, 120/240-volt, AC panelboard at least 508 mm wide with 200-ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panels shall be Square D Company; Westinghouse; General Electric; or equal.

Panelboard EC.--

Panelboard EC shall be indoor type, surface-mounted, bottom feed, factory assembled, 1-phase, 3-wire, 120/240-volt, AC panelboard at least 508 mm wide with 70-ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panels shall be Square D Company; Westinghouse; General Electric; or equal.

Panelboard N.--

Panelboard N shall be indoor type, surface-mounted, bottom feed, factory assembled, 1-phase, 3-wire, 120/240-volt, AC panelboard, suitable for use as service entrance equipment, at least 508 mm wide with 60-ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panels shall be Square D Company; Westinghouse; General Electric; or equal.

Panelboard L.--

Panelboard L shall be outdoor type, rated NEMA 3R, surface-mounted, bottom feed, factory assembled, 3-phase, 4-wire, 120/240-volt, AC panelboard, suitable for use as service entrance equipment, at least 508 mm wide with 200-ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panels shall be Square D Company; Westinghouse; General Electric; or equal.

STARTERS.--**Air compressor combination starter.--**

Air compressor combination starter shall be 3-pole, 240-volt, NEMA Size 1, NEMA rated, line voltage starter and 30 amp, 3-pole motor circuit protector in a NEMA-1 enclosure. Air compressor combination starter shall have two, dual element, 250-volt fuses with 2-pole barrier type fuse base; 240-volt coil, double-break silver contacts and 3 manual reset, non-adjustable thermal overloads, set to trip between 115 and 125 percent of full load motor current, as quoted on the nameplate by the motor manufacturer. Reset button shall be externally operable.

Declassification fan controller .--

Declassification fan controller shall be a NEMA 1 surface mounted enclosure with a hinged door and complete with 15 amp, 3-pole main circuit breaker, fan starters (ST1 and ST2), pushbutton, and terminal blocks mounted inside the enclosure. The "Start-Stop" pushbutton shall be externally operable, and the pilot light shall be externally visible.

Declassification fan motor starters, ST1 and ST2, shall be 3-pole, 240-volt, NEMA size 00, NEMA rated line voltage starters, 120-volt coil and one auxiliary contact complete with manual reset, non-adjustable thermal overloads, set to trip between 115 and 125 percent of full load motor current, as quoted on the nameplate by the motor manufacturer.

Fume exhaust fan controller .--

Fume exhaust fan controller shall be a NEMA 1 surface mounted enclosure with a hinged door and complete with 20-amp, 1-pole main circuit breaker, fan starters (ST3 and ST4), pushbutton, and terminal blocks mounted inside the enclosure. The "Start-Stop" pushbutton shall be externally operable, and the pilot light shall be externally visible.

Exhaust fan motor starters, ST3 and ST4, shall be 1-pole, 120-volt, NEMA size 00, NEMA rated line voltage starters, 120-volt coil and one auxiliary contact.

Evaporative cooler controller.—

Evaporative cooler controller shall be combination 2-speed, 3-pole, 240-volt, NEMA Size 1, NEMA rated, line voltage starter and circuit breaker in a NEMA-1 enclosure. Circuit breaker shall be sized per manufacturer's recommendations. Evaporative cooler controller shall have one, dual element, 250-volt fuse with barrier type fuse base; 120-volt coils, double-break silver contacts and 3 manual reset, non-adjustable thermal overloads for each speed, set to trip between 115 and 125 percent of full load motor current, as quoted on the nameplate by the motor manufacturer. Reset button shall be externally operable. Starter shall be lockable in the OFF position.

Manual motor starters.--

Manual motor starters shall be rated for the intended use, except rating shall be 1 horsepower minimum. They shall provide thermal overload protection in all ungrounded phases, and shall have provisions for locking in the OFF position. Manual motor starter enclosure shall be rated NEMA 4. Manual starters shall meet the requirements of NEMA ICS and shall be as manufactured by Cutler-Hammer, Square D, or equal.

SWITCHES.--**Pushbuttons, selector switches and pilot lights.--**

Pushbuttons, selector switches and pilot lights shall be heavy-duty oil-tight, and manufactured to the requirements of NEMA ICS. Provide suitable NEMA rated enclosures or mount in panels as indicated.

Unless noted otherwise, provide extra-large, integral, metal service legends (legend plates) indicating their specific functions, and laminated phenolic nameplates indicating the equipment they control.

Unless noted otherwise, pushbuttons shall be momentary contact and shall have the number and type of contacts as indicated or as required.

Unless noted otherwise, selector switches shall be maintained contact, shall have the number of positions indicated and shall have the number and type of contacts as indicated or as required,

Pilot light shall be panel mounted, heavy duty, oil tight indicating light with 120-volt, AC, LED lamp with red domed cap.

Pushbuttons, selector switches and pilot lights shall be Square D, Allen-Bradley, Westinghouse, General Electric, or equal.

Door operator disconnect switch.--

Door operator disconnect switch shall be 2-pole, 240-volt, AC, 30-ampere, non-fusible, general duty safety switch in a NEMA-1 enclosure with provision for padlocking in the "OFF" position.

Power transfer switch.--

Power transfer switch shall be a manually operated, 240-volt, 400-amp, 3-phase, 3-pole, double throw switch. Contacts shall be break-before-make when the switch is operated in either direction. The manual transfer switch shall be mounted in a NEMA 3R gasketed enclosure with hinged door. The unit shall be suitable for wall mounting. All connections and components shall be readily accessible from the front of the cabinet. Power transfer switch shall be UL listed. Power transfer switch shall be as manufactured by Kohler, Onan or equal.

MISCELLANEOUS MATERIALS.--**Nameplates.--**

Nameplates shall be laminated phenolic plastic with white core and black front and back. Nameplate inscription shall be in capitals letters etched through the outer layer of the nameplate material.

Warning plates.--

Warning plates shall be laminated phenolic plastic with white core and red front and back. Warning plates inscription shall be in capitals letters etched through the outer layer of the nameplate material.

Plywood backing panels.--

Plywood backing panels for mounting electrical or telephone equipment shall be 19 mm, APA plywood panels, C-D PLUGGED and touch-sanded, Exposure 1.

Paint.--

Plywood backing panels shall receive the following paint system: one prime coat, alkyd, interior wood primer and 2 finish coats, acrylic, interior enamel, semi-gloss.

PART 3.- EXECUTION

INSTALLATION.--

Plywood backing board.--Plywood backing board shall be securely fastened to walls or other vertical framing. Surface to be coated shall be cleaned of all dirt, excess materials, of filler by hand cleaning.

Coatings shall be applied in accordance with the manufacturer's instructions. Each coat shall be applied to a uniform finish, free of skips, brush marks, laps or other imperfections.

Existing panelboards.--Provide new circuit breakers, where required to match existing type unless otherwise shown on the plans. Provide mounting hardware, bus straps, and related materials for proper circuit breaker installation. Provide new panelboard identification nameplate with designation as shown for each panelboard. Remove existing nameplates where applicable. Provide new typewritten circuit directory reflecting changes made under the Contract.

Panelboard installation.--Set cabinets plumb and symmetrical with building lines. Train interior wiring as specified under "Conductor and Cable Installation" in "Basic Materials and Methods" of these special provisions. Touch-up paint any marks, blemishes, or other finish damage suffered during installation. Replace cabinets, doors or trim exhibiting dents, bends, warps or poor fit which may impede ready access, security or integrity.

Mounting height shall be 1.4 meters to the highest circuit breaker handle, measured above the finished floor.

Where "Future" or "Space" is indicated on the plans, branch connectors, mounting brackets, and other hardware shall be furnished and installed for future breaker.

A typewritten directory under transparent protective cover shall be provided and set in metal frame inside each cabinet door. Directory panel designation for each circuit breaker shall include complete information concerning equipment controlled, including room number or area designated on the plans.

Equipment identification.--Equipment shall be identified with nameplates fastened with self-tapping, cadmium-plated screws or nickel-plated bolts.

Nameplate inscriptions shall read as follows:

Item	Letter height, mm	Inscription
Bridge Crane Disconnect	6	BRIDGE CRANE DISCONNECT
Main Switchboard No. 1	6	MAIN SWITCHBOARD NO. 1 120/240 VOLTS, 3 , 4 WIRE
Panel EP	6	PANEL EP 120/240 VOLTS, 3 , 4 WIRE
Panel EL	6	PANEL EL 120/240 VOLTS, 3 , 4 WIRE
Panel EC	6	PANEL EC 120/240 VOLTS, 1 , 3 WIRE
Exterior Lighting Control Cabinet	6	EXTERIOR LIGHTING CONTROL CABINET
Welding Receptacle	6	WELDING RECEPTACLE
Mobile Vehicle Lift Receptacle	6	MOBILE VEHICLE LIFT RECEPTACLE
Evaporative Cooler Controller	6	EVAPORATIVE COOLER CONTROLLER
Fume Exhaust Fan Controllers	6	FUME EXHAUST FAN CONTROLLERS
Declassification Fan Controllers	6	DECLASSIFICATION FAN CONTROLLERS
Air Compressor Combination Starter	6	AIR COMPRESSOR COMBINATION STARTER
Panel N	6	PANEL N 120/240 VOLTS, 1 , 3 WIRE
Exterior Lighting Control Cabinet	6	EXTERIOR LIGHTING CONTROL CABINET
Panel L	6	PANEL L 120/240 VOLTS, 3 , 4 WIRE
De-icing Tank Motor Starter	6	DE-ICING TANK MOTOR STARTER
Power Transfer Switch	6	POWER TRANSFER SWITCH

Warning plates.--Warning plates shall be attached to designated equipment with self-tapping cadmium-plated screws or nickel-plated bolts.

12-16.05 LIGHTING

GENERAL.--This work shall consist of furnishing, installing and connecting all lighting equipment in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive information, photometric curves, catalog cuts, and installation instructions shall be submitted for approval.

PRODUCTS.--

Lighting fixture lamps.--

Lighting fixture lamps shall be type and size as shown on the plans. Lamps shall be General Electric, Phillips, Sylvania, or equal. Fluorescent lamps, unless otherwise noted, shall be 4100K tri-phosphor with a CRI of 70 or greater.

Ballasts.--

All fluorescent fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by the fixture. Fluorescent ballasts shall be UL Listed, Class P and ETL Certified ballasts. All ballasts except 800-milliamper ballasts shall have sound rating A. Fluorescent ballasts except for 800-milliamper ballasts shall be high-frequency electronic ballasts with power factor greater than 0.95, ballast factor at least 0.87, total harmonic distortion less than 10 percent, crest factor less than or equal to 1.6, complying with ANSI C 62.41 Category A for surge protection, and FCC Part 18 for interference.

Lighting fixtures.--

Lighting fixtures shall be as shown on the plans and as specified herein. Outdoor luminaires shall be listed and labeled "Fixture Suitable For Wet Locations."

F1.--

Ceiling-mounted fluorescent fixture with one lamp, electronic ballast, and one-piece, clear acrylic, wrap-around diffuser. The fixture shall be Day Brite, HW series; Columbia Lighting, Prestige series; Lithonia, CB series; or equal.

F2.--

Pendant-mounted fluorescent fixture with one lamp, electronic ballast, baked enamel ribbed reflector, complete with end plates and wire-guard. The fixture shall be Day Brite, Silverado series; Columbia Lighting, CH series; Lithonia, AF series; or equal.

F3.--

Pendant-mounted fluorescent fixture with two lamps, 800 MA ballast and baked enamel ribbed reflector, complete with end plates and wire-guard. The fixture shall be Columbia Lighting, CSR series; Lithonia, AF series; Day Brite, Silverado series; or equal.

F4.--

Ceiling-mounted fluorescent fixture with two lamps, electronic ballast, and one-piece, clear acrylic, wrap-around diffuser. The fixture shall be Day Brite, HW series; Columbia Lighting, Prestige series; Lithonia, CB series; or equal.

F5.--

Pendant-mounted fluorescent fixture suitable for installation in damp locations with one lamp, cold weather ballast and prismatic acrylic diffuser. The fixture shall be Lithonia, DMS series; Day-Brite, Cascade series; or equal.

H1.--

Outdoor, wall mounted, 70-watt, 120-volt high pressure sodium luminaire with integral ballast. The fixture shall have a heavy duty, die cast aluminum housing with gasketed, clear, prismatic lens and vandal shield. The fixture shall be Day-Brite, WLM series; Holophane, Wallpak series; Lithonia, TWH series; or equal.

H2.--

Outdoor, wall mounted, 400-watt, 120-volt high pressure sodium luminaire with integral ballast. The fixture shall have a heavy duty, die cast aluminum housing with gasketed, clear, prismatic lens and vandal shield. The fixture shall be Day-Brite, WLL series; Lithonia, TWH series; or equal.

H3.--

Outdoor, wall mounted, 250-watt, 120-volt high pressure sodium luminaire with integral ballast. The fixture shall be Day-Brite, WLL series; Lithonia, TWH series; or equal.

Light timer switch.--

Light timer switch shall be a mechanically spring wound interval timer switch suitable for mounting in an outdoor location. The switch shall have normally open SPST contacts rated for 20-amps at 120-volts, 60 Hz. The contacts shall be close when the timer is activated. The light timer switch shall have a range of 0-2 hours and shall be adjustable in 15 minute increments. Light timer switch shall be Tork, 500 series; Intermatic, FF6 series; or equal.

Photoelectric unit, PEC.--

Photoelectric unit shall be a photoelectric control suitable for mounting in an outdoor location. The unit shall have a photocell shield to allow adjustment for light level variations and shall have a built-in delay to prevent false cycling. Photoelectric unit shall be as manufactured by Intermatic, Dayton, or equal.

Exterior lighting control cabinet.--

Exterior lighting control cabinet shall consist of a lighting contactor, selector switch and pilot light in a surface mounted enclosure with a lockable hinged door. Enclosure shall be NEMA 3R at the Salt Storage Building and NEMA 1 at all other locations.

Lighting contactor, LC.--

Lighting contactor shall be rated for HID loads, electrically held, 2-pole combination lighting contactor with 120-volt AC coil and 30-ampere, double-break, silver alloy contacts. Contactor shall be as manufactured by Square D Company, I.T.E., Westinghouse, or equal.

Selector switch, SS.--

Selector switch shall be rotary action, double-pole, 3-position, 10-ampere, 120-volt switch. Switch contacts shall have an inductive pilot duty rating of 60 amperes (make), 6 amperes (break) and 10 amperes (continuous) at 120 volts and 35 percent power factor. Selector switch shall have legend plate marked MANUAL-OFF-AUTO.

Pilot light, PL.--

Pilot light shall be panel mounted, heavy duty, oil tight indicating light with 120-volt, AC, LED lamp with red domed cap.

Terminal block, TB.--

Terminal block shall be 30-ampere, 300-volt, molded plastic with two or more mounting holes and two or more terminals in each cast block. The molded plastic shall have a high resistance to heat, moisture, mechanical shock, and electrical potential and shall have a smooth even finish. Each block shall have a molded marking strip attached with screws. Terminal blocks shall have tubular, high pressure clamp connectors.

Electroliner hardware.--

Provide hardware as required and shown on the plans for relocating the existing electroliner.

Concrete.--

Concrete shall be as specified under "Cast-In-Place Concrete" in Section 12-3, "Concrete and Reinforcement," of these special provisions. The concrete shall be commercial quality portland cement concrete containing not less than 337 kilograms of cement per cubic meter.

The following electrical components shall be mounted on the hinged door of the exterior lighting control cabinet:

Selector switch, SS
Indicating light

EXECUTION.--

LIGHTING FIXTURES.--Lighting fixtures shall be mounted securely in accordance with the manufacturer's recommendations. Mounting methods shall be suitable for the particular type of ceiling or support at each location.

The Contractor shall provide all supports, hangers, spacers, channels, fasteners and other hardware necessary to support the fixtures.

Fixtures shall be set at the mounting heights shown on the plans, except heights shown shall be adjusted to meet conditions.

BALLASTS.--All fluorescent fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by fixture.

All ballasts used in unheated areas inside the building or in areas outside of buildings shall be rated for an ambient temperature of -20°C or less.