

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.
Help save water!*

September 9, 2014

04-Ala-92-R5.1/R5.8

04-2G3624

Project ID 0413000221

HPLUL-6204(118)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN ALAMEDA COUNTY IN HAYWARD FROM 0.1 MILE WEST OF INDUSTRIAL BOULEVARD UNDERCROSSING TO HESPERIAN BOULEVARD OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, September 17, 2014.

This addendum is being issued to revise the *Notice to Bidders and Special Provisions*, the *Bid* book, and the Federal Minimum Wages with Modification Number 22 dated September 5, 2014.

In the Special Provisions, Section 8-1.04C, "DELAYED START," is added as attached.

In the Special Provisions, Section 20-2.06B, "MATERIALS," is added as attached.

In the Special Provisions, Section 86-2.18, "NUMBERING ELECTRICAL EQUIPMENT," is deleted.

In the Special Provisions, Section 13, "WATER POLLUTION CONTROL," the second revision clause, "Replace item 3 in the list in the second paragraph of Section 13-3.01B(2)(a) with:" is deleted.

Addendum No. 1
Page 2
September 9, 2014

04-Ala-92-R5.1/R5.8
04-2G3624
Project ID 0413000221
HPLUL-6204(118)E

In the *Bid* book, in the "Bid Item List," Items 64, 65, and 66 are added.

In the *Bid* book, in the "Bid Item List," Items 63 is deleted.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, attachments and the modified wage rates are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/04/04-2G3624

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



BIJAN SARTIPI
District Director

Attachments

Replace "Reserved" in section 8-1.04C with:

Section 8-1.04B does not apply.

Start job site activities within 55 days after receiving notice that the Contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department.

Do not start job site activities until the Department authorizes or accepts your submittal for WPCP or SWPPP, whichever applies.

You may enter the job site only to measure controlling field dimensions and locate utilities.

You may start job site activities before the 55th day after Contract approval if you:

1. Obtain specified authorization or acceptance for each submittal before the 55th day
2. Receive authorization to start

Submit a notice 72 hours before starting job site activities. If the project has more than 1 location of work, submit a separate notice for each location.

Add to section 20-2.06B of the RSS for section 20:

Flow sensor cable must be rated 600V and 194 degree F, be UL listed as Type TC, meet requirements of ICEA/NEMA, and comply with the following:

1. Consist of two no. 16 AWG minimum stranded copper conductors. Insulated conductor must be color coded with a PVC or nylon jacket.
2. Include a tinned cooper braid or aluminized polyester film shield. Where the film is used, a no. 18 (or larger stranded) or no. 16 (solid), tinned, copper drain wire to be placed between the insulated conductors and the shield and in contact with the conductive surface of the shield.
3. Include a black PVC jacket with a minimum nominal thickness of either 50 mils or 48 mils where capacitance of conductors to other conductors and the shield is 87 pF/ft or better. The cable jacket must be marked with the insulation type designation, conductor size, and voltage and temperature ratings.
4. Have an outside diameter of 0.29 to 0.35 inch.
5. Be UV resistant and direct burial type.
6. Have no splices between components except where shown.

**BID ITEM LIST
04-2G3624**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	860797	ELECTRIC SERVICE (IRRIGATION)	LS	LUMP SUM	LUMP SUM	
62	995100	WATER METER CHARGES	LS	LUMP SUM	LUMP SUM	
63	BLANK					
64	200052	PRUNE EXISTING PLANTS	LS	LUMP SUM	LUMP SUM	
65	150685	REMOVE IRRIGATION FACILITY	LS	LUMP SUM	LUMP SUM	
66	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID:

\$
