



D16+	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEETS
May 20, 2011 PLANS APPROVAL DATE THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.				




EXCAVATION IN TRENCH **BACKFILL IN TRENCH**



EXCAVATION IN EMBANKMENT **BACKFILL IN EMBANKMENT**

FILL HEIGHT GREATER THAN 2'-0"



EXCAVATION **METHOD 1** **METHOD 2** **METHOD 3** **EXCAVATION** **METHOD 1** **METHOD 2**

BACKFILL

FILL HEIGHT 2'-0" OR LESS

* 1'-0" Where Method 1 or 2 Backfill is used.
 2'-0" Where Method 3 Backfill is used.

- LEGEND:**
- STRUCTURE EXCAVATION (CULVERT)
 - STRUCTURE BACKFILL (CULVERT) 95% RELATIVE COMPACTION
 - ROADWAY EMBANKMENT
 - SLURRY CEMENT BACKFILL
 - SAND BEDDING (CULVERT)
 - ROADWAY PAVEMENT STRUCTURE
 - ORIGINAL GROUND
- NOTES:**
1. Slope or shore excavation sides as necessary.
 2. Dimensions shown are minimum.
 3. Method 2 and 3 for single or multiple boxes requires an approved external sealing band. See Standard Plan D83A.
 4. Construction of Roadway Pavement Structure in Method 2 or Method 3 shall not disturb the external sealing band installation.

STATE OF CALIFORNIA
 DEPARTMENT OF TRANSPORTATION

**EXCAVATION AND BACKFILL PRECAST
 REINFORCED CONCRETE BOX CULVERT**

NO SCALE

A62G

2010 STANDARD PLAN A62G